State of the Regional Water System



Services of the San Francisco Public Utilities Commission

December 2024

FINAL

List of Contributors:

Brian Barry Tracy Cael Joe Carlevaris Jason Chen Angela Cheung Jacquelyne Cho Eric Choi Amelia Clark Andrew DeGraca Anna Fedman Stacie Feng Josh Gale Jeffrey K Harp Whay Ne Ho Nancy Hom Margaret Hannaford Jowin Jung Chris Graham Ted Allen Annie Li Raymond Mah Nicholas Martin Adam Mazurkiewicz Katie Miller Ellen Natesan Tim Ramirez Scott Riley Enio Sebastiani Eddy So Dan Stewart Shailen Talati Raymond Tan

Mike Williams Alan Wong Derrick Wong Nicole Yturralde Anthony Yu Alan Lane Blake Rothfuss

Table of Contents

1. Intro	oduction and Overview	1
1.1	Purpose of Report	1
1.2	System Overview	1
1.3	Water Enterprise Management Structure	6
1.4	Organization of Report	6
2. Asse	et Management Policy and Capital Planning Process	8
2.1	Asset Management Policy	8
2.1.1	Water Enterprise's Implementation of the SFPUC Asset Management Policy	8
2.1.2	Level of Service History and Objectives	13
2.2	Capital Planning	19
2.2.1	Capital Planning Process Overview	
2.2.2	Capital Prioritization Process Overview	
2.2.3	Optimizing and Balancing the 10-Year Capital Improvement Plan	23
3. Asse	et Management Program Status	24
3.1	Asset Risk Management	24
3.2	Asset Management and Maintenance Roles and Responsibilities	
3.3	Asset Management Objectives	
3.4	Asset Registry	
3.5	Asset Condition	
3.6	Operations and Maintenance Strategies	
3.7	Asset Investment Strategies	
3.8	Budgeting	
3.9	Performance Monitoring	
3.10	Levels of Service	
4. Asse	et Description, Maintenance and Condition, and Capital Improvements	
4.1	Water Storage Assets	
4.1.1	Hetch Hetchy Water	
4.1.2		
4.2	Water Treatment Assets	
4.2.1	Hetch Hetchy Water	51
4.2.2		
4.3	Water Transmission Assets	
4.3.1		
4.3.2	2	

4.4 V	Water Distribution Assets	115
4.4.1	Hetch Hetchy Water	115
4.4.2	Regional Water	118
4.5 I	Buildings and Grounds	121
4.5.1	Hetch Hetchy Water	121
4.5.2	Regional Water	125
4.6 I	Power Generation Assets	130
4.6.1	Hetch Hetchy Water	130
4.7]	Power Transmission Assets	135
4.7.1	Hetch Hetchy Water	135
4.8 l	Power Distribution Assets	143
4.8.1	Hetch Hetchy Water	143
4.8.2	Regional Water	148
4.9 V	Watersheds, Roads, and Bridges	152
4.9.1	Hetch Hetchy Water	153
4.9.2	Regional Water	161
4.10 V	Wastewater Treatment Assets	166
4.10.1	Hetch Hetchy Water	166
4.11 (Communications and Control Assets	169
4.11.1	Hetch Hetchy Water Upcountry Communication Sites	169
4.11.2	Radio	169
4.11.3	Telephone	170
4.11.4	SCADA	170
4.11.5	On-Line Monitoring Program Review	171
4.11.6	Capital Improvements	171
5. Regul	latory Compliance	173
5.1 I	Federal and State Drinking Water Regulations	173
5.1.1	LCRR/LCRI	173
5.1.2	Total Coliform Rule	
5.1.3	Per- and Polyfluoroalkyl Substances	174
5.1.4	Unregulated Contaminant Monitoring Rule	175
5.1.5	Other Revisions	176
5.1.6	Drinking Water Permit Compliance	177
5.2	Environmental Compliance	177
5.2.1	National Pollutant Discharge Elimination System Permit Compliance	179
5.2.2	California Unified Program Compliance (Hazardous Waste and Materials)	179
5.3 5	State of California Division of Safety on Dams	183
5.3.1	Dam Safety Program	184

5.3.2	DSOD Inspections	
5.4	America's Water Infrastructure Act	
5.5	Federal and State Power Regulations	
5.5.1	North American Electric Reliability Corporation/Western Electrici	ty Coordinating
Cour	ncil	
5.5.2	Federal Energy Regulatory Commission	
5.5.3	Wildfire Mitigation Plan	
5.5.4	Physical Security Mitigation Plan	
6. Emer	ging Issues	
6.1	General	
6.1.1	Transitioning to a Cleaner Utility	
6.1.2	Obsolete Equipment/Technology	
6.1.3	U.S. EPA Cyber Security	
6.2	Water Quality	
6.2.1	Disinfection Byproducts	
6.2.2	Taste and Odor	
6.2.3	PFAS	
6.2.4	Microplastics	
6.2.5	Other Contaminants of Emerging Concern	
Appendi	x A: Asset Inventory Tables	
Appendi	x B: Emergency Response and Preparedness Plans	
Appendi	x C: Pipeline Inspection Schedule	
Appendi	x D: Watershed Map	

Tables

Table 1-1: Organization of SRWS Report	7
Table 2-1: Summary of SFPUC Asset Management Guiding Principles and Water	
Enterprise's Asset Management Objectives	9
Table 4-1: O'Shaughnessy Dam Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 35
Table 4-2: Cherry Valley Dam Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 36
Table 4-3: Lake Eleanor Dam Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 36
Table 4-4: Early Intake Dam Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 37
Table 4-5: Priest Dam Preventive Maintenance Summary (July 1, 2022, through June 30,	
2024)	. 38
Table 4-6: Moccasin Dam Preventive Maintenance Summary (July 1, 2022, through June 30,	
2024)	. 39
Table 4-7: O'Shaughnessy Dam Outlet Works Phase I Project Milestones Completed During	
the Current Reporting Cycle	. 40
Table 4-8: O'Shaughnessy Dam Fall Protection Improvements and Spillway Access Project	
Milestones Completed During the Current Reporting Cycle	40
Table 4-9: Cherry Dam Spillway - Short-Term Improvements Project Milestones Completed	
During the Current Reporting Cycle	.41
Table 4-10: Moccasin Dam and Reservoir Long-Term Improvements Project Milestones	
Completed During the Current Reporting Cycle	. 41
Table 4-11: Early Intake Dam – Long-Term Project Milestones Completed During the	
Current Reporting Cycle	. 42
Table 4-12: HHWP Water Storage Projects - Levels of Service Project Drivers	43
Table 4-13: Calaveras Dam Summary (July 1, 2022, through June 30, 2024)	44
Table 4-14: Turner Dam Summary (July 1, 2022, through June 30, 2024)	45
Table 4-15: Pilarcitos Dam Summary (July 1, 2022, through June 30, 2024)	46
Table 4-16: Lower Crystal Springs Dam Summary (July 1, 2022, through June 30, 2024)	47
Table 4-17: San Andreas Dam Summary (July 1, 2022, through June 30, 2024)	48
Table 4-18: Calaveras Reservoir Expansion Project Milestones Completed During the	
Current Reporting Cycle	. 49
Table 4-19: Turner Dam and Reservoir Improvements Project Milestones Completed	
During the Current Reporting Cycle	. 50

Table 4-20: Pilarcitos Dam Improvements Project Milestones Completed During the
Current Reporting Cycle
Table 4-21: San Andreas Dam Facility Improvements Project Milestones Completed During
the Current Reporting Cycle
Table 4-22: Alameda Creek Diversion Dam Restoration Project Milestones Completed
During the Current Reporting Cycle
Table 4-23: RWS Water Storage Projects – Levels of Service Project Drivers
Table 4-24: Rock River Treatment Facility Preventive Maintenance Summary (July 1, 2022,
through June 30, 2024)
Table 4-25: Project Milestones Completed During the Current Reporting Cycle 59
Table 4-26: Sunol Valley Water Treatment Plant Ozone Project Milestones Completed
During the Current Reporting Cycle
Table 4-27: Sunol Valley Water Treatment Plant Short-Term Improvements Project
Milestones Completed During the Current Reporting Cycle
Table 4-28: Long-Term Improvements Project Milestones Completed During the Current
Reporting Cycle
Table 4-29: Sunol Valley Water Treatment Plant Polymer Feed Facility Project Milestones
Completed During the Current Reporting Cycle
Table 4-30: HTWTP Filter Underdrain Project Milestones Completed During the Current
Reporting Cycle
Table 4-31: Regional Groundwater Treatment Improvements Project Milestones Completed
During the Current Reporting Cycle
Table 4-32: RWS Water Treatment Projects – Levels of Service Project Drivers
Table 4-33: Canyon Power Tunnel Preventive Maintenance Summary (July 1, 2022, through
June 30, 2024)
Table 4-34: Canyon Portal Valve House Preventive Maintenance Summary (July 1, 2022,
through June 30, 2024)
Table 4-35: Kirkwood Penstock Preventive Maintenance Summary (July 1, 2022, through
June 30, 2024)
Table 4-36: Early Intake Bypass Tunnel and Pipeline Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)
Table 4-37: Eleanor-Cherry Tunnel Preventive Maintenance Summary (July 1, 2022, through
June 30, 2024)
Table 4-38: Cherry Power Tunnel Preventive Maintenance Summary (July 1, 2022, through
June 30, 2024)
Table 4-39: Granite Portal Valve House Preventive Maintenance Summary (July 1, 2022,
through June 30, 2024)

Table 4-40: Holm Penstock Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 68
Table 4-41: Lower Cherry Aqueduct Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	. 69
Table 4-42: Mountain Tunnel Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 69
Table 4-43: Moccasin Power Tunnel Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	. 70
Table 4-44: West Portal Valve House Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	. 70
Table 4-45: Moccasin Penstock Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	.71
Table 4-46: Foothill Tunnel Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 72
Table 4-47: San Joaquin Pipelines Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 73
Table 4-48: San Joaquin Pipeline Valve Houses Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	.74
Table 4-49: Coast Range Tunnel Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 75
Table 4-50: SJPL Valve and Safe Entry Improvements Project Milestones Completed During	
the Current Reporting Cycle	. 76
Table 4-51: Mountain Tunnel Improvement Project Milestones Completed During the	
Current Reporting Cycle	. 76
Table 4-52: Canyon Tunnel – Hetchy Adit Rehabilitation and O'Shaughnessy Bridge Project	
Milestones Completed During the Current Reporting Cycle	. 77
Table 4-53: Moccasin Penstock Rehabilitation Project Milestones Completed During the	
Current Reporting Cycle	. 78
Table 4-54: HHWP Water Transmission Projects - Levels of Service Project Drivers	78
Table 4-55: Prioritization and Schedule for Cross-Connection Pipeline Mitigation	87
Table 4-56: Cathodic Protection for Water Supply and Treatment Division Transmission	
Pipelines at Various Locations	. 91
Table 4-57: County Line Calibration Summary for the Current Reporting Cycle	94
Table 4-58: Summary of Meter Equipment Replacement, Installation, and Improvement for	
the Current Reporting Cycle	. 95
Table 4-59: As-Needed Pipeline Repairs Project Milestones Completed During the Current	
Reporting Cycle	111

Table 4-60: Corrosion Control (Phase II) Project Milestones Completed During the Current	
Reporting Cycle	112
Table 4-61: San Antonio Pump Station Motor Control Center Upgrades Project Milestones	
Completed During the Current Reporting Cycle	112
Table 4-62: BDPL Nos. 1 through 4 Lining Repair Project Milestones Completed During the	
Current Reporting Cycle	113
Table 4-63: BDPL No. 4 PCCP Repair Project Milestones Completed During the Current	
Reporting Cycle	113
Table 4-64: CSPL No. 2 Reach 5 Lining Replacement Project Milestones Completed During	
the Current Reporting Cycle	114
Table 4-65: CSPL No. 2 Reaches 2 and 3 Rehabilitation Project Milestones Completed	
During the Current Reporting Cycle	114
Table 4-66: RWS Water Transmission Projects – Levels of Service Project Drivers	115
Table 4-67: Cherry Water Distribution System Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	116
Table 4-68: O'Shaughnessy Water Distribution System Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	116
Table 4-69: Early Intake Water Distribution System Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	.117
Table 4-70: Moccasin Water Distribution System Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	118
Table 4-71: Town of Sunol Pipeline Improvement Project Milestones Completed During the	
Current Reporting Cycle	120
Table 4-72: RWS Water Distribution Projects - Levels of Service Project Drivers	.120
Table 4-73: Moccasin Compound Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	122
Table 4-74: South Fork Yard Preventive Maintenance Summary (July 1, 20220, through	
June 30, 2024)	122
Table 4-75: Oakdale Yard Preventive Maintenance Summary (July 1, 2022, through June 30,	
2024)	123
Table 4-76: Warnerville Yard Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	123
Table 4-77: Moccasin Old Powerhouse Hazard Mitigation Project Milestones Completed	
During the Current Reporting Cycle	124
Table 4-78: Moccasin Engineering and Records Building Project Milestones Completed	
During the Current Reporting Cycle	
Table 4-79: HHWP Buildings and Grounds Projects - Levels of Service Project Drivers	.125

Table 4-80: Rollins Road Building Renovation Project Milestones Completed During the	
Current Reporting Cycle	.127
Table 4-81: Millbrae Administration Building HVAC Project Milestones Completed During	
the Current Reporting Cycle	128
Table 4-82: Millbrae Yard Campus Improvements Project Milestones Completed During the	
Current Reporting Cycle	.129
Table 4-83: Sunol Long-Term Improvements Project Milestones Completed During the	
Current Reporting Cycle	.129
Table 4-84: RWS Buildings and Grounds Projects - Levels of Service Project Drivers	.130
Table 4-85: Holm Powerhouse Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	131
Table 4-86: Kirkwood Powerhouse Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	132
Table 4-87: Moccasin Powerhouse Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	132
Table 4-88: Moccasin Powerhouse Bypass Upgrade Project Milestones Completed During	
the Current Reporting Cycle	134
Table 4-89: Moccasin Powerhouse and GSU Rehabilitation Project Milestones Completed	
During the Current Reporting Cycle	.134
Table 4-90: HHWP Power Generation Projects - Levels of Service Project Drivers	.135
Table 4-91: Transmission Lines 1 and 2 Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	136
Table 4-92: Power Transmission Lines 3 and 4 Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	136
Table 4-93: Power Transmission Lines 5 and 6 Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	137
Table 4-94: Transmission Lines 7 and 8 Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	137
Table 4-95: Transmission Lines 9, 10, and 11 Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	138
Table 4-96: Intake Switchyard Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	139
Table 4-97: Moccasin Switchyard Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	139
Table 4-98: Warnerville Substation Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	140
Table 4-99: Calaveras Substation Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	140

Table 4-100: Transmission Lines 7 and 8 Upgrades Project Milestones Completed During	
the Current Reporting Cycle	141
Table 4-101: Transmission Lines Clearance Mitigation Project Milestones Completed	
During the Current Reporting Cycle	142
Table 4-102: Warnerville Substation Rehabilitation Project Milestones Completed During	
the Current Reporting Cycle	142
Table 4-103: Moccasin Switchyard Rehabilitation Project Milestones Completed During the	
Current Reporting Cycle	142
Table 4-104: Power Transmission Projects – Levels of Service Project Drivers	
Table 4-105: Holm Powerhouse to Cherry Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	144
Table 4-106: Cherry Dam to Cherry Valve House Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	144
Table 4-107: Kirkwood Powerhouse to O'Shaughnessy Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	145
Table 4-108: Mather to Cafeteria Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	145
Table 4-109: Mather to Evergreen Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	146
Table 4-110: Moccasin Powerhouse to Low Head Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	146
Table 4-111: Moccasin Powerhouse to Sewer Treatment Plant Preventive Maintenance	
Summary (July 1, 2022, through June 30, 2024)	147
Table 4-112: O'Shaughnessy to O'Shaughnessy Compound Preventive Maintenance	
Summary (July 1, 2022, through June 30, 2024)	148
Table 4-113: Calaveras Dam Power Pole Line Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	149
Table 4-114: Calaveras Substation Power Pole Line Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	149
Table 4-115: Crystal Springs Power Pole Line Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	150
Table 4-116: Pilarcitos Power Pole Line Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	150
Table 4-117: Pulgas Power Pole Line Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	151
Table 4-118: San Andreas Lake Power Pole Line Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	151

Table 4-119: Sawyer Camp Power Pole Line Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	. 152
Table 4-120: Sunol Water Temple Power Pole Line Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	. 152
Table 4-121: Cherry Lake Road Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 153
Table 4-122: Hetch Hetchy Road Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 154
Table 4-123: O'Shaughnessy Adit Access Bridge Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	. 154
Table 4-124: Cherry Lake Road Bridge at Early Intake Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	. 155
Table 4-125: Cherry Lake Road Bridge at Cherry Creek Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	. 155
Table 4-126: Holm Access Bridge Preventive Maintenance Summary (July 1, 2022, through	
June 30, 2024)	. 156
Table 4-127: Moccasin Creek Debris Deflector Bridge Preventive Maintenance Summary	
(July 1, 2022, through June 30, 2024)	. 157
Table 4-128: 2023 January Winter Storm Project Milestones Completed During the Current	
Reporting Cycle	. 158
Table 4-129: 2023 March Winter Storm Project Milestones Completed During the Current	
Reporting Cycle	. 159
Table 4-130: Bridge Replacement Project Milestones Completed During the Current	
Reporting Cycle	. 160
Table 4-131: Watershed, Roads, and Bridges – Levels of Service Project Drivers	. 160
Table 4-132: EBRPD Water System Project Milestones Completed During the Current	
Reporting Cycle	. 162
Table 4-133: Sneath Lane Gate/San Andreas Project Milestones Completed During the	
Current Reporting Cycle	. 163
Table 4-134: Southern Skyline Boulevard Ridge Trail Extension Project Milestones	
Completed During the Current Reporting Cycle	. 164
Table 4-135: SA-1 Service Road/Ingoing Road Project Milestones Completed During the	
Current Reporting Cycle	.164
Table 4-136: Watershed and ROW Protection Project Milestones Completed During the	
Current Reporting Cycle	. 165
Table 4-137: RWS Watershed, Roads, and Bridges Projects – Levels of Service Project	
Drivers	. 165

Table 4-138: O'Shaughnessy Wastewater System Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	166
Table 4-139: Early Intake Wastewater System Preventive Maintenance Summary (July 1,	
2022, through June 30, 2024)	167
Table 4-140: Moccasin Wastewater System Preventive Maintenance Summary (July 1, 2022,	
through June 30, 2024)	168
Table 4-141: Moccasin Wastewater Treatment Plant Project Milestones Completed During	
the Current Reporting Cycle	
Table 4-142: HHWP Wastewater Treatment Project – Levels of Service Project Drivers	169
Table 4-143: Radio Communication Milestones Completed During the Current Reporting	
Cycle	. 171
Table 4-144: Regional SCADA PLC Upgrades Milestones Completed During the Current	
Reporting Cycle	
Table 4-145: Communication System Projects – Levels of Service Project Drivers	
Table 5-1: Facilities in the Aboveground Storage Tank Program	
Table 5-2: Facilities in the California Accidental Release Prevention Program	180
Table 5-3: Facilities in the Hazardous Generator and Hazardous Material Business Plan	
Program	
Table 5-4: Number of SFPUC Division Facilities Enrolled in the Unified Program	
Table A-1: Dams	
Table A-2: Groundwater Wells/Filter Galleries	
Table A-3: Supply Reservoirs	
Table A-4: Treated Water Storage	
Table A-5: Water Treatment Facilities	
Table A-6: Water Transmission – Pipelines and Tunnels	
Table A-7: Water Transmission – Pump Stations	
Table A-8: Water Transmission – Valve Lots	207
Table A-9: Water Transmission – Interties	
Table A-10: Water Transmission – Town of Sunol Distribution System	218
Table A-11: Watershed and Lands Management – Watersheds	
Table A-12: Powerhouses	219
Table A-13: Penstocks	. 219
Table A-14: Watershed and Lands Management – Structures (Non-Operations)	
Table A-15: Buildings and Watersheds – Quarries	223
Table A-16: Buildings and Grounds – Corporation Yards	223
Table A-17: Rolling Stock	223
Table B-1: Relevant Emergency Response Plans for the Regional Water System	
Table B-2: Relevant Plans for the Unified Program	226

Figures

Figure 1-1: Schematic of the Hetch Hetchy Regional Water System	2
Figure 2-1: Mapping Each SFPUC Asset Management Guiding Principle to Multiple Asset	
Management Objectives for the Water Enterprise	8
Figure 3-1: Asset Management Pyramid	. 27
Figure 4-1: Location of RGSR Groundwater Wells	. 58
Figure 4-2: Linear Feet of Pipelines and Tunnels by Material and Installation Decade	. 79
Figure 4-3: Cumulative Pipelines and Tunnels Inventory	. 80
Figure 4-4: Number of Valves Installed by Decade	. 82
Figure 4-5: Number of Valves Exercised at Water Supply and Treatment Division from 2014	
through 2024	. 83
Figure 4-6: Mitigation Priority Breakdowns for BDPL Nos. 1 through 5; CSPL Nos. 1, 2,	
and 3; SSPL; Sunol Region; CSSAPL; SAPL Nos. 1, 2 and 3; and PAPL	.86
Figure 4-7: Cathodically Protected Transmission Pipeline	. 89

List of Abbreviations

AACEI	Association for the Advancement of Cost Engineering International
AAR	Alternatives Analysis Report
AC	alternating current
ACDD	Alameda Creek Diversion Dam
ACTC	Alameda County Transportation Commission
ADAS	automatic data acquisition system
AEP	Alameda East Portal
AF	acre-feet
AFO	acoustical fiber optic
AMI	advanced meter infrastructure
AMP	Asset Management Plan
AMSC	Asset Management Steering Committee
ARV	air release valve
AS	Alameda Siphon
AVV	air vacuum valve
AWIA	America's Water Infrastructure Act of 2018
AWP	Alameda West Portal
AWWA	American Water Works Association
BDPL	Bay Division Pipeline
BFV	butterfly valve
BHR	bioregional habitat restoration
BMP	best management practice
ВО	blowoff valve
B&V	Black & Veatch
CalEPA	California Environmental Protection Agency
CALPL	Calaveras Pipeline
Cal OES	California Governor's Office of Emergency Services
Cal Water	California Water Service Company
CARB	California Air Resources Board
CatEx	categorical exclusion
CISA	Cybersecurity and Infrastructure Security Agency
CSSAPL	Crystal Springs-San Andreas Pipeline
CCSF	City and County of San Francisco

CDD	City Distribution Division
CEA	Compliance Enforcement Authorities
CEQA	California Environmental Quality Act
CER	Conceptual Engineering Report
cfs	cubic feet per second
CIP	Capital Improvement Program
CML	cement mortar lining
CMMS	computerized maintenance management system
COF	consequence of failure
СР	cathodic protection
CRT	Coast Range Tunnel
CSBT	Crystal Springs Bypass Tunnel
CSOS	Crystal Springs Outlet Structure
CSPL	Crystal Springs Pipeline
CSPS	Crystal Springs Pump Station
DBP	disinfection byproduct
DC	direct current
DDW	Division of Drinking Water
DEOP	Division Emergency Operations Plan
DLR	detection limit for purposes of reporting
DO	dissolved oxygen
D/P	differential pressure
DSOD	Division of Safety of Dams
DWR	California Department of Water Resource
EA	Engineering Archive
EAM	Enterprise Asset Management
EAP	emergency action plan
EBMUD	East Bay Municipal Utility District
EBRPD	East Bay Regional Park District
EFWS	Emergency Firefighting Water System
EIR	environmental impact report
EOP	Emergency Operations Plan
ERP	emergency response plan
EV	electric vehicle
FEMA	Federal Emergency Management Agency
FERC	Federal Energy Regulatory Commission

FIRO	Forecast Informed Reservoir Operations	
FY	fiscal year (July to June the following year)	
GCSD	Groveland Community Services District	
GDR	Geotechnical Data Report	
GGNRA	Golden Gate National Recreation Area	
GIR	Geotechnical Investigation Report	
GIS	geographic information system	
gpm	gallons per minute	
GRR	galvanized requiring replacement	
GSU	generator step-up (transformer)	
HAA5	haloacetic acids	
HFPO-DA	hexafluoropropylene oxide-dimer acid	
HHWP	Hetch Hetchy Water and Power	
HTWTP	Harry Tracy Water Treatment Plant	
HVAC	heating, ventilation, and air conditioning	
I-680	Interstate 680	
ICS	Incident Command System	
IFR	instream flow release	
IPS	iron pipe straight threaded plug	
ISO	International Organization for Standardization	
IT	Information Technology	
JOC	job order contract	
KP-OS	Kirkwood Powerhouse to O'Shaughnessy	
kV	kilovolt	
LCA	Lower Cherry Aqueduct	
LCRI	Lead and Copper Rule Improvements	
LCRR	Lead and Copper Rule Revision	
LCSD	Lower Crystal Springs Dam	
LCSR	Lower Crystal Springs Reservoir	
Levels of Service	Levels of Service Goals and Objectives	
LiDAR	Light Detection and Ranging	
LLNL	Lawrence Livermore National Laboratory	
LMPS	Lake Merced Pump Station	
LOF	likelihood of failure	
LOS	Levels of Service Goals and Objectives	
LSL	lead service line	

МСС	motor control center
MCE	maximum credible earthquake
MCL	maximum contaminant level
M/DBP	microbial/disinfection byproduct
MFL	magnetic flux leakage technology
MG	million gallons
mgd	million gallons per day
µg/L	micrograms per liter
MID	Modesto Irrigation District
MND	Mitigation Negative Declaration
MP	Milepost
MPH	Moccasin Powerhouse
MW	megawatt
N/A	not applicable
NAR	Needs Assessment Report
NCSBPL	New Crystal Springs Bypass Pipeline
NCSBT	New Crystal Springs Bypass Tunnel
NEPA	National Environmental Policy Act
NERC	North American Electric Reliability Corporation
NIT	New Irvington Tunnel
NPDES	National Pollutant Discharge Elimination System
NPS	National Park Service
NRLMD	Natural Resources and Lands Management Division
NTP	Notice to Proceed
O&M	operations and maintenance
O&P	operations and planning
OCB	oil circuit breaker
PAC	powdered activated carbon
PAPL	Palo Alto Pipeline
РССР	prestressed concrete cylinder pipe
PFAS	per- and polyfluoroalkyl substances
PFBS	perfluorobutane sulfonic acid
PFHxS	perfluorohexane sulfonic acid
PFNA	perfluorononanoic acid
PFOA	perfluorooctanoic acid
PFOS	perfluorooctane sulfonate

PG&E	Pacific Gas and Electric Company	
PIL	Pilarcitos Dam	
PLC	programmable logic controller	
PM	preventive maintenance	
PMF	probable maximum flood	
ppb	parts per billion	
PRV	pressure-relief valve	
psi	pounds per square inch	
PSMP	Physical Security Mitigation Plan	
Pulgas PS	Pulgas Pump Station	
PVC	polyvinyl chloride	
R&R	rehabilitation and replacement	
RCCCP	Regional Cross-Connection Controls Project	
RCP	reinforced concrete cylinder pipe	
RGSR	Regional Groundwater Storage and Recovery	
RMU	remote monitoring unit	
ROV	remotely operated vehicle	
ROW	right-of-way	
RRA	risk and resilience assessment	
RWS	Regional Water System	
SABPL	San Antonio Backup Pipeline	
SAMP	Strategic Asset Management Plan	
SAPL	San Andreas Pipeline	
SAPS	San Antonio Pump Station	
SCADA	supervisory control and data acquisition	
SF6	sulfur hexafluoride	
SFBOS	San Francisco Board of Supervisors	
SFPUC	San Francisco Public Utilities Commission	
SFWD	San Francisco Water Department	
SFWS	San Francisco Water System	
SJPL	San Joaquin Pipeline	
SMP	surface mining permit	
SOP	standard operating procedure	
sq. mi	square miles	
SRP	Sunol Regional Wilderness Park	
SRWS	State of the Regional Water System	
	0	

SSBPL	Sunset Branch Pipeline
SSPL	Sunset Supply Pipeline
SVCF	Sunol Valley Chloramination Facility
SVWTP	Sunol Valley Water Treatment Plant
SWRCB	State Water Resources Control Board
TBD	to be determined
Т&О	taste and odor
TID	Turlock Irrigation District
TLCM	transmission lines clearance mitigation
TOSPL	Town of Sunol Pipeline
TSOV	turbine shut-off valve
TTF	Tesla Treatment Facility
TTHM	total trihalomethanes
UCMR5	Unregulated Contaminant Monitoring Rule Fifth Round
UCSD	Upper Crystal Springs Dam
UCSR	Upper Crystal Springs Reservoir
UPRR	Union Pacific Railroad
UPS	uninterruptible power supply
U.S. EPA	United States Environmental Protection Agency
USFS	United States Forest Service
UV	ultraviolet
V	volt
VFD	variable-frequency drive
WE	(SFPUC) Water Enterprise
WECC	Western Electricity Coordinating Council
WEEAM	Water Enterprise, Enterprise Asset Management
WMP	wildfire mitigation plan
WQD	Water Quality Division
WSA	Water Supply Agreement
WSAB	Wildfire Safety Advisory Board
WSIP	Water System Improvement Program
WSP	welded steel pipe
WSTD	Water Supply and Treatment Division

1. Introduction and Overview

1.1 Purpose of Report

This 2024 update of the State of the Hetch Hetchy Regional Water System (RWS) report conveys the state of the assets comprising the RWS since the previous update in 2022, covering the period of fiscal years (FYs) 2022/23 and 2023/24 (July 2022 through June 2024). This duration is commonly referred to as the "reporting cycle" throughout this report.

This report is also used to meet a contractual requirement of the Amended and Restated Water Supply Agreement (WSA) of December 2018 between San Francisco Public Utilities Commission (SFPUC) and its wholesale water customers (Section 3.10B):

San Francisco will submit reports to its retail and wholesale customers on the "State of the Regional Water System," including reports on completed and planned maintenance, repair, or replacement projects or programs, by September of every even-numbered year, with reports to start in September 2010.

This report is made available to interested parties and is frequently used internally for reference purposes and budget preparation.

1.2 System Overview

The RWS, owned and operated by SFPUC, consists of a complex series of reservoirs, tunnels, pipelines, pump stations, treatment plants, and power generation and transmission assets that deliver water from Sierra Nevada and Bay Area watersheds to four counties in the Bay Area. The RWS comprises two water systems that were developed independently but are operated as one. The first is *Hetch Hetchy Water*, which imports water from the Tuolumne River and generates hydropower as it is transported downstream. The second is *Regional Water*, originally developed by the Spring Valley Water Company and purchased by the City and County of San Francisco (CCSF) in 1930.

The RWS provides primary water supply for approximately 2.7 million residential, commercial, and industrial customers in San Francisco, Santa Clara, Alameda, San Mateo, San Joaquin, and Tuolumne counties. On average, 15 percent of the water delivered to SFPUC customers is derived from runoff in the Alameda and Peninsula watersheds. The remaining 85 percent comes from Sierra Nevada snowmelt and precipitation via the Tuolumne River and related facilities.

The RWS is shown on Figure 1-1 and spans from the Sierra Nevada to the San Francisco Bay Area. The system begins with three storage reservoirs: Hetch Hetchy Reservoir, Lake Eleanor, and Lake Lloyd.

Hetch Hetchy Reservoir relies on O'Shaughnessy Dam to impound water along the main stem of the Tuolumne River. The Hetch Hetchy watershed is entirely within Yosemite National Park; the majority of lands are in federally designated wilderness area. Water flows by gravity from Hetch Hetchy Reservoir to the Bay Area through a series of tunnels, regulating reservoirs, powerhouses, treatment facilities, and pipelines.




Figure 1-1: Schematic of the Hetch Hetchy Regional Water System

Section 1 – Introduction and Overview 2024 State of the Regional Water System Report

SFPUC's other two impounding reservoirs in the Tuolumne River basin, Lake Eleanor and Lake Lloyd (a.k.a. Cherry Lake), are used primarily to 1) satisfy downstream obligations to Turlock Irrigation District (TID) and the Modesto Irrigation District (MID); 2) maintain minimum instream flow releases below the reservoirs; 3) produce hydroelectric power at Holm Powerhouse; and 4) provide flows for recreational use (i.e., whitewater rafting).

Although Lake Eleanor and Lake Lloyd do not normally supply water directly to the Bay Area, water stored in these reservoirs is instrumental in preserving the Bay Area's water supply in Hetch Hetchy Reservoir. Release of water from these reservoirs can partially fulfill CCSF's inflow obligations to TID and MID, thereby allowing water to be captured and retained in Hetch Hetchy Reservoir for delivery to the Bay Area.

Lake Eleanor is approximately 3 miles above the confluence of Eleanor Creek and Cherry Creek. Lake Lloyd is situated on Cherry Creek, about 4 miles above the confluence with Eleanor Creek. Lake Eleanor and Lake Lloyd are linked by a tunnel and pump facility that allows water to be transferred from Lake Eleanor to Lake Lloyd. As a result of this linkage, the two reservoirs are generally operated as a single unit.

Water that is not released to the creeks below Lake Eleanor and Lake Lloyd is diverted through Cherry Power Tunnel to Holm Powerhouse. Holm Powerhouse is situated on Cherry Creek, about 1 mile upstream of its confluence with the Tuolumne River. Water can be diverted from Lake Lloyd through Holm Powerhouse and released into Cherry Creek, directly upstream of the confluence with the Tuolumne River. These releases also support CCSF's obligations to TID and MID.

Water from Lake Lloyd and Lake Eleanor can be diverted by Lower Cherry Diversion Dam to the Early Intake Diversion Structure on the Tuolumne River, where it would enter Mountain Tunnel to provide an alternative water source for consumption by RWS customers. When supplies from Lake Lloyd and Lake Eleanor are used, all diversions from the Tuolumne River must be filtered. These sources of upcountry, non-Hetch Hetchy water are collectively known as Upcountry Non-Hetch Hetchy Water Supply and were approved by Division of Drinking Water (DDW) in permit amendment No. 5 in 2016.

Water from Hetch Hetchy Reservoir is conveyed through the Canyon Power Tunnel to Kirkwood Powerhouse, where it is used to generate power. Water from Kirkwood Powerhouse is discharged into Mountain Tunnel via the Early Intake Bypass Tunnel and Pipeline. Deliveries to Groveland Community Services District (GCSD) in Tuolumne County are made from waters pumped from Mountain Tunnel. Mountain Tunnel then conveys Hetch Hetchy water to Priest Reservoir, a regulating reservoir. From Priest Reservoir, water enters the Moccasin Power Tunnel and passes through Moccasin Powerhouse, again generating power. Water from Moccasin Powerhouse is discharged directly to Moccasin Reservoir. The state-operated Moccasin Fish Hatchery diverts up to 30 cubic feet per second (cfs) from Moccasin Reservoir.

Water from Hetch Hetchy Reservoir is stored in Priest and Moccasin reservoirs. The majority of local runoff that would normally flow into Priest and Moccasin reservoirs is diverted around the reservoirs and eventually discharges to Don Pedro Reservoir.

After Moccasin Reservoir, the water supply enters Foothill Tunnel via the Moccasin Reservoir Bypass or the Moccasin Gate Tower. The water is treated at the Rock River Lime Plant, along the Foothill Tunnel, to adjust the pH of the water supply by injecting slaked lime (calcium hydroxide). Foothill Tunnel terminates at Oakdale Portal, where the San Joaquin Pipelines (SJPLs) begin.

The SJPLs are three complete pipelines that cross the Central Valley, connecting Foothill Tunnel to the Coast Range Tunnel (CRT). Two additional sections of SJPL (SJPL No. 4 East and SJPL No. 4 West) allow redundancy at the ends of the SJPLs. Crossover facilities (Emery, Pelican, and Roselle) allow transfer of water between pipelines, increasing system resiliency. Throttling stations on SJPL Nos. 2 and 3, in conjunction with the crossovers, allow for any flow target between 70 and 305 million gallons per day (mgd). At the San Joaquin River Valve House, pressure-reducing valves provide pressure relief for the system and a means of drainage at the low point of the pipeline. The SJPLs terminate at the Tesla Valve House, where the water is treated at the Tesla Treatment Facility (TTF). At TTF, water is exposed to ultraviolet (UV) light, pH is adjusted, fluoride is added, and primary disinfection begins with the addition of chlorine.

Water then enters CRT, a 26-mile tunnel terminating at the Alameda East Portal (AEP) in the Sunol Valley in Alameda County. There is a backup disinfection station at Thomas Shaft, approximately 4.5 miles downstream of Tesla Portal. Water traveling through CRT is considered appropriately disinfected upon reaching AEP. AEP is considered the point of entry for the unfiltered Hetch Hetchy supply, in accordance with the RWS drinking water permit.

At AEP, Hetch Hetchy water is split among the four Alameda Siphons that cross the Calaveras Fault and Alameda Creek. Water then flows to the Sunol Valley Chloramination Facility (SVCF), where chlorine is boosted and ammonia is added in the Alameda Siphons to form chloramines. Sodium hydroxide is also added at SVCF to maintain optimal pH levels. Water then continues to the Alameda West Portal (AWP), where it enters the 3.5-mile Irvington Tunnels (Nos. 1 and 2). Hetch Hetchy water can also be diverted to San Antonio Reservoir or the Sunol Valley Water Treatment Plant (SVWTP). Calaveras and San Antonio Reservoirs collect local runoff from their surrounding watersheds, which adds to the overall water supply of the RWS. All local reservoir water in the East Bay is conveyed to SVWTP, where it is treated prior to entering the Alameda Siphons.

From the Irvington Tunnels, the blend of unfiltered Hetch Hetchy water and water treated at SVWTP is split into the five Bay Division Pipelines (BDPLs) at Irvington Portal in Fremont. BDPL Nos. 1, 2, and 5 continue west from the Irvington Tunnels, combining into the Bay Tunnel under San Francisco Bay from Newark to the Ravenswood area, then again splitting flows into BDPL Nos. 1, 2, and 5 to the Pulgas Tunnel west of Redwood City. Bay Tunnel was commissioned in 2014, replacing two existing underwater pipelines. BDPL Nos. 3 and 4 travel south from Irvington Portal and follow the southern shore of San Francisco Bay through Santa Clara, Sunnyvale, Mountain View, Palo Alto, and Stanford to Pulgas Tunnel just west of Redwood City, where all five pipelines meet. Water in the Pulgas Tunnel continues to flow north to Crystal Springs Bypass Tunnel to meet demands on the Peninsula; when demand is low, water is either pumped into the Pulgas Balancing Reservoir for storage or flows into Upper Crystal Springs Reservoir (UCSR) after being dechloraminated at the Pulgas Dechloramination Facility. Palo Alto Pipeline (PAPL)

Section 1 – Introduction and Overview 2024 State of the Regional Water System Report

is supplied by BDPL Nos. 1, 2, and 5, and supplies water south from Redwood City to Palo Alto, Stanford, and Menlo Park.

North of the Crystal Springs bypass facilities, Hetch Hetchy/SVWTP water is transmitted along the Peninsula into CCSF's low-pressure zone system via Sunset Supply Pipeline (SSPL) and Crystal Springs Pipeline (CSPL) Nos. 1, 2, and 3. Terminal storage for the low-pressure zone water consists of the University Mound Reservoir in San Francisco, which is supplied from CSPL Nos. 1 and 2. SSPL low-pressure zone water is transmitted north along the Peninsula to Lake Merced Pump Station (LMPS) in San Francisco, where it is pumped into the high-pressure zone. Water from LMPS either serves demands directly or is stored in Sunset Reservoir and Sutro Reservoir in San Francisco.

San Mateo Creek watershed runoff is captured in Lower Crystal Springs Reservoir (LCSR) and UCSR. Pilarcitos Creek watershed runoff is routed to LCSR for storage. Water from LCSR is transferred to San Andreas Reservoir through Crystal Springs Pump Station (CSPS) and Crystal Springs-San Andreas Pipeline (CSSAPL). Harry Tracy Water Treatment Plant (HTWTP) draws from San Andreas Reservoir for supply and produces high-pressure zone water. Treated water from HTWTP is transmitted through San Andreas Pipeline (SAPL) Nos. 2 and 3 and the Sunset Branch Pipeline (SSBPL). SAPL Nos. 2 and 3 reach high-pressure zone reservoirs in San Francisco. The SSBPL connects high-pressure zone to low-pressure zone water in SSPL through a pressurereducing valve at the Capuchino Valve Lot in Millbrae. In Colma, at the San Pedro Valve Lot, SAPL No. 3 is interconnected with SSPL; north of this point, it is used for low-pressure zone water transmission to Merced Manor Reservoir. Baden Pump Station allows low-pressure zone water from CSPL No. 2 to be pumped to each high-pressure zone pipeline. Baden Pump Station can also be used to transfer high-pressure zone water into low-pressure zone pipelines. These interzone connections accomplished through the Water System Improvement Program (WSIP) at San Pedro Valve Lot, Baden Pump Station, and Capuchino greatly increase operational flexibility, particularly during construction work and emergencies.

Pilarcitos watershed and reservoir is used to partially supply Coastside County Water District and the RWS via inter-basin transfers.

A major upgrade of RWS facilities began in 2002, with the initiation of WSIP. Most projects are completed, and the program is 98 percent complete. As of June 2024, two regional projects remain to be completed: the Regional Groundwater Storage and Recovery (RGSR) project and the Alameda Creek Recapture project. Completion dates for these two projects have been extended to December 7, 2027, and June 30, 2032, respectively, due to project delays resulting from easement and right-of-way (ROW) challenges for groundwater pipeline alignments, and bank erosion and operational complexity challenges for the recapture project. WSIP projects addressing seismic reliability have been completed, significantly increasing the reliability of the system.

Thirteen groundwater wells in northern San Mateo County that were installed under WSIP will produce supplemental dry-year water supply to the RWS as part of a SFPUC conjunctive-use project with the City of Daly City, and the California Water Service Company (Cal Water), which serves South San Francisco and Colma. Six groundwater wells in San Francisco will produce up to 4 mgd of groundwater for retail delivery in San Francisco, helping offset some of San Francisco's demand from the RWS.

1.3 Water Enterprise Management Structure

The RWS is owned and operated by SFPUC, a department of CCSF, and serves both retail and wholesale customers in four counties in the Bay Area. SFPUC is responsible for the operations, maintenance, and development of three utility enterprises: Water, Wastewater, and Power. The Water Enterprise (WE) manages the RWS through two large Operating Divisions that report to the Assistant General Manager, Water: Hetch Hetchy Water and Power (HHWP) and Water Supply and Treatment Division (WSTD).

HHWP manages the *Hetch Hetchy Water* portion of the RWS from the source of the system in the Sierra Nevada to AEP. Additionally, HHWP operates and maintains SFPUC's power generation and transmission system from its upcountry powerhouses in the Sierra Nevada across the valley to Newark.

WSTD manages the *Regional Water* portion of the RWS from AEP at the end of CRT, through the wholesale service area, to terminal reservoirs in San Francisco. Additionally, WSTD operates and maintains multiple water treatment facilities to treat water from the Hetch Hetchy, Alameda Watershed, and Peninsula Watershed supplies.

In addition to the two abovementioned Operating Divisions, WE includes the Natural Resources and Lands Management Division (NRLMD), the Water Quality Division (WQD), the Water Resources Division (WRD), and the City Distribution Division (CDD).

NRLMD is responsible for operations and maintenance (O&M) of SFPUC-owned watershed and ROW lands in the East Bay and Peninsula, and environmental regulatory compliance for WE O&M activities.

WQD provides laboratory services, compliance/operational monitoring, process engineering, regulatory reporting, water quality inquiry/complaint response, and technical support for both HHWP and WSTD in the operation of the RWS.

WRD is responsible for diversifying San Francisco's water supply portfolio through a number of programs, including water conservation, groundwater, recycled water, and onsite water recycling. WRD also evaluates new projects that will help meet future water supply needs in the SFPUC service area, such as groundwater banking, surface water storage expansion, water transfers, purified water, and desalination, as well as technological innovations and other tools that can increase supply or reduce demand.

CDD is an Operating Division responsible for O&M of San Francisco's four active water systems: the Potable System, which includes reservoirs and pump stations; the Groundwater System; the Recycled Water System; and the Emergency Firefighting Water System.

1.4 Organization of Report

The State of the Regional Water System (SRWS) is best communicated by the state of the assets that it comprises. For this reason, the SRWS Report is strategically organized to communicate maintenance, capital, and regulatory work that is accomplished to maintain a sustainable RWS for customers that it serves. Report organization is summarized in Table 1-1.

2024 State of the Regional Water System Report

Section	Core Focus
1	Defines purpose of the SRWS Report and provides an overview of the system and management structure
2	Provides an overview of asset management policies and capital planning business processes that are in place to manage the system
3	Reports on the progress that WE made during reporting cycle on its implementation of the Asset Management Policy
4	Is organized by asset type, providing a detailed report on asset maintenance and condition, as well as relevant capital improvement projects
5	Summarizes the regulators that have jurisdiction over the operation of portions of the RWS, and any inspections or activities that occurred during this reporting cycle
6	Presents potential emerging issues tracked by SFPUC that may have significant impacts to operations and maintenance of the RWS

Table 1-1: Organization of SRWS Report

Notes:

RWS = Regional Water System SFPUC = San Francisco Public Utilities Commission SRWS = State of the Regional Water System WE = Water Enterprise

2. Asset Management Policy and Capital Planning Process

SFPUC has an Asset Management Policy and Capital Planning Process, which is implemented by WE. The policy and process work in tandem to produce a sustainable management structure that supports WE's ability to achieve the Levels of Service Goals and Objectives (LOS or Levels of Service). Building on this foundation, WE developed and mapped specific asset management objectives to the Asset Management Policy; thus, establishing an architecture for management of WE assets.

2.1 Asset Management Policy

The SFPUC Asset Management Policy (SFPUC Policy) guides the planning, design, procurement, construction, operation, maintenance, and retirement of critical infrastructure. Adopted by SFPUC in December 2020, it outlines SFPUC's commitment and approach to managing its diverse portfolio of assets in a manner that maximizes life-cycle value of assets while consistently meeting LOS and performance goals, as well as driving evidence-based decision making. At the heart of the policy exists a set of "Guiding Asset Management Principles" that serve as the backbone of WE's Asset Management strategy. WE's implementation of the SFPUC Policy is discussed in Section 2.1.1, and its "Guiding Asset Principles" are summarized in Table 2-1.

2.1.1 Water Enterprise's Implementation of the SFPUC Asset Management Policy

Since the SFPUC Policy was adopted, WE has worked on an implementation strategy that maps specific, measurable asset management objectives to the "Guiding Asset Management Principles" that were defined in the SFPUC Policy. As illustrated on Figure 2-1, each SFPUC guiding principle may have multiple objectives defined by WE that, once achieved, will bring its Asset Management in alignment with the SFPUC Policy.

The implementation strategy serves as a multi-year road map that will achieve consistency across the WE. The rate of implementation will be specific to each Operating Division and will be heavily influenced by available resources and competing operational priorities. Section 3 provides updates on each asset management objective, highlighting WE's accomplishments and achievements as it works toward full implementation of the SFPUC Policy.

Figure 2-1: Mapping Each SFPUC Asset Management Guiding Principle to Multiple Asset Management Objectives for the Water Enterprise




Table 2-1: Summary of SFPUC Asset Management Guiding Principles and Water Enterprise's
Asset Management Objectives

Guiding Asset Management Principle	SFPUC Principle Description	Water Enterprise Objectives
Asset Risk Management	Develop and implement a risk management methodology that integrates understanding of risk across all asset classes and facilities.	See 2.1.1.1
Asset Management and Maintenance Roles and Responsibilities	Establish organizational roles, responsibilities, and accountability, at the Enterprise and Bureau levels, across the various asset classes, for the management of the life cycle of the assets.	See 2.1.1.2
Asset Management Objectives	Establish, publish, and regularly review asset management objectives to guide capital and maintenance planning. The objectives provide the necessary detail to connect daily workforce priorities with the broader policy goal and LOS.	See 2.1.1.3
Asset Registry	Maintain a detailed asset inventory in CMMS and/or GIS.	See 2.1.1.4
Asset Condition	Perform periodic asset condition assessments to maintain the system in reliable working order.	See 2.1.1.5
Operations and Maintenance Strategies	Develop and implement reliability-centered, preventive, and corrective maintenance programs, across all asset classes, based on condition assessment findings and asset criticality.	See 2.1.1.6
Asset Investment Strategies	Incorporate asset management findings into operating and capital budgets. Develop capital projects that directly address gaps in asset performance relative to established LOS and performance metrics.	See 2.1.1.7
Budgeting	Develop budgets for all prioritized work; identify implementable funding plans in collaboration with SFPUC Finance.	See 2.1.1.8
Performance Monitoring	Evaluate asset performance; investigate asset incidents and failures; and record available asset data for use in reviewing asset management objectives, updating the asset registry, assessing asset conditions, and informing operations and maintenance strategies and asset investment strategies.	See 2.1.1.9
LOS	Establish, publish, and regularly review LOS, and related performance objectives.	See 2.1.1.10

Notes:

CMMS = Computerized Maintenance Management System

GIS = geographic information system

LOS = Levels of Service Goals and Objectives

SFPUC = San Francisco Public Utilities Commission

Section 2 – Asset Management Policy and Capital Planning Process 2024 State of the Regional Water System Report

2.1.1.1 Asset Management Guiding Principle: Asset Risk Management

SFPUC Guiding Principle Description. Develop and implement a risk management methodology that integrates understanding of risk across all asset classes and facilities.

Objectives

- Develop a Risk Framework that standardizes the use of consequence of failure (COF) and likelihood of failure (LOF) as the main drivers for determining system risk throughout WE.
- Maintain emergency response plans (ERPs) for all WE Divisions.
- Further develop and maintain a risk register in a computerized maintenance management system (CMMS), including a score for COF, LOF, and Risk.
- 2.1.1.2 <u>Asset Management Guiding Principle: Asset Management and Maintenance</u> Roles and Responsibilities

SFPUC Guiding Principle Description. Establish organizational roles, responsibilities, and accountability, at the Enterprise and Bureau levels, across the various asset classes, for the management of the life cycle of the assets.

Objectives

- Develop an asset change management process.
- Develop WE and Division-level matrices to clearly outline roles and responsibilities for asset management and O&M staff.

2.1.1.3 Asset Management Guiding Principle: Asset Management Objectives

SFPUC Guiding Principle Description. Establish, publish, and regularly review asset management objectives to guide capital and maintenance planning. The objectives provide the necessary detail to connect daily workforce priorities with the broader policy goal and LOS.

Objectives

- Establish Asset Management Objectives for WE that map back to SFPUC's Asset Management Policy.
- Review the objectives to meet the system's operational needs at least once every 2 years.
- Report on the status of the Asset Management Objectives once every 2 years.

2.1.1.4 Asset Management Guiding Principle: Asset Registry

SFPUC Guiding Principle Description. Maintain a detailed asset inventory in CMMS and/or geographic information system (GIS).

Objectives

- Continue to develop and maintain a detailed asset registry with increased standardization and uniformity across WE (asset classification, subclassification, specifications, and taxonomy).
- Develop a shared definition of an "asset" throughout WE.
- Continue to use and standardize location and functional/location hierarchies within CMMS and GIS.
- Develop and maintain a GIS database for WE's linear assets.

2.1.1.5 Asset Management Guiding Principle: Asset Condition

SFPUC Guiding Principle Description. Perform periodic asset condition assessments to maintain system in reliable working order.

Objectives:

- Complete planned and scheduled asset condition assessments that inform maintenance, investment, and risk mitigation strategies.
- Prioritize condition assessments to increase system reliability.

2.1.1.6 Asset Management Guiding Principle: Operations and Maintenance Strategies

SFPUC Guiding Principle Description. Develop and implement reliability-centered, preventive, and corrective maintenance programs, across all asset classes, based on condition assessment findings and asset criticality.

Objectives:

- Develop a Strategic Asset Management Plan (SAMP) and individual Asset Management Plans (AMPs).
- Establish the ability to use CMMS to demonstrate compliance with federal, state, and local regulatory requirements.
- Demonstrate proper stewardship of environmental resources under SFPUC control through the use of CMMS reporting.

2.1.1.7 <u>Asset Management Guiding Principle: Asset Investment Strategies</u>

SFPUC Guiding Principle Description. Incorporate asset management findings into operating and capital budgets. Develop capital projects that directly address gaps in asset performance relative to established LOS and performance metrics.

Objectives:

• Use asset management data to develop expenditure reports that compile costs for facilities, assets, and maintenance programs.

- Develop and implement a replacement planning approach to estimate asset useful life, renewal, and replacement requirements and costs.
- Design future facilities based on information gathered through the asset management program.

2.1.1.8 Asset Management Guiding Principle: Budgeting

SFPUC Guiding Principle Description. Develop budgets for all prioritized work; identify implementable funding plans in collaboration with SFPUC Finance.

Objectives:

- Update the 10-Year Capital Improvement Program (CIP) and annual operating budget by integrating data from condition assessments, estimates of remaining useful life, failure analyses, replacement costs, maintenance programs, and LOS into a well-informed forecast of Capital and Rehabilitation and Replacement (R&R) Program costs.
- Develop expenditure reports that compile costs for facilities, assets, and maintenance programs a quick way to tell where money is going and what it is accomplishing.

2.1.1.9 Asset Management Guiding Principle: Performance Monitoring

SFPUC Guiding Principle Description. Evaluate asset performance; investigate asset incidents and failures; and record available asset data for use in reviewing asset management objectives, updating the asset registry, assessing asset conditions, and informing O&M strategies and asset investment strategies.

Objectives:

- Formalize asset failures analysis and root cause analysis across WE.
- Complete peer reviews of maintenance programs to ensure that the scope of maintenance is consistent with industry standards and create opportunities to increase standardization and uniformity across the WE, Enterprise Asset Management (WEEAM) Programs.
- Establish and maintain Key Performance Indicators to track planning and scheduling, asset, and asset management efficiency and effectiveness.

2.1.1.10 Asset Management Guiding Principle: Levels of Service

SFPUC Guiding Principle Description. Establish, publish, and regularly review LOS, and related performance objectives.

Objectives:

• Review LOS goals and objectives every odd year.

See Section 2.1.2 for WE's Levels of Service

2.1.2 Level of Service History and Objectives

In 2008, the SFPUC adopted LOS for WE in conjunction with the approval of the WSIP Programmatic Environmental Impact Report. Those Levels of Service provided the basis for many WSIP projects. The Amended and Updated LOS Goals and Objectives (November 2023) builds from the base of those adopted in 2008. They generally retain the 2008 Levels of Service and carry them forward with additions to ensure that Levels of Service are maintained and/or updated, and to cover areas not previously included in 2008, such as In-City Delivery Reliability and Workforce and Community Support.

The approved LOS language is included in the following paragraphs.

GOAL: Drinking Water Quality - Maintain High Water Quality

System Performance Objective:

- Operate and maintain RWS facilities to comply with or surpass all current and future federal and state drinking water quality requirements.
- Provide clean, unfiltered water originating from Hetch Hetchy Reservoir, filtered water from Bay Area watersheds, and appropriately treated water from other sources.
- Continue to implement watershed protection measures in SFPUC's Peninsula, Alameda, and Tuolumne watersheds to protect watershed ecosystems and drinking water quality.
- Maintain applied research, planning, and outreach programs to ensure that customer water quality expectations are met.
- Respond to 100 percent of In-City customer service inquiries or complaints about water quality within 2 business hours of initial contact and RWS events upon exceedance of established threshold criteria.

GOAL: Regional Seismic Reliability - Maintain Ability to Meet Current Seismic Standards

System Performance Objective:

- Design and construct water and related power system improvements to meet current seismic standards (e.g., Division of Safety of Dams [DSOD]), and regularly evaluate the ability of the system to meet current seismic standards.
- Maintain or resume delivery of 229 mgd to the three regions in the SFPUC service area (East/South Bay, Peninsula, and San Francisco) within 24 **hour**s after a major earthquake. The performance objective is to provide delivery to at least 70 percent of the turnouts in each region, with 104, 44, and 81 mgd delivered to the East/South Bay, Peninsula, and San Francisco, respectively.
- Restore facilities to meet a daily demand of 265 mgd within 30 days after a major earthquake.

GOAL: Regional Delivery Reliability – Maintain Delivery Reliability During Normal Operations and Maintenance

System Performance Objective:

- Meet all local, state, and federal water, power, and environmental regulations to support the proper operation of the water system and proper operation of power facilities essential to the operation of the water system.
- Provide operational flexibility to allow planned maintenance shutdown of individual facilities without interrupting customer service.
- Provide operational flexibility to minimize the risk of service interruption due to unplanned facility upsets or outages.
- Maintain emergency response and recovery plans for major water delivery assets to minimize the duration of unplanned outages.
- Provide operational flexibility and system capacity to replenish local reservoirs as needed.
- Operate and maintain RWS facilities to meet a daily peak demand of 300 mgd.
- Operate and maintain RWS facilities to meet a daily demand of 265 mgd under the conditions of one planned shutdown of a major facility for maintenance (a reach of a San Joaquin Pipeline or a reach of a BDPL), concurrent with one unplanned facility outage due to a natural disaster, emergency, or facility failure/upset. During planned shutdowns of the Tuolumne River supply, the system can meet full winter demands (approximately 150 mgd). In the event of an unplanned loss of one water treatment plant, the water system can still meet a minimum delivery of 115 mgd, until the Tuolumne River supply are restricted to the period from November 1 through March 31, and no longer than 60 days, with special exceptions for shutdowns of up to 100 days. The return-to-service goal for planned shutdowns of the Tuolumne River supply is no more than 7 days.
- Operate upcountry and Bay Area water reservoirs to optimize water supply and comply with environmental regulations while mindful of downstream conditions.
- Provide wholesale customers with timely information and data sufficient to support operational decision-making of their retail systems.

GOAL: In-City Seismic Reliability - Reduce Vulnerability to Earthquakes

System Performance Objective:

- **Storage.** Maintain seismically reliable potable water storage to provide at least 20 pounds per square inch (psi) pressure throughout each pressure zone.
- **Fire Suppression.** In conjunction with the Emergency Firefighting Water System, within 3 hours of a major earthquake, provide at least 50 percent of anticipated water demand

from post-seismic fires in each of 46 Fire Response Areas, and at least 90 percent of Citywide average water demand from post-seismic fires.

- Water Supply Restoration. Deliver basic life-sustaining water supply (for hygiene, sanitation, and consumption if boiled or disinfected) and ensure restoration of potable water system.
 - Within 24 hours, limited network of critical transmission mains (greater than or equal to 12-inch diameter) that serve major hospitals will be pressurized.
 - Within 72 hours, limited network of critical secondary distribution system pipelines (< 12-inch-diameter) will be pressurized.
 - Within 7 days, limited network of critical transmission and distribution mains will be disinfected and restored to potable service.
 - Within 90 days, secondary distribution system will be restored to potable service.
 - Use alternative water sources such as groundwater to supplement Sunset and Sutro Reservoirs.

GOAL: In-City Delivery Reliability - Reliably Deliver Water to All In-City Retail Customers

System Performance Objective

- Maintain potable water storage to provide at least 2 days of winter day demand plus a minimum 2 hours of fire suppression at three hydrants (1,500 gallons per minute [gpm] from each hydrant) in each pressure zone with storage greater than 1 million gallons, and two hydrants (1,500 gpm from each hydrant) for each pressure zone with storage ≤ 1 million gallons.
- Maintain a minimum pressure of 20 psi throughout the distribution system.
- Respond to 100 percent of customer service inquiries or complaints regarding water service within 2 business hours of initial contact.
- Maintain deliveries so that ≤ 1.0 percent of service connections are without water for up to 4 hours as a result of an unplanned outage per year.
- Maintain deliveries so that ≤ 0.5 percent of service connections are without water for 8 hours or longer as a result of an unplanned outage per year.

GOAL: Water Supply - Meet Customer Water Needs in Non-Drought and Drought Periods

System Performance Objective:

• Meet an average annual water demand of 265 mgd from the SFPUC watersheds for retail and wholesale customers during non-drought years, consistent with the Water Supply Agreement between San Francisco and its wholesale customers in Alameda, San Mateo, and Santa Clara Counties.

- Meet dry-year delivery needs while limiting rationing to a maximum 20 percent systemwide reduction in water service during extended droughts.
- Diversify and improve use of new water sources and drought management, including groundwater, recycled water, conservation, transfers, storage expansion, purified water, desalinated water, and technological innovations that can increase supply and/or water use efficiency.
- Maintain San Francisco retail residential potable water use below 45 gallons per capita per day.
- Realize annual Real Water Losses of less than 10 percent of water supplied to San Francisco.
- Meet 80 percent of San Francisco's Recreation and Parks Department irrigation demands with recycled water by December 31, 2025.

GOAL: Environmental Stewardship - Maintain High Environmental Performance Standards

System Performance Objectives

- Meet all current and anticipated environmental legal requirements.
- Manage SFPUC watershed and ROW lands to protect and restore native ecological resources, protect and preserve cultural resources, and minimize wildfire risk.
- Manage and operate the WE assets consistent with the WE Environmental Stewardship Policy.

GOAL: Sustainability – Enhance Sustainability in all System Activities (Environmental, Economic and Social)

System Performance Objective:

- Energy Utilization
 - Maintain a gravity-driven water system.
 - Minimize the carbon footprint of all water system operations through sustainable design and operational practices.
- Security
 - Comply with or surpass all current and future federal and state physical and cyber security requirements.
- Workforce Support
 - Attract, develop, and retain a healthy, safe, well-trained, productive, and well-equipped workforce, reflective of the communities that SFPUC serves.

- Provide and promote opportunities for knowledge transfer and staff development in areas critical to meeting the Levels of Service.
- Implement the WE Racial Equity Action Plan.
- Community Support
 - Be mindful of and responsive to community needs throughout the SFPUC service area as part of operating and maintaining the water system.
 - Maintain a proactive program of public outreach regarding all aspects of the water system.
 - Provide the public with appropriate educational opportunities by providing education programs and recreational opportunities (where appropriate) in cooperation with other local, state, and federal agencies.
 - Expand targeted, thoughtful efforts to build relationships with Federally Recognized Tribes and other California Native Americans.
 - Manage watershed and ROW lands to protect cultural and tribal resources.
- Effective Asset Management
 - Ensure cost-effective use of funds and other resources.
 - Implement effective asset management programs for all assets (facilities, lands, and equipment), consistent with SFPUC's Asset Management Policy.
 - Adequately maintain RWS assets. Annually complete 80 percent of preventive maintenance work, 80 percent of corrective maintenance work, and have <10 percent of assets in unserviceable state.
 - Provide water meter data for fair and timely billing of both wholesale and retail water customers, as well as effective management of water supplies.
- Strategic Planning
 - Continually evaluate and plan for changing environmental, fiscal, and social conditions, (e.g., climate change, development, regulation and other factors outside of SFPUC's control) that influence the ability to achieve these Levels of Service.

Progress on Strategic Efforts

We will be modifying the next version of this report to include progress on LOS strategic planning efforts not previously included in this report. For this reporting period, we will update the status of two WE efforts, they are:

- Climate change; and
- Expand targeted, thoughtful efforts to build relationships with Federally Recognized Tribes and other California Native Americans.

Climate Change

WE continues to adjust operations in response to climate change.

Since the late 1990s, SFPUC performed reservoir operations on snowmelt-fed watersheds, using hydrologic models driven by weather forecasts. While continuing to see impacts of climate change on weather and catchment hydrologic response, SFPUC has advanced this process, developing a systematic approach for reservoir operations across the upcountry area. Like other utilities focusing on this effort, SFPUC has adopted some of the procedures of the Forecast Informed Reservoir Operations (FIRO) framework. SFPUC continues to improve our modeling tools to predict inflow to our reservoirs. Today, SFPUC relies on many short- and long-term precipitation and temperature scenarios to drive these models through runoff. In addition to data and forecast output from the National Weather Service, SFPUC also relies on products from the California Nevada River Forecasting Center, Airborne Snow Observatories and Center for Western Weather and Water Extremes. SFPUC feels this progression has:

- improved water supply management;
- improved response to heavy/warm rainfall events; and
- supported various environmental objectives, including our Upper Tuolumne River flow effort.

SFPUC's efforts will expand over the next reporting period. SFPUC intends to develop a consistent policy across the WE that takes into consideration the impacts of climate change on infrastructure improvements, system operations, and maintenance. This effort will take multiple years.

Commitment to Stewardship of Cultural and Tribal Resources

SFPUC has made great strides in both cultural resources management and developing tribal relationships through the earnest efforts of key staff supported by management. Building on this foundation, the planning and development of the Alameda Watershed Center has cemented SFPUC's commitment to furthering our collaboration in this important realm. Partnering with tribal communities, state and federal agencies, other City departments, and non-governmental organizations has helped build our agency's cultural and tribal resource stewardship capacity.

SFPUC recognized the need to dedicate staff and seek professional services support for this mission-critical work. Collaboration with the Muwekma Ohlone on the Alameda Watershed Center has been integral to deepening SFPUC's understanding of tribal cultural resources and recognizing the significance of traditional ecological knowledge. A pilot program to upgrade the cultural resources management program for the HHWP project area is in progress. By committing agency resources to these important efforts, SFPUC demonstrates its priorities to protect and preserve cultural and tribal resources and build meaningful relationships based on trust and reciprocity with California Native Americans.

2.2 Capital Planning

SFPUC's 10-Year CIP is a long-range forecast of capital investments required across its three enterprises: Water, Wastewater, and Power. The 10-Year CIP is typically updated biennially, with minor updates in the between years, and includes two years of project budgets approved for capital spending and an additional 8 years of planned appropriations for future project budgets. The 10-Year CIP is adopted by SFPUC and approved by the City of San Francisco Board of Supervisors (SFBOS) during the fiscal year prior to the first year of the 10-Year CIP.

Capital projects that support the RWS are organized into two 10-Year CIPs – the Hetch Hetchy Water CIP and the Regional Water CIP; these are adopted by SFPUC with the other plans and integrated into SFPUC's Financial Plan and long-term rate-setting calculations. The Hetch Hetchy Water CIP includes capital improvements to assets that are operated and maintained by HHWP. Similarly, the Regional Water CIP includes capital improvements to assets that are operated and maintained by WSTD, WQD, and NRLMD.

The objectives for the capital plans are that they are 1) aligned with each enterprise's priorities, requirements, and needs; 2) reviewed to confirm that adequate staffing and contracting resources are available to implement; and 3) considered "affordable," based on meeting affordability goals developed by Finance. The Capital Planning Process generally includes: 1) identification and prioritization of candidate capital projects; 2) development of new and updates to/confirmation of existing project scopes, schedules, and budget estimates; 3) confirmation of project deliverability; 4) review of impacts to long-term rates and resulting affordability for rate-payers; 5) optimization and balancing to meet annual budget targets and overall capital priorities, resulting in an optimized balanced 10-Year CIP that is presented to SFPUC for adoption.

In 2022, the 10-Year CIP that was adopted for FY2023-2032 did not show a balance of "uses" (spending) versus "sources" (incoming funds) for years 3 through 10; however, because the first 2 years were balanced, the 2-year budgets were adopted and approved. Consequently, SFPUC decided to update the 10-Year CIP during 2023, normally a "between year," with the goal of optimizing and balancing the CIP by spending down unspent appropriations, confirming project cost estimates, and reviewing affordability and long-term impacts from increasing rates. On February 14, 2023, SFPUC adopted a balanced 10-Year CIP for FY2024-2033 that included a \$977 million budget for the Hetch Hetchy Water CIP and a \$1,135 million budget for the Regional Water CIP.

In 2023, SFPUC took on the Capital Planning Improvement Initiative to improve budget preparation processes for better consistency, governance, standardization, guidance, and project deliverability. After a thorough assessment, the program implemented new tools, established clear roles, and developed 10-Year CIP Development Guidelines. The Guidelines resulted in improved practices for all SFPUC departments, leading to a more efficient budget development process, with enterprises more transparently prioritizing projects based on deliverability and affordability – in addition to risk, criticality, and required investment due to regulations. In addition, in 2023, SFPUC adopted the Affordability Policy, which established agency-wide performance metrics for evaluating the impact of rate increases over a 20-year planning horizon. This allowed more realistic and data-driven forecasting of impacts from rate increases, resulting in higher confidence on the affordability of the 10-Year CIP.

During 2023, SFPUC staff followed the Guidelines and developed a draft 10-Year CIP that met affordability targets. Because of the robust capital planning process, which included deliverability review, along with the plan's conformance with the Affordability Policy, SFPUC adopted the 10-Year CIP for FY2025-2034 on February 13, 2024. The CIP included a \$1,534 million budget for the Hetch Hetchy Water CIP and a \$1,626 million budget for the Regional Water CIP, an increase of \$557 million and \$491 million for both programs, respectively, from the previous year's plan. Some of the primary reasons for these forecasted cost increases include higher post-pandemic market pricing for ongoing projects, additional critical projects needed for rehabilitating pipelines and treatment facilities, and greater scope definition for future alternative water supply projects.

2.2.1 Capital Planning Process Overview

The WE was instrumental in 2023 in helping develop the 10-Year CIP Development Guidelines due to its already robust capital planning practices. The Guidelines provided additional process details, helped to clarify each step of the process, and coordinated deadlines and requirements for different departments and functions. The processes that the WE implements to develop the 10-Year CIP that are included in the Guidelines are outlined below.

2.2.1.1 Identification of Candidate Capital Projects

Through its robust asset management practices, WE identifies and prioritizes the capital investments that are required to keep the RWS in reliable operating condition. Each of WE's Operating Divisions is responsible for identifying candidate capital projects based on asset management data, regulatory requirements, emerging needs, and specific program goals or objectives (such as Alternative Water Supply projects). Data used to identify candidate projects vary but may include condition, age, operational performance, regulatory requirements, technology improvements, and estimated remaining life. Once identified, a list of candidate projects is produced for each Operating Division so that estimates may be developed for the candidate projects' scope, schedule, and budget.

2.2.1.2 <u>Development of Scope, Schedule, and Budget Estimates</u>

For preparation of the 10-year CIPs, both active projects and new candidate projects undergo a project development and confirmation process that either updates or establishes scope, schedule, and budget for each project prior to advancing to the deliverability review.

New Candidate Projects

To confirm the project's scope, schedule, and budget for a new candidate project, a multidiscipline team is assembled from WE's Operating Divisions and Infrastructure. Led by the Operating Division, the team discusses the need for the project and develops a basic scope of work that can be used to establish an initial schedule and budget. Infrastructure then leads the team to further develop the schedule and budget for the project.

The budget developed for a new candidate project usually does not have much project maturity (typically less than 2 percent of project definition) and is often the result of assessment or inspection work that was recently completed by the WE Operating Divisions. Because the project definition is low at this stage of the project, the cost estimates carry ranges and contingencies that

are commensurate with the level of information on which they were based. Cost estimates are typically treated as Class 5 estimates, according to the Association for the Advancement of Cost Engineering International (AACEI) guidelines, and carry a range of -50 percent to +100 percent. Additionally, built into the initial estimates are contingencies for design and reserves for unknowns. Lastly, the estimates include assumptions for escalation, which are calculated to the midpoint of construction once a schedule is determined.

Similar to the budget, the initial schedule for a new candidate project is developed collaboratively between the WE's Operating Divisions and Infrastructure. Under Infrastructure's leadership, the initial schedule for a new candidate project is developed by identifying the phases and deliverables that are expected for the project. Infrastructure applies its experience to identify the durations for each of the phases and milestones, and build up a draft of the initial schedule. The Operating Division may identify potential system outage constraints, including durations and boundaries, and the project's construction schedule is adjusted as appropriate. It is noted that this exercise may impact the project's cost estimate because the mid-point of construction may change, resulting in a change in the escalation part of the cost estimate.

Once candidate projects have scopes, schedules, and budgets established, they are entered into a capital planning database (SFPUC is currently using Unifier software) so they can be further evaluated based on the Operating Divisions' priorities, the funding available, and Infrastructure's resources.

Active Capital Projects

Unlike new candidate projects, active projects were approved in previous capital plans and have a moderate to strong project maturity level. The project teams have improved information, such as completed planning documents (e.g., Alternatives Analysis Report [AAR]) or partial design submittals (e.g., 35 percent Detailed Design) to advance the project's schedule and budget. Also to the benefit of the active projects is a Project Controls team that works closely with Project Managers to track the health of the project in a quantitative manner that produces data for capital planning and reporting purposes. Project budgets and schedules are updated at each project milestone (completion of multiple planning and design phases), and independent cost estimates are frequently performed when additional cost confirmation is desired.

Using data provided by the Project Controls team, the most recently updated budget and schedule for each active project is reviewed by a multi-discipline team from WE's Operating Divisions and Infrastructure, similar to the team that was assembled to vet new candidate projects. The project budget and schedule are prepared using a detailed nine-project-phase structure. The structure includes: 1) project management; 2) planning; 3) environmental; 4) ROW; 5) design; 6) bid and award; 7) construction management; 8) construction; and 9) closeout, and each phase is evaluated for overruns and underruns using earned value management principles.

The active project budgets account for contingencies and reserves; however, the ranges and percentages of contingencies are reduced compared to those used for new candidate projects, in a manner commensurate with the project's maturity level. Cost estimates follow the guidelines of AACEI and typically include estimates from Class 4 through Class 1 as the project matures from the conceptual level to a complete design ready for advertisement.

Additionally, the outage assumptions for each active project are reviewed by WE's Operating Divisions, and adjustments are made to the project's scope, schedule, and budget if necessary. Because large capital projects typically span multiple years, outage assumptions for each active capital project are reviewed with each CIP development cycle. This review is completed to determine whether the previously documented outage assumptions remain valid, recognizing that operational circumstances can change over long periods of time (years) for a host of reasons that range from emergency repairs to extreme drought or flood.

At the end of this exercise, the active project's budget and schedule is adjusted accordingly and updated into Unifier so it can be further evaluated side by side with the new candidate projects for deliverability and priority.

2.2.1.3 <u>Confirmation of Deliverability</u>

For all active projects managed by Infrastructure, each bureau within Infrastructure (Project Management Bureau; Engineering Management Bureau; Construction Management Bureau; Environmental Management Group; Project Controls; and Contracts Administration Bureau) reviews each project to confirm that resources are and will continue to be available to support each project. First, the availability of project team leaders is confirmed by reviewing assignments for Project Manager, Project Engineer, Resident Engineer, Environmental Project Manager, and Project Controls Engineer. This is performed by Bureau Managers, who confirm that leadership is in place and that team leaders have adequate availability for each project. The remaining resources needed for the project are then evaluated. This is generally performed by reviewing the project's budget for soft costs and comparing it to the schedule for the planning, design, and construction phases. The number and classifications of staff are estimated from the budgets (such as the number of engineers for each discipline needed for design of each project) for each phase of the work. Then Bureau Managers total the staff estimates and compare them to current staffing levels to determine whether existing staffing is available to successfully implement the projects according to the planned budgets and schedules.

If internal (SFPUC) resources are not available to execute projects, outside resources from other San Francisco Chapter 6 departments (CCSF departments that perform construction projects), such as the San Francisco Department of Public Works, are offered the opportunity to support the projects. If no Chapter 6 department has the necessary resources available, professional service contracts are considered and confirmed. For each active project, it is determined whether professional service contracts are needed for planning, design, or construction management support. Existing contracts are identified for availability, reserving a portion of each contract's authority for relevant designated projects. Identification of new contracts and inclusion of the contract procurement timeline during project planning is important, especially for professional services contracts, because procurement may take 1 year or longer. Future potential contracts are identified by Project and Bureau Managers and communicated to Contracts Administration staff, who support the procurement process; Contracts Administration workloads are evaluated on an 18- to 24-month look-ahead basis to accommodate future contracting needs.

Active projects maintain detailed Project Management Plans that are updated whenever the project moves to a new phase. Key project leaders are listed, and resource requirements are detailed for the current phase. This is a useful tool for confirming deliverability as the project progresses.

During the capital planning process, new and candidate projects are not evaluated for deliverability until after the existing active projects are confirmed. Then candidate projects can be added into the deliverability review to see if there is sufficient resource capacity to initiate new projects. Infrastructure may comment back to WE that resources are or are not available to initiate the new project, in which case the project may be delayed or deferred until resources can be made available.

2.2.2 Capital Prioritization Process Overview

New candidate projects and active projects are uploaded into a master database with the scope, schedule, and budget that was developed during the previous steps of the planning process. The database also includes narratives for justification and statements of impact to operations. Projects are then assigned a criticality ranking based on criteria and methodologies specific to each of WE's Operating Divisions. The criticality ranking is based on multiple factors, which include:

- active project versus new candidate project;
- remaining useful life and LOF of the asset(s);
- COF;
- contribution to LOS;
- project impacts to other projects within 10 years;
- regulatory requirements;
- environmental and community benefits;
- safety to the public and SFPUC personnel; and
- financial impacts.

Using a scoring system, WE staff meet to score projects, developing a criticality score for the project and the overall ranking for all projects. The criticality ranking is used to inform choices about which projects to assign financial, staffing, and contracting resources.

2.2.3 Optimizing and Balancing the 10-Year Capital Improvement Plan

Once the projects are vetted, resources confirmed, and priorities set, the same multi-discipline team from both WE and Infrastructure begin the process of balancing the 10-year CIP to the financial targets established by Finance. Several iterations and refinements of the CIP master schedule are necessary between WE, Infrastructure, and Finance staff to balance CIP priorities, financial projections, strategic planning, management considerations, and operational needs. Iterations and refinements may include adjusting scopes and schedules to bring the 10-year CIP within financial targets.

In addition to adjusting the project's scopes and schedules, the team also looks for creative solutions to optimize the capital plan. The goal of the optimization process is to reduce system risk while still meeting affordability targets set by the Finance. Optimization concepts typically include 1) leveraging WE's Operating Divisions' R&R teams to complete small projects to accommodate deferment of large capital projects; 2) partially encumbering large construction contracts over multiple years to reduce the amount of unspent funds in a single FY; 3) identifying alternate resource plans to improve deliverability; and 4) realigning budgets from projects that are forecast to underspend or have closed.

3. Asset Management Program Status

WE remains focused on meeting the Levels of Service while applying strategic asset management tactics that minimize operating costs and system risks to benefit the rate payers. Section 2.1 presented the multi-year Asset Management strategy adopted by SFPUC in 2020, which will achieve consistency across the entire WE while also aligning its Asset Management practices with the SFPUC policy. Recognizing that this is a multi-year effort, WE made progress this reporting cycle to advance its Asset Management business practices. This section summarizes notable activities from recent reporting periods for WE overall, and for individual Divisions where noted.

3.1 Asset Risk Management

Objective #1. *Develop a Risk Framework that standardizes the use of COF and LOF as the main drivers for determining system risk throughout WE.*

Status and Update:

WE continues to transition to a risk-based capital planning strategy that will leverage its asset management data to forecast and prioritize future capital projects. The strategy involves summarizing WE infrastructure and establishing a probability of failure based on age and condition, and estimating a cost for replacement. When such a model is fully developed, WE will have the ability to communicate risks associated with the acceleration or deferment of capital investments, allowing for the opportunity to optimize its capital planning efforts. During the reporting period, WE further validated its asset registry data, conducted condition assessments of key infrastructure, and agreed on standardization of asset failure modes throughout WE. These accomplishments are key foundational steps in the transition to a risk-based capital planning strategy.

Objective #2. *Maintain Emergency Action Plans (EAPs) for all WE Divisions.*

Status and Update:

WE has EAPs in place for all of its regulated dams. The California Governor's Office of Emergency Services (Cal OES) has approved all EAPs that are currently in place. WE staff are also trained in the Incident Command System (ICS), and key facilities have pre-deployed emergency response materials to improve efficiency immediately following an event. WE staff managed the early 2023 winter storms using ICS and complied with the Federal Emergency Management Agency's (FEMA's) reimbursement processes for the initial emergency response and rehabilitation work. WE divisions continue to develop and refine predeployment emergency response materials to improve efficiency immediately following an event.

Objective #3. Further develop and maintain a risk register in CMMS, including a score for COF, LOF, and Risk.

Status and Update:

WE continues to work toward a risk framework that will be used to assign scores to each asset in Maximo. WE divisions are at various stages of development on this objective.

HHWP has a risk framework in place, is beginning to implement the framework for capital planning purposes, and is currently feeding "asset level" information into the risk model using Location Systems in Maximo.

WSTD is working on developing COF and LOF, starting with our pump station assets. This effort is expected to take up to 4 years to develop, working with consultants. Other assets will follow. Capital project prioritization currently relies on qualitative assessments from internal and external subject matter experts.

3.2 Asset Management and Maintenance Roles and Responsibilities

Objective #1. *Develop an asset change management process.*

Status and Update:

WE maintains a complex, diverse, and ever-evolving portfolio of assets. Continual process improvement is critical to ensure that WE meets its asset management objectives now and into the future. In the spirit of continual process improvement and integration of asset management policies and programs, WE has an interdivisional Asset Management Steering Committee (AMSC). The purpose of AMSC is to ensure integration and alignment of asset management programs, policies, and procedures, to the extent feasible, within WE. To assist in fulfilling its purpose, AMSC may develop a specific Task Force to address the objectives listed in Section 2.1.1. Each Task Force will comprise subject matter experts from each division. Such a Task Force has been developed to address the asset framework effort that is nearing completion.

Objective #2. *Develop WE and Division-level matrices to clearly outline roles and responsibilities for asset management and O&M staff.*

Status and Update:

WE's progress toward this objective is at various stages. In May of 2024, the WE began the development of a SAMP that will clearly outline asset management roles and responsibilities.

HHWP completed an end-to-end review of current business processes related to asset management, including the review of current procedures for alignment with "best practices." Complementing this work, asset management roles and responsibilities are being codified through the development of role and responsibility matrices for each business process, ensuring adequate staffing and training levels within the division.

In October 2020, WSTD developed Asset Management Procedures that defined asset management roles and responsibilities within WSTD and established procedures for managing and maintaining assets in Maximo. Because the majority of WSTD's assets come from capital projects or job order contracts (JOCs), WSTD has been working closely with Infrastructure staff to improve the delivery of assets from design and construction to O&M. Progress made in this reporting cycle includes the SVWTP Ozonation Project, which is expected to add nearly 1,000 assets. WSTD has been involved early in the design phase to ensure that the asset registry and preventative maintenance program are completed prior to the facility being turned over to operations.

NRLMD has hired a consultant team to assist with its efforts at identifying and formalizing asset classifications and databases, including outlining roles and responsibilities for asset management for NRLMD.

3.3 Asset Management Objectives

Objective #1. Establish Asset Management Objectives for WE that map back to SFPUC's Asset Management Policy.

Status and Update:

WE established Asset Management Objectives that will be further codified in the upcoming WE SAMP.

Objective #2 – *Review the objectives to meet the system's operational needs at least once every 2 years.*

Status and Update:

WE reviewed the Asset Management Objectives; no updates are recommended this reporting cycle. Objective achieved.

Objective #3. Report on the status of the Asset Management Objectives once every 2 years.

Status and Update:

WE provided updates to all Asset Management Objectives. Objective achieved.

3.4 Asset Registry

Objective #1. *Continue to develop and maintain a detailed asset registry with increased standardization and uniformity across WE (asset classification, subclassification, specifications, and taxonomy).*

Status and Update:

WE maintains asset registries of varying levels of development. WE is making significant progress in standardizing asset data throughout WE, using a consistent format that includes asset classifications, subclassifications, failure modes, asset taxonomy, and attribute information. A standardized "drill down" structure in Maximo has been established to increase uniformity across the WE when entering asset records. HHWP and WSTD asset registries are reasonably well defined, detailed,

and are used at all levels to inform O&M decisions, as well as project work. Both divisions maintain asset registries comprising tens of thousands of asset records and related attributes, as well as asset classification, subclassifications, and failure modes.

HHWP is currently working with a consultant to "recast" all asset records so they meet the newly established WE format/framework and include asset classifications, subclassifications, failure modes, asset taxonomy, and attribute information for more than 15,000 asset records.

WSTD has completed its asset registry and preventative maintenance program at SVWTP, which includes functional location hierarchies and failure codes for all assets. WSTD is currently working on the asset registry and preventative maintenance program at HTWTP, with completion expected by the end of 2024. This will mark the completion of the asset registry for all WSIP projects.

NRLMD has hired a consultant team and begun the process of creating a pilotlevel inventory of assets that it is responsible for managing.

Regardless of current maturity level, there is an effort throughout WE to move together toward a common framework for its asset management practices (facilitated by a consultant). The effort is focused on the foundational levels of EAM, following the Asset Management Pyramid depicted in Figure 3-1. Two building blocks of EAM were examined in detail by the consultant for implementation of the framework:




Figure 3-1: Asset Management Pyramid

Objective #2. *Develop a shared definition of an "asset" throughout WE.*

Status and Update:

CCSF's Controller's Office Policy and Procedures Manual has a detailed definition of "fixed" assets. Generally, items that are "used in operations," "have a useful life over one year," and have an initial value greater than \$5,000 are considered assets by city definition and are treated as such. WE's definition for what constitutes an asset for inclusion in Maximo is included in WSTD's October 2020 Asset Management Procedures; a standardized definition beyond this, for use throughout WE, will be included in the WE SAMP.

Objective #3. Continue to use and standardize location and functional/location hierarchies within CMMS and GIS.

Status and Update:

WE continues to standardize multiple datasets in CMMS and GIS, including functional location hierarchy. This is being accomplished both through the interdivisional asset framework and asset registry update efforts, which include representatives from across WE. The AMSC will also influence how GIS is used as an asset management tool and will set standards for uniformity across WE. WE has advanced its GIS databases over the reporting cycle, using internal staff and securing multiple professional services task orders that will continue to support WE into the next reporting cycle.

HHWP is midway through an update of more than 10,000 assets records in Maximo and is preparing to complete an audit of these assets to confirm consistency throughout the dataset. The audit will be performed using facility walkdowns and CMMS data reviews. Functional hierarchies will also be improved through the development and review of HHWP AMPs and facility walkdowns.

WSTD's transmission and distribution pipeline, line valve, and vault assets are in both Maximo and GIS. WSTD has been collecting and updating pipeline appurtenance data in both Maximo and GIS as part of the Regional Cross-Connection Controls Project (RCCCP).

Objective #4. *Develop and maintain a GIS database for WE's linear assets.*

Status and Update:

WE made significant investments into advancing the GIS databases. The GIS database was advanced to include enterprise web maps and dashboards for viewing pipeline asset data; the ability to search using mile marker, SFPUC placename, pipeline station, and/or appurtenances; and the ability to spatially link from the web map to SharePoint to access pipeline drawings and documents for SJPLs, power transmission lines, and underground utilities. In the Bay Area, the GIS database provides support for critical programs such as pipeline

inspection, Underground Service Alert, emergency response, and hydraulic modeling. It has become a component in succession planning because of its ability to share linear asset data intuitively with new employees. There are also numerous GIS-based displays that can be used to view work orders in the office or on mobile devices in the field.

3.5 Asset Condition

Objective #1. *Complete planned and scheduled asset condition assessments that inform maintenance, investment, and risk mitigation strategies.*

Status and Update:

WE completed multiple condition assessments during this reporting cycle. WE recognizes the value of this objective and intends to continue making progress during the next reporting cycle.

HHWP continues to make condition assessments through asset maintenance inspections, annual shutdowns, and assessments conducted by outside consultants. These assessments are cataloged in maintenance engineering, Asset Management Services, or records. They are also used to inform maintenance, operations, and capital investment strategies.

WSTD completed condition assessments for its eight pump stations.

Objective #2. *Prioritize condition assessments to increase system reliability.*

Status and Update:

WE recognizes the value of this objective and intends to make progress during the next reporting cycle. WE currently does not have a written prioritization strategy for performing condition assessments. WE intends to review individual condition assessment program-level documents, such as WSTD's approach for performing inspection and condition assessments of its linear assets, to assist in the development of a condition assessment prioritization strategy that is consistent across WE and applicable to both linear and fixed assets.

HHWP regularly conducts condition assessments through maintenance inspections conducted by HHWP employees, as well as outside engineering firms. Condition assessments are prioritized by LOS, risk modeling, and feedback from the field through annual preventative and corrective maintenance work.

3.6 Operations and Maintenance Strategies

Objective #1. *Develop an SAMP and individual AMPs.*

Status and Update:

In May of 2024, the WE began development of a WE SAMP.

HHWP is nearing completion of our powerhouse AMP. Additionally, HHWP completed a full audit of our Penstock and Communications AMP. Quarterly meetings for each AMP occur with engineering, maintenance, and operations staff.

WSTD is working on our first AMP for our pump stations. AMP development will be a decade(s)-long effort driven by availability of funding and resources. WSTD is evaluating the gap in resources and funding required to meet this objective and will include it as a proposal in the next budget cycle.

Objective #2. *Establish the ability to use CMMS to demonstrate compliance with federal, state, and local regulatory requirements.*

Status and Update:

WE is making progress on this objective, focusing on both HHWP and WSTD. HHWP and WSTD have a maturing capability to use Maximo data to provide evidence of compliance for multiple regulators and have incorporated regulatorydriven preventive maintenance (PM) requirements in their Maximo databases. The PM completion records are regularly used by HHWP and WSTD facility managers to demonstrate compliance with federal, state, and local regulatory requirements during inspections and audits. Additionally, WE was able to use CMMS data to support reimbursement for declared emergencies during the reporting period.

HHWP has deployed mobile Maximo to a portion of field staff and has tested the use of electronic work orders and inspection forms for regulatory work and condition assessments.

WSTD has deployed Mobile Maximo to all field and trade staff so the process of documenting work on site may be streamlined by attaching inspection forms, taking photographs, and entering work logs while also adding relevant information to assets such as equipment data sheets and O&M manuals for reference. WSTD is in the process of working with the SFPUC Information Technology Services department to implement another mobile application that would allow regulatory inspectors to access compliance reports more efficiently.

Objective #3 -Demonstrate proper stewardship of environmental resources under SFPUC control through the use of CMMS reporting.

Status and Update:

Maximo is an integral tool used to meet WE's environmental stewardship policy objectives of protecting sensitive environmental, cultural, and tribal resources. To ensure that sensitive resources remain protected during operational activities, environmental review and regulatory permitting requirements are integrated into WSTD and HHWP work planning and implementation using Maximo. Input received from state and federal partners during interagency coordination efforts is also embedded in the Maximo workflow. Key WE staff who participate in this process include environmental planners, maintenance planners, supervisors, and managers. CMMS reports demonstrate the integrity of WE's environmental review processes.

3.7 Asset Investment Strategies

Objective #1. Use asset management data to develop expenditure reports that compile costs for facilities, assets, and maintenance programs.

Status and Update:

HHWP has begun tracking the ten most expensive work orders, facilities, and assets through the use of CMMS data. HHWP is also tracking the cost of each unit shutdown year over year. This information is reviewed monthly by Asset Management Services staff and reported annually to the HHWP management team.

Additional staffing in WSTD will be necessary to make progress on this and some of the other objectives of the Asset Management Program. A proposal for resources will be included in the next budget cycle.

Objective #2. Develop and implement a replacement planning approach to estimate asset useful life, renewal, and replacement requirements and costs.

Status and Update:

HHWP's approximately 16,000 assets were summarized into approximately 1,200 assemblies. For each of these assemblies, HHWP calculated a percentage of useful life (age divided by expected life). Additionally, a high-level cost estimate for replacement was completed for each assembly. Also, HHWP has started using AMPs as a tool to review and update the estimated end of life data field in Maximo.

WSTD is working toward obtaining asset cost data and useful life estimates for new capital assets. There are currently no cost data or estimates of asset useful life for WSTD's assets in Maximo. **Objective #3.** Design future facilities based on information gathered through the asset management program.

Status and Update:

WSTD uses information gathered through the asset management program to inform future designs on a regular basis by providing input to capital projects. In this reporting period, WSTD obtained approval from the Commission to solesource metering pumps for the next 8 years at WSTD water treatment facilities. Performance reliability was the primary driver. However, WSTD was able to use maintenance and purchasing records in Maximo to show that, when sourced from other vendors, positive displacement pumps used as chemical metering pumps had three times the maintenance costs of the sole-sourced metering pumps. Additionally, WSTD and HHWP have begun partnering with the Engineering Management Bureau to begin integrating during the project design phase.

3.8 Budgeting

Objective #1. Update the 10-Year CIP and annual operating budget by integrating data from condition assessments, estimates of remaining useful life, failure analyses, replacement costs, maintenance programs, and LOS into a well-informed forecast of Capital and R&R Program costs.

Status and Update:

HHWP currently integrates critical CMMS data to formulate budgets and inform capital investment planning. We work annually to improve this process to gain greater accuracy and a more refined capital investment plan, supported by the risk tool and executive team meetings and evaluations.

WSTD performed condition assessments on pump stations, certain sections of pipelines, three out of five DSOD jurisdictional dams, and most of the critical switchgear/switchboards for key facilities. Data gathered informed the FY2025-2034 CIP, R&R program priorities, scope, cost, and schedule. Significant progress is still needed that includes all the elements described in the objective for all groups of assets.

Objective #2 *–Develop expenditure reports that compile costs for facilities, assets, and maintenance programs – a quick way to tell where money is going and what it is accomplishing.*

Status and Update:

HHWP currently tracks the 10 most expensive assets, locations, and work orders, as well as unit shutdown cost. Staff are briefed weekly as this information is generated.

3.9 **Performance Monitoring**

Objective #1 – Formalize asset failures analysis and root cause analysis across WE.

Status and Update:

WE has standardized the use of failure modes in Maximo to align with asset classification and the corresponding problem cause and remedy.

HHWP maintains a current business process for root cause analysis using CMMS.

WSTD performs root cause analysis for failures that impact the RWS performance or regulatory compliance. These incident reports are completed by operational staff.

Objective #2. *Complete peer reviews of maintenance programs to ensure that the scope of maintenance is consistent with industry standards and create opportunities to increase standardization and uniformity across the WEEAM Programs*

Status and Update:

WE's development of AMPs supports a peer review of its maintenance programs and supports alignment with industry standards; the consultant subject matter expert performs work structure breakdown reviews, asset registry audits, and asset hierarchy reviews.

WSTD is working on our first AMP, including peer review for our pump stations. AMP development will be a long-term effort driven by availability of funding and resources. WSTD is evaluating the gap in resources and funding required to meet this objective and will include it as a proposal in the next budget cycle.

Objective #3. *Establish and maintain Key Performance Indicators to track planning and scheduling, asset, and asset management efficiency and effectiveness.*

Status and Update:

HHWP began using Maximo Scheduler to ensure that asset maintenance priorities are met efficiently and effectively. On a weekly basis, schedule compliance is measured, briefed, and discussed with crew supervisors.

3.10 Levels of Service

Objective #1 – *Review LOS every odd year.*

Status and Update:

WE made significant updates to LOS during this reporting period. The updates can be found in Section 2.1.2 of this report.

4. Asset Description, Maintenance and Condition, and Capital Improvements

This section is organized by the primary asset types that make up the RWS:

Water Storage	Water Treatment	1
Water Distribution	Buildings and Grounds	
Power Transmission	Power Distribution	1
Wastewater Treatment	Communications and Control	

Water Transmission Power Generation Watersheds, Roads, and Bridges

For each asset type, SFPUC is providing 1) a description of the assets; 2) a summary of the maintenance completed and condition; and 3) information on the asset's active or planned capital investments.

WE is actively working to review and update its PM records. The effort is anticipated to take 5 years, with 2022 being year 1. As this effort progresses, so will the information provided in the SRWS report.

For the purposes of the SRWS report, the capital improvement sections include 1) a summary of the scope of work; 2) an explanation of how the capital investment aligns with WE's LOS; and 3) a summary of the project milestones that were achieved during the current reporting cycle.

4.1 Water Storage Assets

SFPUC owns and operates multiple dams to store water both upcountry and locally in the greater Bay Area region. For asset classification purposes, outlet piping, valves, and spillways are considered part of the dams. These dams are regulated by the State of California's DSOD.

4.1.1 Hetch Hetchy Water

HHWP is responsible for the maintenance and operation of six dams. The dams include medium head dams that are used as regulating reservoirs, as well as larger high head dams that provide water storage for the RWS.

4.1.1.1 Asset Descriptions, Maintenance, and Condition

O'Shaughnessy Dam

Description. The RWS begins in the Hetch Hetchy Valley of Yosemite National Park at O'Shaughnessy Dam and Hetch Hetchy Reservoir. O'Shaughnessy Dam is a 312-foot-high abovestreambed (430 feet above the lowest point in the foundation) gravity arch dam that impounds 360,360 acre-feet (AF) of water along the main stem of the Tuolumne River, creating Hetch Hetchy Reservoir. The dam was originally built in 1923 and raised in 1938. Hetch Hetchy Reservoir collects water from the surrounding 459 square miles of the Hetch Hetchy watershed for the purpose of providing potable water supply to the Bay Area and power generation at Kirkwood and Moccasin Powerhouses.

Maintenance. Table 4-1 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Valve Exercise	Completed annually	Annual exercise of Valves 1 through 8, 12, 15, and 16 (Note: Valve 13 is out of service and pending replacement.)
Vegetation Management	As needed	Removal of vegetation on dam, along groins and near leakage weirs
Inspection	Completed weekly	Inspected by watershed keepers
	Completed annually	Inspected by safety engineer
Surveillance and Monitoring	Continuously monitored	Reservoir water levels and releases via SCADA alarms
	Completed weekly	Leakage weir readings
	Completed annually	Joints, settlement, and deflection surveys

Table 4-1: O'Shaughnessy Dam Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. The dam's concrete is in good condition; however, much of its mechanical equipment has exceeded its anticipated useful life and requires capital improvement. This includes the face valves, instream flow release (IFR) valves, slide gates, and bulkheads. Currently, one of the two IFR valves does not operate; however, normal dam operations can be performed with only one IFR valve in operation. The bulkheads (aka shutter gates) are also nonoperational, which impacts HHWP's ability to perform maintenance on the supply wells and slide gates. Additionally, many of the dam's access structures and drainage systems are inadequate and require capital investment. O'Shaughnessy Dam is fit for service; however, its mechanical equipment requires capital investment to ensure reliable future operations. There are multiple capital projects planned to address these deficiencies.

Cherry Valley Dam

Description. Cherry Valley Dam is a 315-foot-high earth and rock fill dam, measured from crest to the streambed. Lake Lloyd, the reservoir impounded by Cherry Valley Dam, stores approximately 273,500 AF. The dam was built in 1955. Water from the Cherry-Eleanor system is used for downstream flow obligations and power generation at Holm Powerhouse. With treatment and prior DDW approval, water from Lake Lloyd can be used to provide additional water supply in drought or emergency conditions.

Maintenance. Table 4-2 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Valve Exercise	Completed monthly	Exercise Butterfly Valves 1 and 2
	Completed monthly	Jet Flow Valves 1 and 2
	Completed annually	Exercise of Butterfly Valve 3
Vegetation Management	As needed	Removal of vegetation on dam, along groins and near leakage weirs
Inspection	Completed weekly	Inspected by watershed keepers
	Completed annually	Inspected by safety engineer
Surveillance and	Continuously monitored	Reservoir water levels and releases via SCADA alarms
Monitoring	Completed weekly	Leakage weir readings
	Completed annually	Settlement and deflection surveys

Table 4-2: Cherry Valley Dam Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Cherry Valley Dam is in satisfactory condition; however, the intake tower to Cherry Power Tunnel requires rehabilitation. Additionally, the spillway is unable to pass the facility's design flood. As a result of the spillway condition, HHWP has implemented a FIRO strategy to avoid spill. Cherry Valley Dam is fit for service, with a capital project to address these deficiencies.

Lake Eleanor Dam

Description. Eleanor Dam is a 61-foot-high concrete buttressed arch dam, measured from dam crest to streambed. Lake Eleanor stores approximately 27,113 AF (capacity with flashboards). The dam was built in 1918. Water from the Cherry-Eleanor system is used for downstream flow obligations and power generation at Holm Powerhouse. With treatment and prior DDW approval, water from the Lake Eleanor can be used to provide additional water supply in drought or emergency conditions.

Maintenance. Table 4-3 summarizes maintenance work.

Table 4-3: Lake Eleanor Dam Preventive Maintenance Summary		
(July 1, 2022, through June 30, 2024)		

Name of PM	Completion Date(s)	Description
Valve Exercise	Completed annually	Annual exercise of Slide Gates 1 through 4 and Guard Valves 3A and 4A
Vegetation Management	As needed	Removal of vegetation on dam and along groins
Inspection	Completed weekly	Inspected by watershed keepers
	Completed annually	Inspected by safety engineer
Surveillance and	Continuously monitored	Reservoir water levels and releases via SCADA alarms
Monitoring	Completed annually	Settlement and deflection surveys

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Condition. Lake Eleanor Dam is in satisfactory condition and is fit for service; however, the facility requires capital investment to address the condition of the bridge, as well as concrete and erosion protection. There are multiple capital projects to address these deficiencies.

Early Intake Dam

Description. Early Intake Dam is a 56-foot-high concrete arch dam, measured from the crest to streambed. The dam impounds a storage volume of about 115 AF. The dam was built in 1924. Located on the mainstem of the Tuolumne River immediately downstream of Kirkwood Powerhouse, the dam provides the flexibility to divert water from the Tuolumne River or diversions from Lower Cherry Aqueduct (LCA) into Mountain Tunnel. With treatment and prior DDW approval, water diverted at this dam into the RWS can be used to provide additional water supply in drought or emergency conditions.

Maintenance. Table 4-4 summarizes maintenance work.

Name of PM	Completion Date(s)	Description	
Valve Exercise	Completed annually	Annual exercise of Sluice Gates 1 and 2, and Guard Gates 1 and 2	
Vegetation Management	As needed	Removal of vegetation on dam and along groins	
Inspection	Completed weekly	Inspected by watershed keepers	
	Completed annually	Inspected by safety engineer	
Surveillance and	Continuously monitored	Reservoir water levels and releases via SCADA alarms	
Monitoring	Completed biannually	Cracks, settling, and deflection surveys	
	Completed annually	LiDAR surveying of dam movement and crack mapping	

Table 4-4: Early Intake Dam Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

LiDAR = Light Detection and Ranging

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Early Intake Dam is in poor condition. The dam's concrete has a well-documented history of alkali aggregate reaction, which has resulted in cracking and joint failures at the lift lines. Additionally, during the planning phase of the "Interim Improvements Project," a potential stability issue was discovered, which has resulted in abandoning the interim repair project to accelerate the long-term improvements project. The dam is still capable of diverting water from LCA into Mountain Tunnel if an alternative water source for consumption by RWS customers is needed; however, the dam is nearing the end of its useful life, and capital investment is required.

Priest Dam

Description. Priest Dam is a 170-foot-high earth and rock dam, measured from crest to downstream toe. The dam impounds a storage volume of 1,706 AF. The dam was built in 1923.

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Priest Reservoir stores Hetch Hetchy water before it reaches Moccasin Powerhouse via Moccasin Power Tunnel. Priest Reservoir has a pipeline bypass that can be used when local reservoir turbidities are high, typically during and following storm events.

Maintenance. Table 4-5 summarizes maintenance work.

Table 4-5: Priest Dam Preventive Maintenance Summary (July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Valve Exercise	Completed annually	Annual exercise of Bypass Butterfly Valve, Slide Gates 1 and 2, and Drain Valve
Vegetation Management	As needed	Removal of vegetation on dam, along groins and near leakage weirs
Inspection	Completed weekly	Inspected by watershed keepers
	Completed annually	Inspected by safety engineer
Surveillance and Monitoring	Continuously monitored	Reservoir water levels, inflows, and releases via SCADA alarms
	Completed weekly	Leakage weir readings
	Completed monthly	Piezometers
	Completed biannually	Settlement and deflection surveys

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Priest Dam is in satisfactory condition and is fit for service. The dam has a history of settlement and deflection, most of which occurred early in the dam's life cycle. HHWP is currently conducting the geotechnical investigation to document the dam's material characteristics so the dam stability analysis can be refreshed. Once the investigation is complete, additional geotechnical instrumentation will be installed to monitor dam performance.

Moccasin Dam

Description. Moccasin Dam is a 60-foot-high earth and rock dam, measured from crest to downstream toe. The dam impounds a storage volume of 552 AF. The dam was built in 1929. After leaving Moccasin Powerhouse, RWS water is stored at Moccasin Reservoir to provide a constant flow rate in Foothill Tunnel. Moccasin Reservoir includes a bypass pipeline that connects Moccasin Powerhouse with Foothill Tunnel and can be used when local reservoir turbidities are high or when performing maintenance at Moccasin Reservoir.

Maintenance. Table 4-6 summarizes maintenance work.

Table 4-6: Moccasin Dam Preventive Maintenance Summary (July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Valve Exercise	Completed annually	Annual exercise of Gates 1, 1A, 2, 2A, and 3
Vegetation Management	As needed	Removal of vegetation on dam, along groins and in spillway
Inspection	Completed weekly	Inspected by watershed keepers
	Completed annually	Inspected by safety engineer
Surveillance and Monitoring	Continuously monitored	Reservoir water levels, inflows, and releases via SCADA alarms
	Completed weekly	Leakage weir readings
	Completed monthly	Piezometers
	Completed biannually	Settlement and deflection surveys

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Moccasin Dam is in satisfactory condition; however, the spillway is undersized and is not capable of passing the updated design flood that resulted from the March 2018 storm. The dam is fit for service, with a capital project to address these deficiencies.

4.1.1.2 <u>Capital Improvements</u>

HHWP currently has capital projects in its water storage program, representing a total capital investment of \$604.1 million. HHWP also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

O'Shaughnessy Dam Outlet Works Phase I (Approved Budget \$43.7 Million; Substantial Completion: 2025)

Scope. The project includes four subphases: 1) replacement of two IFR valves; 2) improvements to access and address drainage in the gallery and stairs; 3) installation of new bulkheads; and 4) the planning phase for the slide gate and drum gate rehabilitation. Subphase (2) has been split into four separate construction packages: a. HH-1002R – O'Shaughnessy Dam Fall Protection Improvements and Spillway Access; b. JOC-94-02 – O'Shaughnessy Dam Lights and Wiring Improvements; c. HH-1015 – O'Shaughnessy Dam Drainage and Miscellaneous Improvements; and d. supply well crack remediation (the preliminary planning phase was initiated, but no milestones were completed during this reporting period).

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-7.

Table 4-7: O'Shaughnessy Dam Outlet Works Phase I Project Milestones Completed During the		
Current Reporting Cycle		

Milestone	Date Complete
Bulkheads. CatEx	December 2022
Bulkheads. DB-135 NTP – Design	September 2023
Bulkheads. Basis of Design Report	December 2023
Bulkheads. 50% Design	February 2024
Bulkheads. 95% Design	February 2024
Bulkheads. 100% Design	April 2024
Bulkheads. DB-135 NTP – Construction	May 2024
JOC-94-02 O'Shaughnessy Dam Lights and Wiring Improvements - NTP	February 2024
HH-1015 Drainage and Miscellaneous Improvements - 100% Design	January 2024
Instream Flow Release. Conceptual Engineering Report (Final)	September 2022
Instream Flow Release. 100% Design	March 2023
Instream Flow Release. HH-1011 NTP	August 2023
Instream Flow Release. HH-1011 – installation of two knife gate valves	February 2024

Notes:

CatEx = categorical exclusion JOC = job order contract NTP = Notice to Proceed

O'Shaughnessy Dam Outlet Works Phase II (Approved Budget \$184.1 Million; Substantial Completion 2041)

Scope. The scope of Phase II includes: 1) replacement of six 60-inch and one 72-inch needle valves; 2) refurbishment of one 72-inch butterfly valve; 3) rehabilitation of three drum gates; 4) refurbishment or replacement of 12 slide gates (beginning with design phase); 5) installation of a new 108-inch diversion pipe isolation valve; and 6) improvements to the division tunnel.

Milestones Completed During the Reporting Cycle. The project is scheduled and budgeted to begin in 2025; therefore, no milestones were achieved during this reporting cycle.

HH-1002 O'Shaughnessy Dam Fall Protection Improvements and Spillway Access (Approved Budget \$3.9 Million; Substantial Completion 2022)

Scope. The scope of this project was reduced to only access improvements, including fall protection systems that meet Occupational Safety and Health Administration requirements for multiple ladders and landings; and to improve personnel access to the spillway.

Milestones Completed During the Reporting Cycle. The milestone achieved during this reporting cycle is summarized in Table 4-8.

Table 4-8: O'Shaughnessy Dam Fall Protection Improvements and Spillway Access ProjectMilestones Completed During the Current Reporting Cycle

Milestone	Date Complete
HH-1002R – Construction Final Completion	January 2023

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Cherry Dam Spillway – Short-Term Improvements (Approved Budget \$14.9 Million; Substantial Completion: 2027)

Scope. The scope of this project is to re-establish containment of the breached spill channel from the 2010 spill; and to install armoring to protect the upper spill channel section against erosion from spillway releases of up to 2,000 cfs.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-9.

Table 4-9: Cherry Dam Spillway – Short-Term Improvements Project Milestones Completed During the Current Reporting Cycle

Milestone	Date Complete
Geotechnical Investigation of soils	October 2023
Hydraulic modeling of cfs in the spillway for DSOD	March 2024
Preliminary design to redirect spillway flows	June 2024

Notes:

cfs = cubic feet per second DSOD = Division of Safety of Dams

Moccasin Dam and Reservoir Long-Term Improvements (Approved Budget \$142.2 Million; Substantial Completion 2034)

Scope. The project will involve construction of a new concrete spillway, with adequate flow capacity along the alignment of the existing auxiliary spillway and additional flood protection of the Moccasin project facilities.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-10.

Table 4-10: Moccasin Dam and Reservoir Long-Term Improvements Project Milestones
Completed During the Current Reporting Cycle

Milestone	Date Complete
Geotechnical investigation of soils (Phase 1)	August 2023
Hydrological study of cfs probable maximum flood event	March 2024
Hydraulic modeling of cfs in the dam and spillways for DSOD	May 2024
AAR completed	January 2024
CER started	January 2024
Environmental reviews for project design started	January 2024

Notes:

AAR = Alternatives Analysis Report

CER = Conceptual Engineering Report

cfs = cubic feet per second

DSOD = Division of Safety of Dams

Early Intake Dam Interim Improvements (Approved Budget \$1.3 Million; Substantial Completion: Not Applicable)

Scope. The objective of the Interim Improvements project was to extend the life of Early Intake Dam by 20 to 25 years so that the long-term improvements project could be deferred. The scope of the project was budgeted for relatively minor improvements, such as grouting or an upstream liner. Unfortunately, a new stability concern was discovered during the investigation phase of the project that could not easily be remedied by interim measures. In light of the new information, the Interim Improvements project was closed, and the resources were reallocated to accelerate the "Long-Term" project.

Milestones Completed During the Reporting Cycle. There were no milestones achieved by the project during this reporting cycle; work is being completed under the "Long-Term" project.

Early Intake Dam – Long-Term (Approved Budget \$100.1 Million; Substantial Completion: 2035)

Scope. The scope of this project is not confirmed and requires additional planning. The objective of the Long-Term project is to provide a long-term solution for the dam, which has been experiencing significant cracking and deterioration from alkali-aggregate reactivity since construction in the 1920s.

Milestones Completed During the Reporting Cycle. The milestone achieved during this reporting cycle is summarized in Table 4-11.

Table 4-11: Early Intake Dam – Long-Term Project Milestones Completed During the Current Reporting Cycle

Milestone	Date Complete
List of alternatives developed	January 2024

Eleanor Dam Rehabilitation (Approved Budget \$113.9 Million; Substantial Completion: 2038)

Scope. The scope of this project is not confirmed and requires additional planning. Mitigation alternatives may include solutions such as improvements to increase the spill capacity, installation of a liner on the upstream face of the dam, pressure grouting, concrete repairs, valve replacement, and installation of concrete lining and riprap for foundation armoring. During this reporting cycle, it was determined that the scope to repair Eleanor Dam bridge would be moved to this project from the Bridge Replacement project. The Eleanor Dam bridge project updates are reported in the Watersheds, Roads and Bridges asset classification section.

Milestones Completed During the Reporting Cycle. No milestones were achieved during this reporting cycle. Milestone updates for the Eleanor Dam bridge project are reported in the Watersheds, Roads and Bridges asset classification section.

Summary of Levels of Service Project Drivers

LOS drivers for water storage capital improvements are summarized in Table 4-12.

	Level of Service							
Project	Drinking Water Quality	Regional Seismic Reliability	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
O'Shaughnessy Dam Outlet Works Phase I	~					~	~	~
O'Shaughnessy Dam Outlet Works Phase II			~			~		
HH-1002R O'Shaughnessy Dam Fall Protection Improvements and Spillway Access								~
Cherry Dam Spillway - Short-Term Improvements			~			~	~	~
Moccasin Dam and Reservoir Long-Term Improvements	~		~			~	~	
Early Intake Dam Interim Improvements			~					
Early Intake Dam – Long Term			~					
Eleanor Dam Rehabilitation			~			~	~	~

Table 4-12: HHWP Water Storage Projects – Levels of Service Project Drivers

Notes:

HHWP = Hetch Hetchy Water and Power

4.1.2 Regional Water

WSTD is responsible for the maintenance and operation of five dams. The dams, situated in the East and West Bay, are part of a system of local reservoirs that provide water storage for the RWS.

4.1.2.1 Asset Descriptions, Maintenance, and Condition

Calaveras Dam

Description. Calaveras Dam is a 220-foot-high earth and rockfill dam. The original dam was completed in 1925, and a new replacement dam was completed in 2019. Calaveras Reservoir is SFPUC's largest local reservoir. It has a capacity of 96,850 AF and is capable of holding 42 percent of the local storage capacity and 7 percent of the total system capacity. It is filled by direct inflow from Arroyo Hondo and Calaveras Creek, as well as from Alameda Creek via the Alameda Creek Diversion Dam (ACDD) facility. The spillway is an open channel with an ogee crest capable of passing the probable maximum flood (PMF). The outlet works is equipped with three levels of adit valves that provide operational flexibility. A lower fourth adit allows the reservoir to be emptied in an emergency.

Name of PM	Completion Date(s)	Description
Valve Exercise	January 2023 to March 2023, and February 2024	Operating valves V21, V22, V23, V25, V26, V27, V31, V33, and V34 in response to rain events during winter months
Vegetation Management	August 2022 and May 2024 June through October 2022 April through June 2024	Goat grazing Rodent Control
Monthly Inspection	Completed monthly	Frequency of inspection: weekly during rainy season and monthly during non-rainy season, in accordance with the initial fill plan and SOP; until April 2023. After the reservoir fill operation is completed, inspection will occur monthly
Surveillance and Monitoring	August 22, 2022, and monthly survey starting on March 2023 to June 2024	Engineering survey performed by SFPUC

Table 4-13: Calaveras Dam Summary (July 1, 2022, through June 30, 2024)

Notes:

PM = preventive maintenance SFPUC = San Francisco Public Utilities Commission SOP = standard operating procedure

Condition. Calaveras dam is in satisfactory condition. The dam crest is well aligned, and no signs of instability or distress are noted. In addition, the upstream riprap is uniform and intact.

The spillway concrete surface appears to be in satisfactory condition, even though minor spalling and cracking were observed. Some of the sealant area and joint area have started to deteriorate. Minor seepage was observed from the spillway floor. Repair of the concrete defects is being planned. The outlet structure, including the adit valves and controls, was in good condition. No significant concrete cracking, spalling, or signs of structural distress were observed. Minor seepage and mineral deposits were observed inside the intake structure. Vegetation and rodent control were deemed acceptable.

The 2022/23 storm event caused damage to the facility. Damage included erosion on the downstream slope and on the upstream right groin; a sinkhole on an old ranch road, which was not part of the dam; dislodging of spillway floor concrete joint caulking material; and accumulation of fallen debris on Bench C above the spillway hillside. These damages do not affect the stability of the dam. Repairs are underway and are estimated to finish in 2026, with a cost of approximately \$2.8 million.

The dam is safe for continued use.

Turner Dam

Description. Turner Dam, which impounds water at the San Antonio Reservoir, is a 195-foot-high earth embankment dam. San Antonio Reservoir is one of two SFPUC reservoirs in the East Bay.

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

It is the third largest local reservoir, with a capacity of 50,500 AF. The dam, completed in 1965, was constructed on San Antonio Creek, a tributary of Alameda Creek. The reservoir is used to capture and store local runoff. It is also used to store water transferred from Hetch Hetchy Reservoir, Calaveras Reservoir, the South Bay Aqueduct blow-off, and Pond F3 East.

Maintenance. Table 4-14 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Valve Exercise	December 6, 2022	12-month valve exercise for Y01, Y02, Y03, Y04, Y05, Y20, Y21, and Y22
Vegetation Management	August 2022, and May 2024 June through October 2022 April through June 2024	Goat grazing Rodent control
Monthly Inspection	Completed monthly	
Surveillance and Monitoring	July 11, 2022 October 26, 2022 December 28, 2022 June 15, 2023 November 30, 2023	Semi-annual surveillance and monitoring

Note:

PM = preventive maintenance

Condition. Turner Dam is in satisfactory condition. The dam crest is well aligned, and the embankment shows no signs of instability or distress. Vegetation control is acceptable. At the spillway, the concrete shows no significant structural deficiencies. The riprap of the downstream channel is stable and largely intact, with a minor shift in a very small area caused by the 2022/2023 winter storm. Rodent control is satisfactory, with no significant burrowing activity observed. Heavy erosion can be observed on the only access road to the inlet gallery. The erosion repair work is currently in the planning phase.

During the 2022/2023 storm event, heavy rains, strong winds, and intense surface water runoff caused damage to the dam infrastructure, including erosion toward the end of the riprap repair. The damages include 6 to 24 inches of displaced riprap on the slope and invert. The geotextile fabric that lines the area was also ripped out. The repair will include placing material as required to secure geotextile fabric and fill in the eroded area. The estimated cost is approximately \$140,000, with an anticipated completion timeline around 2026.

The dam is safe for continued use.

Pilarcitos Dam

Description. Pilarcitos Dam is a 95-foot-high earthen embankment dam. It was constructed in 1866, raised in 1874, and is the oldest DSOD jurisdictional dam in the RWS. The reservoir storage capacity is 3,100 AF. Pilarcitos Reservoir supply can be transferred to LCSR for storage, or transferred to the Coastside County Water District, which serves the Half Moon Bay area.

Name of PM	Completion Date(s)	Description		
Valve Exercise	December 2022 to May 2023, and December 2023 to May 2024	Valves S10, S11, and S12 operation and exercise		
Vegetation Management	October 17, 2023, to January 3, 2024	Vegetation removal		
Monthly Inspection	Completed monthly			
Surveillance and Monitoring	November 21, 2022 April 4, 2023 June 28, 2023 November 1, 2023 November 28, 2023	Semi-annual surveillance and monitoring		

Table 4-15: Pilarcitos Dam Summary (July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. Pilarcitos Dam is currently in satisfactory condition, with DSOD signaling a forthcoming change to a rating of "poor." DSOD has concurred with the Embankment Stability Analysis Report, dated December 2022, that the dam could experience seismic-induced crest settlements that exceed the existing 4.70 feet total freeboard under the maximum credible earthquake (MCE). Also, the forebay and the spillway structures are deficient against the MCE forces, and the spillway capacity is deficient against the PMF. The dam and embankment show no indications of instability or distress. The riprap on the stream face appears to be uniform and intact. Vegetation and rodent control are acceptable, with the following concerns: 1) emerging woody vegetation was observed; 2) clusters of burrow holes were observed at the downstream face of the dam; and 3) sensitive habitat flags were observed on the left groin. Due to environmental concerns, SFPUC cannot implement a more robust rodent and vegetation control plan. At the spillway, the concrete repairs completed in 2017 and 2019 have held up well. No new cracks or spalls were noted. One of the slide gates is not operational, due to corrosion at the U-shaped spillway weir. This work will be included in the next CIP project. The valves in the outlet structure are fully operational. The dam is safe for continued use.

Stone Dam, downstream of Pilarcitos Reservoir, is a non-jurisdictional thin arch masonry dam constructed in 1871 by the Spring Valley Water Company. It currently serves as a diversion structure to supply water to Coastside County Water District. Regular maintenance of the spillway is required for this purpose. The dam survived the 1906 and 1989 earthquakes, and impoundment is minimal enough that it does not qualify as a DSOD jurisdictional dam.

Stone Dam is in satisfactory condition, but structural deterioration of the spillway access structure prevents operational use of its stop logs; and the reservoir storage capacity is limited due to sediment deposition and lack of regular dredging. The dam is safe for continued use.

Upper and Lower Crystal Springs Dams

Description. Upper Crystal Springs Dam (UCSD) is a 92.5-foot-high non-DSOD jurisdictional earth embankment dam. It was built in 1877, and was raised in 1891 and again in 1924. In 1924,

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

modifications were made to the UCSD so that the upper and lower dams are hydraulically connected functionally, making them act as one. UCSD is also the roadbed supporting Highway 92 as it crosses the reservoirs. UCSR stores local runoff and water from Hetch Hetchy. Water from Hetch Hetchy is dechloraminated or dechlorinated and adjusted for pH at the Pulgas Dechloramination Facility before entering UCSR.

Lower Crystal Springs Dam (LCSD) is a 163-foot-high concrete gravity dam constructed in 1890. The dam was built with interlocking concrete blocks and survived both the 1906 and 1989 earthquakes without significant damage. The combined storage capacity of UCSR and LCSR is 69,300 AF. In 2015, SFPUC completed a WSIP project that enlarged the spillway and stilling basin, raised the parapet wall, and improved the emergency outlet works. These improvements enable the PMF and other very large and infrequent floods to safely pass LCSR spillway, outlet works, and dam crest, as well as restoring LCSR to its historical storage capacity.

Maintenance. Table 4-16 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Valve Exercise	November 16, 2023	12-month valve exercise for H81, H82, H84, H87, H91, H92, H10, H11, H12, H20, H21, and H22
Vegetation Management	August 2023 to February 2024	Vegetation removal by JOC contractor as part of the access Stairs Installation Project
Monthly Inspection	Completed monthly	
Surveillance and Monitoring	November 9, 2022 March 31, 2023 June 20, 2023 October 30, 2023 November 27, 2023 May 29, 2024	Semi-annual surveillance and monitoring

Table 4-16: Lower Crystal Springs Dam Summary (July 1, 2022, through June 30, 2024)

Notes:

JOC = job order contract

PM = preventive maintenance

Condition. The interlocking concrete blocks show no new signs of structural distress. The spillway approach, control section, stilling basin, and downstream channel are clear and unobstructed. The concrete surface of the spillway and walls have minor cracking, consistent with curing. The outlet is fully operational. Rodent activities were observed at this location and will be addressed. Vegetation control is considered satisfactory. A rock masonry retaining wall on the upstream left abutment failed during the 2022/2023 winter storm, and a project is planned to replace the wall. Other damage to the dam infrastructure includes the collapse of the stone wall along the bank of the reservoir and the guard rail on the wall, and ground failure behind the wall. The scope of the repair work includes a geotechnical investigation, along with design and construction of a codecompliant retaining wall. The estimated cost of this project is \$2,100,000. This project has not yet started. Both dams are safe for continued use.

Lower Crystal Dam is in satisfactory condition.

San Andreas Dam

Description. San Andreas Dam is a 105-foot-high earth embankment dam, built in 1870, with a storage capacity of 19,000 AF. The San Andreas Fault runs along the eastern abutment of the dam. This reservoir is adjacent to the HTWTP and is the raw water source for the plant. The reservoir stores local runoff and water pumped from LCSR through CSSAPL from the CSPS. Two outlet structures, San Andreas Outlet Structure 2 and San Andreas Outlet Structure 3, were upgraded by WSIP in 2015.

Maintenance. Table 4-17 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Valve Exercise	November 8, 2022	12-month valve exercise for N21, N31, and N33
Vegetation Management	June 22, 2023 May 26, 2024	Prescribed burn and goat grazing on San Andreas Dam
Monthly Inspection	Completed monthly	
Surveillance and Monitoring	November 29, 2022 March 30, 2023 June 22, 2023 October 30, 2023 November 21, 2023	Semi-annual surveillance and monitoring

Table 4-17: San Andreas Dam Summary (July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. San Andreas Dam is in fair condition due to the condition of its spillway. The paved crest, upstream and downstream slope, and abutment contacts show no signs of instability or distress. The upstream riprap is even and uniform. Vegetation and rodent control are generally good. Sensitive habitat flags and rodent borrows were observed on the downstream face of the dam. Due to environmental concerns, SFPUC cannot implement a more robust vegetation control or rodent control plans. At the spillway, the concrete surface is in fair condition. Typical concrete cracks on the spillway wall and flood are hairline cracks and concrete spalls. Periodic repair of the concrete is required because the spillway is in the vicinity of San Andreas Fault and is subject to ground creep. The spillway approach, control structure, and downstream chute are clear and unobstructed. The steel beams under the spillway bridge were recently sandblasted and repainted. The valves in the two outlet structures are operational. This dam and its appurtenances are safe for continued use.

Alameda Creek Diversion Dam

Description. Upper ACDD was constructed between 1925 and 1932 and serves as the impound for the Alameda Creek Diversion Tunnel, a concrete-lined tunnel that delivers water to Calaveras Reservoir. ACDD is on Alameda Creek, approximately 12 miles south of the City of Pleasanton and approximately 2.5 river miles upstream of the confluence with Calaveras Creek. ACDD is an Ogee crest spillway concrete gravity structure that is bounded by cutoff walls both upstream and downstream and sits on a concrete apron formed into the bed of Upper Alameda Creek.

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Maintenance. ACDD is not a DSOD jurisdictional dam. Although inspections and preventive maintenance is performed, it is not done with the same frequency as with DSOD dams.

Condition. ACDD has been inoperable due to recent storm impacts. During the 2022-2023 winter, historic rains in the area caused flooding in Upper Alameda Creek, with peak flows occurring on December 31, 2022. High flow rates in the creek dislodged and transported river sediment material downstream, where it was caught by ACDD. The trapped sediment clogged and damaged ACDD's appurtenance structures. Additionally, ACDD lost electrical functionality, making sluiceway gates inoperable. ACDD, as well as the Alameda Creek Diversion Tunnel, has been inoperable since, due to sediment blocking the sluiceway gates, diversion gates, and fish screens; and the loss of electrical functionality for the entire facility.

4.1.2.2 <u>Capital Improvements</u>

Regional Water currently has capital projects in its water storage program, representing a total capital investment of \$126.1 million. Summaries for each of the active large capital projects are provided in the following sections.

Calaveras Reservoir Expansion Project (Approved Budget \$15.1 Million; Substantial Completion: 2039)

Scope. This project involves expansion of the Calaveras Reservoir to store excess RWS supplies or other source water in wet/normal years. No expansion of water rights from the local watershed is anticipated. With the Calaveras Dam Replacement project in place, Calaveras Dam holds a capacity of 96,850 acre-feet, or 31 billion gallons of water. Through an expansion, up to an additional 289,000 acre-feet, or 94 billion gallons, of storage could be realized. This project is in the early planning phase. The scope of work will include raising the Calaveras Dam, increasing the capacity of the outlet structures and spillway, and adding transmission and pumping facilities needed to bring water to the reservoir.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-18.

Table 4-18: Calaveras Reservoir Expansion Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete		
Project planning in progress	Pending		

Turner Dam and Reservoir Improvements Project (Approved Budget \$100 Million; Substantial Completion: 2035)

Scope. This project entails investigating the seismic stability and hydraulic performance of Turner Dam (including the outlet structure and spillway) and correcting any deficiencies. The scope of work will be confirmed following completion of the condition assessment, Needs Assessment Report, and AAR.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-19.

Table 4-19: Turner Dam and Reservoir Improvements Project Milestones Completed During theCurrent Reporting Cycle

Milestone	Date Complete		
Geotechnical investigation complete	June 30, 2023		

Pilarcitos Dam Improvements Project (Approved Budget \$64.43 Million; Substantial Completion: 2034)

Scope. This project entails investigating the seismic stability and hydraulic performance of Pilarcitos Dam (including the forebay outlet structure, outlet tunnel, outlet pipeline, and spillway), and correcting any deficiencies. Following completion of the AAR, project scope will be finalized.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-20.

Table 4-20: Pilarcitos Dam Improvements Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete		
AAR Draft	June 30, 2023		

Note:

AAR = Alternative Analysis Report

San Andreas Dam Facility Improvements Project (Approved Budget \$32.2 Million; Substantial Completion: 2033)

Scope. This project entails investigating the seismic stability and hydraulic performance of San Andreas Dam (including outlets, spillways, and appurtenances), and correcting any deficiencies. The scope of work of work for construction will likely include improvements to the following assets: 1) embankment dam; 2) emergency outlet and pipeline; 3) spillway; and 4) other ancillary facilities.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-21.

Table 4-21: San Andreas Dam Facility Improvements Project Milestones Completed During theCurrent Reporting Cycle

Milestone	Date Complete
AAR	March 31, 2024

Note:

AAR = Alternative Analysis Report

Alameda Creek Diversion Dam Restoration Project (Approved Budget \$8.5 Million; Substantial Completion: 2026)

Scope. Repairs and improvements to ACDD are broken into short-term repairs and long-term improvements. The short-term scope includes minor repairs and condition assessment. The long-

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

term scope will be determined and funded after the condition assessment is performed and will focus on operational strategy, power and communications study, and facility improvements.

JOC 95-03 has been issued for the minor repairs and condition assessment of the various impacted ACDD facility equipment and is expected to be completed no later than October 2024.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-22.

Table 4-22: Alameda Creek Diversion Dam Restoration Project Milestones Completed Duringthe Current Reporting Cycle

Milestone	Date Complete
JOC 95-03 for minor repairs and condition assessment issued	Anticipated October 2024
Project planning in progress	Pending

Note:

JOC = job order contract

Summary of Levels of Service Project Drivers

LOS drivers for by water storage capital improvements are summarized in Table 4-23.

	Level of Service							
Project	Drinking Water Quality	Regional Seismic Reliability	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
Calaveras Reservoir Expansion Project						~		
Turner Dam and Reservoir Improvements Project		✓	~					
Pilarcitos Dam Improvements Project		✓	~					
San Andreas Dam Facility Improvements Project		√	~					
Alameda Creek Diversion Dam Restoration Project						~	~	

Note:

RWS = Regional Water System

4.2 Water Treatment Assets

4.2.1 Hetch Hetchy Water

HHWP owns and operates one RWS treatment facility:

Rock River Treatment Facility

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

4.2.1.1 Asset Descriptions, Maintenance, and Condition

Rock River Treatment Facility

Description. Rock River Treatment Facility (aka Rock River Lime Plant) is situated along Foothill Tunnel near Knights Ferry. The plant doses Hetch Hetchy water deliveries to the RWS with hydrated lime (calcium hydroxide) to raise the pH and alkalinity of the water for SJPL corrosion control. The plant includes two quicklime (calcium oxide) storage silos; lime dust handling equipment; two lime slakers, consisting of chemical feeders, rotary mixers, associated piping, and their controls; a backup electric generator and propane tank; and a bin for grit waste storage for offsite disposal.

Maintenance. Table 4-24 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Water Sampling	Completed weekly	Sampled for chemistry and bacterial agents
Instrument	Completed weekly	Instruments verified weekly
Verification and Calibration	Completed monthly	Instruments recalibrated monthly
Inspection	Completed weekly	Facility inspected by HHWP Stationary Engineer
Surveillance and Monitoring	Continuously monitored	Plant monitored continuously via internal dataloggers

Table 4-24: Rock River Treatment Facility Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power PM = preventive maintenance

Condition. Rock River Treatment Facility is in good condition and remains fit for service.

4.2.1.2 <u>Capital Improvements</u>

There are no large capital improvements for HHWP's Water Treatment assets included in the current 10-year capital plan.

4.2.2 Regional Water

Regional Water has six major treatment facilities: TTF, Thomas Shaft Chlorination Facility, SVCF, SVWTP, Pulgas Dechloramination Facility, and HTWTP. TTF primarily treats Tuolumne-based supplies, and the two filtration plants treat local watershed water. Treatment improvements are ongoing, such as the addition of ozone and flocculation aid polymer, to ensure reliable operation and meet the aesthetic expectations of customers. These facilities, along with small treatment facilities that are part of the supporting utilities at remote SFPUC locations, are listed in Appendix A.

Asset descriptions for the major RWS facilities are provided in the following sections, organized from upstream to downstream. RGSR project wells are also included due to recent work done to construct the wells and upcoming work to improve the wells' operation.

4.2.2.1 Asset Descriptions, Maintenance, and Condition

Tesla Treatment Facility

Description. TTF is at the entrance to CRT, near Tracy. Treatment of Hetch Hetchy supply at this facility consists of UV light and chlorine disinfection, pH reduction using carbon dioxide, and fluoride addition. The UV system was brought online during the summer of 2011 to meet regulatory requirements from the Long-Term 2 Enhanced Surface Water Treatment Rule. In the event of a chlorination failure at the TTF, the Thomas Shaft Chlorination Facility, about 4.4 miles west of Tesla on CRT, will automatically start and boost chlorine to maintain disinfection. The detention time necessary for complete chlorine disinfection is obtained within the 25-mile length of CRT.

Maintenance. Routine inspection and maintenance for the TTF is performed throughout the year. A comprehensive PM program is also completed for the facility when it is offline during any scheduled Hetch Hetchy outages. Additional maintenance service contracts for critical assets and components have been set up to provide quarterly inspection and diagnostics of the TTF electrical room heating, ventilation, and air conditioning (HVAC) air handling units; and quarterly and annual maintenance of the three flywheel uninterruptible power supply (UPS) units. In January 2024, preventative maintenance was successfully completed on all electrical switchgear, switchboard, and transformer units.

Work continues with the modification of one of the existing carbon dioxide feed systems to enable the operator to feed chemical at a lower dose. A new carbon dioxide flow control valve and a flowmeter were installed and tested, with additional supervisory control and data acquisition (SCADA) programming and testing to be performed. The carbon dioxide feed system remains functional in manual mode.

Condition. TTF is in good condition. The facility's flywheel UPS units are no longer supported by the manufacturer, making maintenance and repairs more difficult to perform. A capital improvement project is planned to replace the flywheel UPS units and upgrade the chemical metering pumps. WSTD will also continue to explore options for more efficient treatment of the TTF domestic water system and installation of a booster pump to the existing water quality analyzers downstream of the TTF.

Thomas Shaft Chlorination Facility

Description. Thomas Shaft Chlorination Facility is 4.4 miles downstream of TTF on CRT. Thomas Shaft serves two critical functions. First, it serves as a backup chlorination facility to provide disinfection of the water supply in the event of a failure of the chlorine feed system at TTF. Second, it serves as a potable water supply source for the Lawrence Livermore National Laboratory (LLNL) campus at Site 300. A small UV system at Thomas Shaft supplements disinfection for LLNL deliveries at high CRT flow rates. The initial standby disinfection facilities were installed in 1995 and subsequently upgraded in 2002. The disinfection facilities for the Lawrence Livermore supply were added in 2010/2011 as part of WSIP.

Maintenance. Recent improvements at Thomas Shaft facility include the replacement of the electrical room HVAC unit, sample pump, level transmitter, and sodium hypochlorite injection tubing used for backup chlorination of CRT. Upcoming work includes the replacement of two obsolete UPS units and bypass switches.

Condition. Thomas Shaft Facility is in good condition.

Sunol Valley Chloramination Facility

Description. SVCF is immediately adjacent to the Alameda Siphons. The SVCF serves two primary functions: ammonia addition and sodium hypochlorite trim for chloramination, and caustic addition for corrosion control.

Additionally, the facility can feed sodium bisulfite for dechlorination and pH adjustment purposes. This operation is used during periods when 1) the Hetch Hetchy or SVWTP water do not meet drinking water standards and consequently must be discharged to either an adjacent quarry pit, San Antonio Creek, or San Antonio Reservoir; or 2) Hetch Hetchy water is used to refill San Antonio Reservoir and water must be treated to meet National Pollutant Discharge Elimination System (NPDES) requirements for total chlorine and pH prior to discharge.

SVCF also has a fluoride feed facility that was constructed to serve as a backup fluoride injection point for TTF and SVWTP. In addition, the adjacent Sunol Dechlorination Facility was later constructed to use calcium thiosulfate and fluoride for dechlorination and pH adjustment, respectively, of Hetch Hetchy water being transferred to the San Antonio Reservoir for storage.

Maintenance. Routine inspection and maintenance for the SVCF is performed throughout the year to maintain operational reliability and redundancy. Recent improvements include the replacement of the two 8,000-gallon aqua ammonia storage tanks and seismic upgrades of their concrete tank support pedestals. Ongoing efforts are being taken to replace older Coriolis-type flowmeters that are used to measure chemical dosing from the SVCF chemical metering pumps into the Alameda Siphons. The flowmeter replacements are nearly complete and are being performed by WSTD's electronic maintenance technicians during scheduled shutdowns.

Condition. SVCF is in fair condition. The upcoming SVCF Improvements project scope includes the rehabilitation of the fluoride system; replacement of the carrier water pumps; system integration of the SVCF with the Sunol Dechlorination Facility; replacement of the SVCF chemical metering pumps and pump controllers; and upgrades to SVCF's main programmable logic controller (PLC) hardware. The project is expected to begin construction in the fall of 2024, with construction completion in early 2026.

Sunol Valley Water Treatment Plant

Description. SVWTP was originally constructed in 1966 and expanded in 1974; significant improvements were completed in 2003 (Phase I) and in 2013 (WSIP). The SVWTP is a 160 mgd conventional filtration plant. Water from the Calaveras and San Antonio Reservoirs flows by gravity to the facility, where it goes through the treatment process. When higher flow rates are needed or not hydraulically feasible due to lower reservoir levels, the pumps at the San Antonio Pump Station (SAPS) are used to convey water from San Antonio Reservoir to SVWTP. Although an operational rarity, Hetch Hetchy water can be treated at the plant via SAPS to mitigate water quality issues. Water leaving the plant is chloraminated, fluoridated, and pH-adjusted before

entering the Alameda Siphons via the facility's treated water reservoir. The plant is unique in that raw water passes through a distribution structure that channels the water to individual treatment trains. This allows the different raw water sources (Calaveras, San Antonio, and Hetch Hetchy) to be treated by different treatment trains. The WSIP project upgraded the existing filters and added a fifth flocculation and sedimentation basin, chlorine contactor, treated water reservoir, and chloramination and fluoridation systems. These upgrades greatly improved the plant's reliable capacity and redundancy. Improvements made since 2013 include replacement of existing chemical piping, replacement of valves in the sludge lagoons, drainage improvements near an existing electrical building, installation of safety handrails around four existing sedimentation basins, relocation of the SCADA server room, and installation of a powdered activated carbon (PAC) system to mitigate potential taste and odor (T&O) events.

Maintenance. Routine inspection and maintenance for the SVWTP occur during scheduled plant shutdowns before and after scheduled Hetch Hetchy outages. In 2022, one of the master filter backwash valves failed; it was removed and rebuilt in 2023. Structural repairs were also recently completed on the SVWTP chemical unloading area canopy structure, and to the agua ammonia and sodium hypochlorite canopy structure. In addition, waterproofing work was recently completed to repair leaks discovered in one of the chlorine contact tank outlet weirs. Projects currently under construction are the replacement of the plant's main UPS unit, scheduled for completion by the fall of 2024; the replacement of the generator diesel particulate filter and load bank, scheduled for completion in the spring of 2025; and replacement of the Flocculation Basin #3 baffle walls, scheduled for completion by the summer of 2025. In the fall of 2024, a large capital improvement project will begin the construction phase of a new ozonation facility at SVWTP to remove T&O compounds associated with algal blooms in San Antonio and Calaveras Reservoirs; and to provide other water quality benefits, such as disinfection byproduct (DBP) reduction. This new facility will address long-term T&O control associated with algal blooms in San Antonio and Calaveras Reservoirs. Projects in the design phase include the SVWTP Short-Term Improvements project. The scope of work will include replacement of the filter valves, sludge system piping, sodium hydroxide feed piping, filter air scour piping, cationic polymer piping, and feed pumps; repairs to address concrete spalling in the sedimentation basins; and repair or replacement of the sedimentation scraper equipment. These areas were identified by WSTD staff for replacement and upgrades to ensure continued reliability of the SVWTP.

Condition. SVWTP is in good condition.

Pulgas Dechloramination Facility

Description. The purpose of the Pulgas Dechloramination Facility is to dechlorinate or dechloraminate the water discharged from the Pulgas Tunnel to the UCSR, while meeting NPDES permit requirements. The facility is immediately downstream of the Pulgas Pump Station and Balancing Reservoir. It has a treatment capacity of approximately 200 mgd and uses sodium hypochlorite, sodium bisulfite, and carbon dioxide to dechloraminate and adjust the pH of the receiving water prior to discharge.

Maintenance. Recent upgrades to the Pulgas Dechloramination Facility include the replacement of the UPS unit and external bypass switches to improve UPS reliability during utility power interruptions. The facility's rain gutters, which had corroded and deteriorated over the years,

were also replaced. Future improvements include rehabilitation of one of the sodium hypochlorite fiberglass-reinforced plastic storage tanks to extend the tank's service life.

Condition. Pulgas Dechloramination Facility is in good condition.

Harry Tracy Water Treatment Plant

Description. HTWTP is in San Bruno. It was originally constructed in 1972, with significant improvements completed in 2014. HTWTP primarily supplies the high-pressure zone customers on the Upper Peninsula and San Francisco. When necessary, it can also supplement low-pressure zone customers through the pressure-reducing valve at Capuchino Valve Lot. Source water for HTWTP is pumped from Crystal Springs Reservoir to San Andreas Reservoir, where it is again pumped to the HTWTP. HTWTP is a 140 mgd direct filtration plant that provides pre-oxidation with ozone, coagulation, flocculation, filtration through dual-media filters, fluoridation, corrosion control, and disinfection with sodium hypochlorite and ammonia to form chloramines. Significant improvements were made at HTWTP during WSIP to mitigate concerns about meeting the LOS. In particular, the chlorine contactor and the 11-million-gallon treated water reservoir were relocated to more stable ground. The new treated water reservoir has a foundation supported by more than 800 piles driven down 12 to 61 feet to bedrock. Additional improvements included upgrades to the sludge-handling process, a new washwater tank, a new substation, switchgear, and motor control center (MCC). The conveyance structures that bring water from San Andreas Reservoir to HTWTP were rebuilt to comply with the latest seismic code.

Maintenance. The most recent improvement at HTWTP was the installation of new stainless steel underdrains for Filters Nos. 1 to 6. Prior to these underdrain upgrades, two of the filters experienced a failure, during which several underdrain blocks were dislodged from the filter floor, allowing filter media and unfiltered water to enter the filter gullet. In addition to the filter underdrain replacement, there have been smaller R&R projects in the last 2 years addressing the overall reliability of the HTWTP. These projects included implementing an auto-flushing sequence for the sludge transfer pumps with PLC consolidation, repairs to one of three standby generators, replacement of actuated isolation valves for the north chemical storage tanks, replacement of both pressure reducing valves for the liquid oxygen system, seismic upgrades to the aqua ammonia piping supports, and new stainless steel aqua ammonia piping in the chemical injection/mixing vault. In the Ozone building, the ozone generator power supply unit PLCs are obsolete and are in the process of being replaced, with the completion anticipated by the end of 2024.

Upcoming projects currently in design include HVAC replacement for the Ozone Building server room; an upgraded fire-suppression system at the raw water pump station and Ozone Building server room; new vibration monitoring and alarm equipment for the raw water pumps; internal corrosion repair of the existing high rate washwater clarifiers; structural repairs of the East Chemical Storage canopy; improvements to facility access doors and roof skylights; and roofing repairs. A future capital improvement project will include replacement of six electrical substation transformers and their corresponding disconnect switches that are more than 30 years old and are considered to be in either poor or fair condition.

Condition. HTWTP is in fair condition.

RGSR Groundwater Production Wells

Description. To meet dry-year delivery needs and diversify water supply options, SFPUC has constructed a network of groundwater wells that connect to the San Francisco Water System (SFWS) and the RWS (Figure 4-1). These wells operate as two separate systems under the San Francisco Groundwater Supply project and RGSR project. Groundwater treatment varies among the different well sites based on source water quality conditions and may include chloramination, pH adjustment, fluoridation, blending for chromium VI and nitrate, removing naturally occurring ammonia, and blending or filtration for manganese.

Of the 13 wells that were constructed under the RGSR project, nine wells are connected to the RWS. The remaining four wells will be connected and treated via the partnering agencies' (City of Daly City and California Water Service) respective systems. Eight of the nine RWS wells have received conditional use approval from the State Water Resources Control Board (SWRCB). In 2021, SFPUC recognized that existing resources were insufficient to operate and maintain the decentralized RGSR RWS wells. Staffing shortages remain today, with competing priorities of the WE. In 2023, SFPUC proposed, and SWRCB concurred with, changing four of the RWS wells from active to standby status, leaving the following RWS wells in active status.

- Colma Bay Area Rapid Transit or F Street Well
- Serra Bowl or B Street Well
- Colma Boulevard Well
- Millbrae Yard Well

The RGSR Well Operations Plan was updated and submitted to SWRCB in June 2024 to reflect the active and standby status of the RWS wells.

During this reporting period, O&M improvements for select groundwater facilities were completed as part of the Phase 2A project. The work included the addition of flowmeters and variable-frequency drives (VFDs) for existing well pumps, surge anticipation valve modifications, and cathodic protection for some of the wells.

To improve the long-term operability of the RWS wells, the Regional Groundwater Treatment Improvements project was initiated and will begin its planning phase later in 2024. This project will identify, design, and construct long-term improvements to the RGSR wells to meet the following goals:

- 1. meet current and future anticipated water quality regulations;
- 2. improve overall RGSR reliability and minimize impact to the RWS;
- 3. simplify operations and maintenance of the existing facilities; and
- 4. provide long-term sustainable water deliveries.

Maintenance. SFPUC continues to maintain the pumps and treatment systems for the four active well sites. Buildings and grounds maintenance, including the security systems, are provided for the five standby well sites (Hickey Boulevard, Serramonte Boulevard, Mission Road, Poncetta Drive, and Southwood Drive).

Condition. RGSR groundwater wells are in good condition with the improvements made under Phase 2A.





4.2.2.2 Capital Improvements

Regional Water currently has capital projects in its water treatment program, representing a total capital investment of \$267.8 million. Regional Water also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

Sunol Valley Chloramination Facility Project (Approved Budget \$14.82 Million; Substantial Completion: 2026)

Scope. The primary objective of the project is to increase reliability at the fluoridation facility, SVF, and Dechlorination Facility. The scope of the project includes: 1) addressing various deficiencies of the chemical feed systems, controls, and related equipment, which will lower the current maintenance costs of the existing equipment; 2) redesign and commission of the Dechlorination Facility; and 3) upgrade of the main PLC at SVCF to provide better reliability, security, and support for the replaced pump local control panels.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-25.

Milestone	Date Complete
95% Design	October 3, 2023
100% Design	November 2, 2023
Construction award	February 13, 2024
Notice to proceed; start of construction	July 29, 2024

 Table 4-25: Project Milestones Completed During the Current Reporting Cycle

SVWTP Ozone Project (Approved Budget \$252.14 Million; Substantial Completion: 2029)

Scope. In recent years, SFPUC's SVWTP has experienced more frequent T&O events from seasonal algal blooms than had occurred historically. This project's objective is to install ozone treatment facilities as a long-term solution to control T&O events encountered in the raw water supply from both the San Antonio and Calaveras Reservoir sources. The scope of this project is to install a raw water ozonation system at SVWTP, which will include the following major components: 10-inchthrough 66-inch-diameter piping, elbows, and valves; concrete valve vaults; an ozone generator building (an approximately 10,000-square-foot concrete structure); an electrical building (an approximately 1,250-square-foot concrete structure); loop cooling water systems (an approximately 375-square-foot concrete pad, skid system, pumps, valves, and piping); cryogenic oxygen tank systems (an approximately 2,300-square-foot foundation, liquid oxygen system equipment, stainless steel piping, valves, fittings, and controls); liquid oxygen vaporizer systems (equipment, piping, valves, fittings, and controls); ozone generators (generators, piping, valves, fittings, and controls); ozone injector systems (an approximately 3,200-square-foot concrete structure, stainless steel injector units and piping, quenching chemical injection system, 66-inchdiameter piping and manifold, valves, pumps, and controls); an ozone contact basin (an approximately 12,000-square-foot concrete structure); ozone destruct systems (equipment, piping, valves, fittings, and controls); prechloramination facilities for bromate control; instrumentation and controls; shop space; solar panels; standby power systems; high-voltage and low-voltage electrical equipment and distribution systems; minor Calaveras Substation upgrades to support the ozone facility power needs; underground utilities; and site improvements. The project also includes the design of a utility water/fire protection pump station.

Milestones Completed During the Reporting Cycle. Milestones achieved by this project during this reporting cycle are summarized in Table 4-26.

the Current Reporting Cycle		
Milestone	Date Complete	
Milestone	Date Complete	

Table 4-26: Sunol Valley Water Treatment Plant Ozone Project Milestones Completed During

Milestone	Date Complete
Conceptual engineering report	January 18, 2022
Completed EIR	July 13, 2023
Bid advertisement	September 29, 2023

Note:

EIR = environmental impact report

Sunol Valley Water Treatment Plant Short-Term Improvements (Approved Budget \$78.64 Million; Substantial Completion: 2029)

Scope. The primary objective of the SVWTP Short-Term Improvements project is to improve regional delivery reliability by addressing various conditions and deficiencies at SVWTP. The construction scope of work includes the following: repair filter valve, valve frame, and anchoring; upgrade sludge system piping, valves, cross-collectors, and monitoring system; upgrade chemical piping system; upgrade filter air scour piping; repair concrete spalling in the sedimentation basins; repair settled water conduit leakage; repair concrete pad and coating at Caustic Tank farm; Cat-C polymer feed system reconfiguration; repair super scrapers; and construct a utility water/fire protection pump station. The project includes \$7.54 million in expenditures for work performed prior to October 2018, under the SVWTP Phase 3 project and the start of the current scope for the SVWTP Short Term Improvements project.

Milestones Completed During the Reporting Cycle. Milestones achieved by this project during this reporting cycle are summarized in Table 4-27.

 Table 4-27: Sunol Valley Water Treatment Plant Short-Term Improvements Project Milestones

 Completed During the Current Reporting Cycle

Milestone	Date Complete
50% Design	December 1, 2022
Completed EIR	July 13, 2023
95% Design	May 10, 2023

Note:

EIR = environmental impact report

Sunol Valley Water Treatment Plant Long-Term Improvements (Approved Budget \$35.62 Million; Substantial Completion: 2034)

Scope. The primary objective of the SVWTP Long-Term Improvements project is to improve regional delivery reliability by addressing various conditions and deficiencies of the SVWTP. Upgrades were identified through condition assessments and staff observations, review of LOS, subsequent feasibility studies, and alternative analyses. These upgrades include 1) installation of an emergency eyewash station at the chlorine contact tank; 2) repairs to bird netting deficiencies at the flocculation/sedimentation basins and filters; 3) installation of new bird netting for fluoride storage and the chemical delivery dock; 4) replacement of main switchboards 1 and 2, removal of ATS-1, ATS-2, and ATS-3, and incorporation of functionality into the new switchgear; 5) addition of a redundant 2-megawatt (MW) standby generator with active particulate air filters; 6) replacement of all General Electric power circuit breakers (not all are arc-flash-rated); 7) repairs to the concrete pad and coating at the caustic tank farm; 8) reconfiguration of the Cat-C polymer feed system; 9) installation of the washwater pumps soft starter system; 10) installation of air monitors for the aqua ammonia tanks; and 11) roadway and site improvements.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-28.

Table 4-28: Long-Term Improvements Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete
Project planning in progress	Pending

Sunol Valley Water Treatment Plant Polymer Feed Facility Project (Approved Budget \$19.05 Million; Substantial Completion: 2024)

Scope. The SVWTP flocculation/sedimentation basin (2013) and the four existing basins are not able to achieve their rated capacity under all operating and water quality conditions. This project will entail constructing a new flocculant aid and polymer system, including: 1) polymer feed building with polymer totes and a tote storage area; 2) polymer blending units; 3) batch tanks, tank and tote mixers, and batch tanks polymer transfer pump; 4) polymer feed pumps, piping, and valving; and 5) site improvements.

Milestones Completed During the Reporting Cycle. The milestone achieved by this project during this reporting cycle is summarized in Table 4-29.

Table 4-29: Sunol Valley Water Treatment Plant Polymer Feed Facility Project MilestonesCompleted During the Current Reporting Cycle

Milestone	Date Complete
Design	Deferred until after ozone project is complete

HTWTP Filter Underdrain Replacement Project (Approved Budget \$14.4 M; Substantial Completion: 2024)

Scope. Underdrains in two filters in a bank of six have failed since 2019, and replacement of the underdrains is being prioritized to restore HTWTP's treatment capacity and reliability. The project includes: 1) removal and disposal of existing filter media, and provision of new filter media; 2) procurement and installation of new stainless steel filter underdrains for six filters; 3) modification of air distribution piping beneath filter underdrains; 4) cleaning and recoating of main air distribution piping; and 5) demolition work and concrete work.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-30.

Table 4-30: HTWTP Filter Underdrain Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete
Contract award	July 12, 2022
Notice to proceed; start of construction	October 3, 2022
Substantial completion	October 2, 2023
30% construction	March 31, 2023
60% construction	June 30, 2023

Notes:

HTWTP = Harry Tracy Water Treatment Plant

Regional Groundwater Treatment Improvements Project (Approved Budget \$38.6; Substantial Completion: 2033)

This project will improve the performance of the Regional Groundwater Wells and treatment systems in the South Westside Basin. This project will: 1) address emerging well water quality issues that require treatment; 2) provide additional reliability for treatment systems at the wells; and 3) evaluate the potential for a consolidated treatment facility (through alternatives analysis only). If a centralized treatment alternative is selected, the estimated project cost could potentially be \$250 million, which includes construction of approximately 14 miles of 8-inch- to 24-inch-diameter pipeline, a pump station, storage tanks, treatment facilities, and other ancillary facilities.

Scope. The current project consists of design and construction of facilities at individual well sites, including: 1) installation of an ammonia analyzer at one site; 2) construction of manganese enclosures at two sites; 3) installation of a building, filtration, and ammonia analyzer at one site; 4) upsizing of pedestals and tanks for 2-week storage of sodium hydroxide at five sites; 5) upsizing of pedestal and tanks for 2-week storage of sodium hydroxide at one site; 7) installation of a detention (contact) tank to address high levels of ammonia without enclosure at one site; 8) upsizing of pedestals, tanks, and overall chemical systems for a change in chemical concentration from 50 percent to 25 percent at five sites; 9) installation of a chlorine detention (contact) tank to address high levels of bucket elevators for sodium fluoride at seven sites; 12) a study to compare liquid versus powder fluoride; 13) a study of reverse flow (lockout study for minimum shutdown time); and 14) reimbursement to Cal Water for supporting the project design and construction for the South San Francisco Main well.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-31.

Table 4-31: Regional Groundwater Treatment Improvements Project Milestones CompletedDuring the Current Reporting Cycle

Milestone	Date Complete
Project planning in progress	Pending

Summary of Levels of Service Project Drivers

LOS drivers supporting the water treatment capital improvements are summarized in Table 4-32.

			-		-			
	Level of Service							
Project	Drinking Water Quality	Regional Seismic Reliability	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
SVCF Project	~							
SVWTP Ozone Project	✓							
SVWTP Short-Term Improvements	~		~					
SVWTP Long-Term Improvements	~		~					
SVWTP Polymer Feed Facility Project	~		~					
HTWTP Filter Underdrain Replacement Project	~		~					
Regional Groundwater Treatment Improvements Project	~					~		

Table 4-32: RWS Water Treatment Projects - Levels of Service Project Drivers

Notes:

HTWTP = Harry Tracy Water Treatment Plant RWS = Regional Water System SVCF = Sunol Valley Chloramination Facility SVWTP = Sunol Valley Water Treatment Plant

4.3 Water Transmission Assets

SFPUC owns and operates multiple water transmission assets, including tunnels, penstocks, and pipelines. The responsibility for O&M of these assets is divided geographically between both HHWP and Water Supply and Treatment.

4.3.1 Hetch Hetchy Water

HHWP is responsible for the maintenance and operation of multiple water transmission assets that work as a system to transport water from the Sierra Nevada Mountains to AEP, spanning nearly the entire width of California. These assets include:

Canyon Power Tunnel	Granite Portal Valve House	Moccasin Penstock
Canyon Portal Valve House	Holm Penstock	Foothill Tunnel
Kirkwood Penstock	Lower Cherry Aqueduct	San Joaquin Pipelines
Early Intake Bypass Tunnel and	Mountain Tunnel	San Joaquin Valve House
Pipeline		
Eleanor-Cherry Tunnel	Moccasin Power Tunnel	Coast Range Tunnel
Cherry Power Tunnel	West Portal Valve House	

4.3.1.1 Asset Descriptions, Maintenance, and Condition

Descriptions of the HHWP water transmission assets, along with summaries of their maintenance and condition, are provided in the following sections, organized from upstream to downstream. A summary of the assets organized by classification is included in Appendix A, in the Upcountry section of Table A-6.

Canyon Power Tunnel

Description. Canyon Power Tunnel, built in 1965, is a 10.4-mile-long tunnel that conveys water from O'Shaughnessy Dam to Kirkwood Penstock. Approximately 51,000 feet of the tunnel is unlined, horseshoe-shaped, and measures approximately 14 feet by 14.5 feet, minimum. Approximately 4,100 feet of the tunnel is concrete- or steel-lined. Canyon Power Tunnel includes two adits: North Mountain and Hetchy Adit.

Maintenance. Table 4-33 summarizes maintenance work.

Table 4-33: Canyon Power Tunnel Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	External inspection performed annually	Inspect portals for changes in seepage
	Completed weekly	Adit and adit leakage monitored
Surveillance and Monitoring	Continuously monitored	Turbidity, pressure, and flows monitored continuously via SCADA alarms

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Canyon Power Tunnel is in good condition. It was last inspected in 2009, and the schedule for the next inspection will be determined in the next reporting cycle. The internal inspection frequency for this asset is 20 years. During this reporting cycle, no new deficiencies were noted, and the tunnel is fit for service; however, Hetchy Adit requires capital improvements, and a project is currently in progress.

Canyon Portal Valve House

Description. Canyon Portal Valve House is upstream of Kirkwood Penstock and downstream of Canyon Tunnel. Inside the valve house there is a single 96-inch-diameter butterfly valve, as well as the mechanical and electrical equipment necessary for its operation.

Maintenance. Table 4-34 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Valve Trip Test	Completed weekly	Perform trip test of valve
Inspection	Completed annually	Mechanical inspection of valve, actuator, and associated equipment; valve stems are greased
	Completed weekly	Facility inspected by HHWP watershed keeper
Surveillance and Monitoring	Continuously monitored	Alarmed and monitored continuously via SCADA

Table 4-34: Canyon Portal Valve House Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Canyon Portal Valve House is in good condition. One of the functions of the Canyon Portal Valve House is to provide protection to the Kirkwood Penstock and Kirkwood Powerhouse in the event of a penstock failure. The system has instrumentation and control installed that would identify the failure event and close the valve, stopping flows to the Kirkwood Penstock. Corrective Maintenance resolved instrumentation and control problems that caused the penstock isolation valve to mis-operate during the previous reporting period. Canyon Portal Valve House is fit for service.

Kirkwood Penstock

Description. Kirkwood Penstock (formerly known as Canyon Penstock) is a 1,950-foot coated steel pipe that ranges from 43.75 to 98 inches in diameter and conveys water from Canyon Power Tunnel to Kirkwood Powerhouse. Constructed in 1967, the penstock is an essential component for both water and power reliability. The penstock 1) serves as a direct passageway for primary source water from O'Shaughnessy Dam, with little to no redundancy; and 2) is required for power generation at Kirkwood Powerhouse.

Maintenance. Table 4-35 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed weekly	Inspected by HHWP watershed keeper for leaks, rockfall, and movement
Vegetation Management	Annually or as needed	Removal of vegetation to reduce fire danger and ease inspections
Surveillance and Monitoring	Continuously monitored	Pressure and flows monitored continuously via SCADA alarms; penstock movement is monitored and alarmed

Table 4-35: Kirkwood Penstock Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance SCADA = supervisory control and data acquisition

Condition. Kirkwood Penstock is in good condition; however, due to its historical stability performance, HHWP monitors the upper reach of the penstock for movement using an automated

system. The system was installed in 2018 as a series of risk mitigation measures that were implemented to extend the life of the asset. During the inspection and monitoring performed by HHWP in this reporting cycle, no deficiencies were noted, and all recorded movements were within the established thresholds. Additionally, HHWP identified the couplings on Kirkwood Penstock as a "critical spare" item due to their technical design requirements and long procurement lead time. HHWP procured multiple large-diameter penstock couplings in 2022 as necessary for emergency repairs. Kirkwood Penstock is fit for service.

Early Intake Bypass Tunnel and Pipeline

Description. Early Intake Bypass Tunnel and Pipeline conveys water from Kirkwood Powerhouse directly into Mountain Tunnel. The bypass consists of a tunnel on the northern side of the Tuolumne River, leading to a steel pipe crossing the river to Mountain Tunnel on the southern side. The 2,030-foot tunnel comprises approximately 1,500 feet of unlined, 14-foot by 14.5-foot (minimum) horseshoe-shaped tunnel; and approximately 500 feet of concrete or steel-lined tunnel. The water exits Early Intake Bypass Tunnel, entering a 293-foot-long, 9.5-foot-diameter pipeline that crosses over the Tuolumne River. There is an unused Venturi meter on the downstream end of the pipeline.

Maintenance. Table 4-36 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	External inspections scheduled annually	Inspect portals for changes in seepage
	Completed weekly	Above-ground sections and access inspected by watershed keeper for leaks
Surveillance and Monitoring	Continuously monitored	Turbidity, pressure, and flows monitored continuously via SCADA alarms

Table 4-36: Early Intake Bypass Tunnel and Pipeline Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Early Intake Bypass Tunnel and Pipeline is in good condition. The tunnel was inspected in 2019. The internal inspection frequency for this asset is 20 years. During this reporting cycle, no deficiencies in condition were noted. The Early Intake Bypass Tunnel and Pipeline are both fit for service.

Eleanor-Cherry Tunnel

Description. Eleanor-Cherry Tunnel, built in 1960, is a 1.1-mile-long tunnel that conveys water from Lake Eleanor to Lake Lloyd (a.k.a. Cherry Lake). Approximately 5,700 feet of the tunnel is unlined, horseshoe-shaped, and measures approximately 10 feet by 10 feet. Approximately 200 feet of the tunnel is concrete or steel-lined, and measures approximately 8.5 feet by 8.5 feet.

Maintenance. Table 4-37 summarizes maintenance work.

Table 4-37: Eleanor-Cherry Tunnel Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	External inspections scheduled annually	Inspect portals for changes in seepage
Surveillance and Monitoring	Completed daily	Flows estimated daily via mass balance

Note:

PM = preventive maintenance

Condition. Eleanor-Cherry Tunnel was last inspected in 2017. The internal inspection frequency for this asset is 20 years. The tunnel is in good condition and is fit for service.

Cherry Power Tunnel

Description. Cherry Power Tunnel, built in 1960, is a 5.6-mile-long tunnel that transmits water from Lake Lloyd (aka Cherry Reservoir) through Granite Portal to Holm Penstock.

Maintenance. Table 4-38 summarizes maintenance work.

Table 4-38: Cherry Power Tunnel Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	External inspections scheduled annually	Inspect portals for changes in seepage
	Completed weekly	Adit inspections
Surveillance and Monitoring	Continuously monitored	Turbidity, pressure, and flows monitored continuously via SCADA alarms

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Cherry Power Tunnel is in good condition and fit for service. The tunnel was last inspected in 2000. The next inspection is scheduled for 2025.

Granite Portal Valve House

Description. Granite Portal Valve House is upstream of Holm Penstock and downstream of Cherry Power Tunnel. Inside the valve house there is a single 96-inch-diameter butterfly valve, as well as the mechanical and electrical equipment necessary for its operation.

Maintenance. Table 4-39 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Valve Trip Test	Completed weekly	Perform trip test of valve
Inspection	Completed annually	Mechanical inspection of valve, actuator, and associated equipment; valve stems are greased
	Completed weekly	Facility inspected by HHWP watershed keeper
Surveillance and Monitoring	Continuously monitored	Alarmed and monitored continuously via SCADA

Table 4-39: Granite Portal Valve House Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Granite Portal Valve House is in good condition and remains fit for service. One of the functions of Granite Portal Valve House is to provide protection to Holm Penstock in the event of a penstock failure, similar to Canyon Portal Valve House's function for Kirkwood Penstock. The system has instrumentation and control installed that would identify the failure event and close the valve, stopping flows to Holm Penstock.

Holm Penstock

Description. Holm Penstock (formerly known as Cherry Penstock) is a 6,800-foot coated steel pipe that ranges from 80 to 108 inches in diameter and conveys water from Cherry Power Tunnel to Holm Powerhouse. Constructed between 1959 and 1962, the penstock is a critical component for power generation at Holm Powerhouse.

Maintenance. Table 4-40 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed weekly	Inspected by HHWP watershed keeper for leaks, rockfall, and movement
Vegetation Management	Annually or as needed	Removal of vegetation to reduce fire danger and ease inspections
Surveillance and Monitoring	Continuously monitored	Pressure and flows monitored continuously via SCADA alarms

Table 4-40: Holm Penstock Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. A condition assessment of the Holm Penstock was last conducted in 2013, following the Rim Fire. The penstock is in good condition. An updated condition assessment is scheduled in the CIP, after which a relining or recoating project will likely be proposed and added to the CIP, if deemed necessary. The Holm Penstock is fit for service.

Lower Cherry Aqueduct

Description. LCA is 3.8 miles long and comprises 1.8 miles of tunnel, 0.04 mile of concrete conduit, 1.1 miles of concrete-lined canal, 0.04 mile of 72-inch-diameter redwood stave pipe, 0.2 mile of 54-inch-diameter steel pipe, and 3,320 feet of 36-inch-diameter steel pipe. LCA provides SFPUC with access to either Lake Lloyd or Lake Eleanor storage for drinking water purposes in an emergency or drought condition. LCA includes a small diversion dam on Cherry Creek that routes releases from the Cherry and Eleanor watersheds through a series of tunnels, open canals, and steel pipeline to Early Intake Reservoir.

Maintenance. Table 4-41 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed biweekly	Inspected by HHWP watershed keeper for leaks, rockfall, and movement
Vegetation Management	Annually or as needed	Removal of vegetation to reduce fire danger and ease inspections
Flush and Gate Operation	Completed annually	Aqueduct operated annually, pushing water though all gates, tunnels, canals, and pipes; leaks and constrictions are monitored and fixed

Table 4-41: Lower Cherry Aqueduct Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power PM = preventive maintenance

Condition. LCA is in good condition and is fit for service.

Mountain Tunnel

Description. Mountain Tunnel is a critical water conveyance facility for the Hetch Hetchy System source. Built between 1917 and 1925, Mountain Tunnel extends 19.2 miles from Early Intake Dam to Priest Reservoir. Approximately 37,000 feet of the tunnel is unlined and horseshoe-shaped, measuring approximately 13.5 feet by 13.5 feet. Approximately 60,000 feet of tunnel is concrete-lined and horseshoe-shaped, measuring approximately 10 feet by 10 feet.

Maintenance. Table 4-42 summarizes maintenance work.

Table 4-42: Mountain Tunnel Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	External inspections scheduled annually	Inspect portals for changes in seepage
	Completed weekly	Adit inspections, with exception of South Fork Adit
	Completed monthly	South Fork Adit inspection
Surveillance and Monitoring	Continuously monitored	Turbidity, pressure, and flows monitored continuously via SCADA alarms

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Mountain Tunnel condition continues to improve as the Mountain Tunnel Improvement project nears completion. The asset condition rating has improved from the "fair condition" reported previously in 2022. The inspection frequency for this asset is 20 years. Internal inspections will resume in about 20 years, following completion of the Mountain Tunnel Improvement project.

Moccasin Power Tunnel

Description. Moccasin Power Tunnel, built in 1925, is a 1-mile-long tunnel that conveys water from Priest Reservoir to Moccasin Penstocks. Most of the concrete-lined tunnel is horseshoe-shaped, and it measures approximately 13 feet by 13 feet.

Maintenance. Table 4-43 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	External inspections scheduled annually	Inspect portals for changes in seepage
	Completed weekly	Adit inspections
Surveillance and Monitoring	Continuously monitored	Turbidity, pressure, and flows monitored continuously via SCADA alarms

Table 4-43: Moccasin Power Tunnel Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

PM = preventive maintenance SCADA = supervisory control and data acquisition

Condition. An internal inspection of Moccasin Power Tunnel was completed in 2019. The internal inspection frequency for this asset is 20 years. The Moccasin Power Tunnel is in good condition and remains fit for service.

West Portal Valve House

Description. West Portal Valve House is upstream of Moccasin Penstock and downstream of Moccasin Power Tunnel. Inside the valve house there are three 104-inch-diameter butterfly valves, as well as the mechanical and electrical equipment necessary for their operation.

Maintenance. Table 4-44 summarizes maintenance work.

Table 4-44: West Portal Valve House Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description	
Valve Trip Test	Completed weekly	Perform trip test of valve	
Inspection		Mechanical inspection of valve, actuator, and associated equipment; valve stems are greased	
	Completed weekly	Facility inspected by HHWP watershed keeper	
Surveillance and Monitoring	Continuously monitored	Alarmed and monitored continuously via SCADA	

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. West Portal Valve House is in fair condition due to its age. Historically, the valve house was used as an isolation point for maintenance and construction of Moccasin Penstock; however, improved safety practices no longer rely on single butterfly valves as an isolation point. It is recommended to investigate this further to determine whether improvements are appropriate to provide access inside Moccasin Penstock while the Moccasin Power Tunnel remains in service.

Moccasin Penstock

Description. Moccasin Penstock is set of coated steel pipes within the HHWP system that conveys water from Priest Reservoir to Moccasin Powerhouse. Constructed in 1924, with new sections completed in 1969, the penstock is an essential component of SFPUC water and power reliability in that it 1) serves as a direct passageway for primary source water from Hetch Hetchy Reservoir, with little redundancy; and 2) is a critical asset for power generation at Moccasin Powerhouse.

Maintenance. Table 4-45 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed weekly	Inspected by HHWP watershed keeper for leaks, rockfall, and movement
Vegetation Management	Annually or as needed	Removal of vegetation to reduce fire danger and ease inspections
Surveillance and Monitoring	Continuously monitored	Pressure and flows are monitored continuously via SCADA alarms

Table 4-45: Moccasin Penstock Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power PM = preventive maintenance SCADA = supervisory control and data acquisition

SCADA = supervisory control and data acquisition

Condition. Moccasin Penstock is in fair condition, given its age and deficiencies in its anchor blocks, lining, and coatings. The penstock remains fit for service. There is a capital project to address the penstock's deficiencies.

Foothill Tunnel

Description. Foothill Tunnel is a 16.3-mile-long tunnel that conveys water from Moccasin Reservoir to Oakdale Portal, the entrance to the SJPLs. Most of the tunnel is horseshoe-shaped, and it measures approximately 14 feet by 14 feet. About half of the of the tunnel is unlined rock. The tunnel crosses beneath Don Pedro Reservoir via the Red Mountain Bar Siphon. Between the siphon and Oakdale Portal, the Rock River Lime Plant adjusts the water pH at the Rock River Shaft.

Maintenance. Table 4-46 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	External inspections scheduled annually	Inspect portals for changes in seepage
	Completed monthly	Inspection and exercise blowoffs at Brown and Pedro adits
Surveillance and Monitoring	Continuously monitored	Turbidity, pressure, and flows monitored continuously via SCADA alarms

Table 4-46: Foothill Tunnel Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

PM = preventive maintenance SCADA = supervisory control and data acquisition

Condition. A condition assessment of Foothill Tunnel was performed in 2020. The internal inspection frequency for this asset is 20 years. Foothill Tunnel is in good condition and fit for service.

San Joaquin Pipelines

Description. There are four SJPLs, but only three (SJPL Nos. 1, 2, and 3) extend the entire 47.5 miles across the San Joaquin Valley. SJPL No. 4 has a 6.7-mile-long eastern reach, beginning at Oakdale Portal; and a 10.5-mile-long western reach, ending at Tesla Portal. The SJPLs were constructed over an 80-year period. SJPL Nos. 1 through 4 were completed in 1934, 1953, 1968, and 2014, respectively. The purpose of the pipelines is to convey Hetch Hetchy water across the San Joaquin Valley, from Foothill Tunnel to CRT. Ancillary facilities, such as throttling stations, crossover valve vaults, metering facilities, and pressure-relief facilities are part of the overall SJPL network.

Pipe materials include steel, prestressed concrete cylinder pipe (PCCP) (about 7 miles on SJPL No. 3) and reinforced concrete cylinder pipe (RCP) (on the western and eastern ends of SJPL No. 2, totaling about 20 miles of pipe). SFPUC maintains several maintenance programs on the SJPLs including:

- PCCP: The PCCP is baselined for wire breaks about every 15 years using electromagnetic technology, with the detection and location of additional wire breaks monitored using acoustical fiber optic (AFO) technology.
- CP Systems: SFPUC maintains a combination of impressed current and galvanic CP systems. A summary of maintenance activities is provided in Table 4-47.

Maintenance. Table 4-47 summarizes maintenance work.

Name of PM	Completion Date(s)	Description	
Pipe			
Internal Inspection	Completed as needed	HHWP Water Operations and Engineering inspect for lining condition, leaks, valve condition	
External Inspection	Completed weekly	Facility inspected by HHWP watershed keeper	
Valve Box Maintenance	Completed every 10 months	Blowoff valve and air valve operation	
Surveillance and Monitoring	Continuously monitored	Pipeline pressure, flow, and turbidity alarmed and monitored continuously via SCADA; SJPL No. 3, Section A, monitored for wire breaks	
CP Systems	·		
Impressed current systems	Completed quarterly	Verify that rectifier is on and read panel meters for volts and amps	
	Completed quarterly	Interrupt impressed current system rectifiers and measure pipe-to-soil potential at test stations	
	Completed annually	Measure pipe-to-soil potential at test stations for galvanic anodes	
	Completed annually	Complete system evaluation, including rectifier inspection, adjustment, and balancing of stations	
Galvanic systems	Completed annually or following construction/ condition assessment activities	Spot checking to verify functionality	
	Completed annually	Verify connectivity along the galvanic ribbon	

Table 4-47: San Joaquin Pipelines Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

CP = cathodic protection HHWP = Hetch Hetchy Water and Power PM = preventive maintenance SCADA = supervisory control and data acquisition SJPL = San Joaquin Pipeline

Condition. The four SJPLs are currently undergoing a systemic condition assessment. An inspection of SJPL No. 1 (in-line magnetic flux leakage technology [MFL]) was completed in 2021. Results indicate significant pipeline wall thinning due to corrosion on approximately 2 miles of pipe. Construction is in progress to replace or repair these pipe sections, with completion anticipated by August 2026.

The statuses of SJPL condition assessments are as follows:

- SJPL No. 1: Completed in 2021.
- SJPL No. 2:
 - Steel only: MFL and sizing tool planned for January/February 2025.
 - RCP: Visual inspection of 3 miles of pipe planned for January/February 2025.

- SJPL No. 3:
 - PCCP only: A condition assessment of SJPL PCCP was performed in February 2023, using electromagnetic technology to re-baseline/confirm the estimated number of wired breaks. The condition assessment compared well with data collected from the AFO system.
 - Steel: 29 miles of MFL and sizing tool were inspected during February 2024.
 - Remaining steel: The balance of the pipeline is planned to be inspected with MFL and sizing tool in January/February 2026.
- SJPL No. 4:
 - Inspection of 17 miles of SJPL No. 4 using MFL and sizing tool is planned for January/ February 2026.

SJPL Nos. 1, 2, 3, and 4 are fit for service.

SJPL Valve Houses

Description. A series of valve houses and throttling stations along the SJPLs are used to isolate and control flows through the SJPLs. These include Oakdale Portal, Throttling Station 3/4, Throttling Station 2 East, Throttling Station 2 West, P4J, Emery Crossover, Albers Valve House, Roselle Crossover, San Joaquin Valve House, Pelican Crossover, Tesla UV Valve House, Tesla Portal 1/2 Valve House, and Tesla Portal 3 Valve House. The valve houses are remotely monitored and supervised from Moccasin Control Center.

Maintenance. Table 4-48 summarizes maintenance work.

(July 1, 2022, through June 30, 2024)		
Name of PM	Completion Date(s)	Description
Internal Inspection	Completed as needed	Inspection of lining, leaks, and valve condition; Oakdale Portal Valves inspected in 2021
	Weekly	Facility inspected by HHWP watershed keeper
Maintenance	Completed quarterly	Operate and inspect valves, including actuators and manual handwheels
Surveillance and Monitoring	Continuously monitored	Facilities have security alarms that are monitored continuously; pipeline pressure and flow are alarmed and monitored continuously via SCADA

Table 4-48: San Joaquin Pipeline Valve Houses Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. There are eight valve houses providing isolation and flow control through the SJPLs. The original valve houses at Tesla, San Joaquin, and Oakdale are fit for service and in fair condition. The remaining five valve houses were constructed during the SJPL No. 4 construction,

circa 2010, and are in good condition. In 2021, the PLCs and remote terminal units were upgraded in the San Joaquin Valve House to improve supervisory monitoring and controls. Unfortunately, due to valves that are not rated for the required pressures and an overall lack of redundancy, the valve houses do not provide adequate isolation to support work inside the pipelines unless the entire Hetch Hetchy System is shut down. There are multiple capital projects to address the previously described deficiencies.

Coast Range Tunnel

Description. CRT is a 25.1-mile-long tunnel that conveys partially treated Hetch Hetchy water from TTF, just downstream of the SJPLs, to AEP. The finished diameter of the lined tunnel is 10.5 feet. Six construction shafts were used to build the tunnel from 1927 to 1934. All of the shafts were backfilled, except for the Thomas Vent Shaft, which connects the tunnel with the ground surface.

Maintenance. Table 4-49 summarizes maintenance work.

Table 4-49: Coast Range Tunnel Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
1	External inspections scheduled annually	Inspect portals for changes in seepage
Surveillance and Monitoring		Turbidity, pressure, and flows monitored continuously via SCADA alarms

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. CRT was last inspected in 2015. The internal inspection frequency for this asset is 20 years. The tunnel is in good condition and is fit for service.

4.3.1.2 <u>Capital Improvements</u>

HHWP currently has capital projects in its water transmission program, representing a total capital investment of \$865.3 million. HHWP also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

SJPL Valve and Safe Entry Improvements (Approved Budget \$157.8 Million; Substantial Completion: 2028)

Scope. The objective of this project is to allow for safe entry into any and all sections of the SJPLs for inspection and maintenance while the remainder of the system stays in service. The project will be completed in four phases: 1) Phase 1A – Pipeline 2 Tesla and Oakdale Entry Improvements; 2) Phase 1B – Pipelines 3 and 4 Tesla and Oakdale Entry Improvements; 3) Phase 2 – Pelican, Roselle, Emery and P4J Entry Improvements; and 4) Phase 3 – Tesla Surge Stack.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-50.

Table 4-50: SJPL Valve and Safe Entry Improvements Project Milestones Completed During the
Current Reporting Cycle

Phase	Milestones	Completion Date
Phase 2A	65% Design for HH-1012 (Phase 2A)	November 2022
	95% Design for HH-1012 (Phase 2A)	May 2023
	100% Design for HH-1012 (Phase 2A)	October 2023
	Issued NTP for Constriction HH-1012 (Phase 2A)	May 2024
Phases 2B and 2C	95% Design for HH-1016 (Phases 2B and 2C)	June 2024
Phase 3	95% Design for HH-1009 (Phase 3)	March 2023
	100% Design for HH-1009 (Phase 3)	May 2023
	Issued NTP for Construction HH-1009 (Phase 3)	February 2024

Note:

NTP = Notice to Proceed

SJPL Valve Remote Control and Monitoring (Approved Budget \$38.7 Million; Substantial Completion: 2028)

Scope. The objective of this project is to design and construct new SJPL remote supervisory controls that would enable remote operation from Moccasin to remotely operate in-line and cross-over valve actuators.

Milestones Completed During the Reporting Cycle. The project is scheduled and budgeted to begin in 2024; therefore, no milestones were achieved during this reporting cycle.

Mountain Tunnel Improvement Project (Approved Budget \$268.7 Million; Substantial Completion: 2026)

Scope. This project will rehabilitate Mountain Tunnel, including: 1) repair of the lining; 2) adit and tunnel entry improvements; 3) access road improvements; and 4) installation of a new flow-control facility at Priest Reservoir to ensure that the tunnel can reliably provide drinking water to customers for the next 100 years.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-51.

Table 4-51: Mountain Tunnel Improvement Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete
Survey of tunnel and of siphon at South Fork; geological evaluation of South Fork Siphon; installation of rock dowels at the Priest Adit tie-In	2022 Shutdown (January through March)
Tunnel lining repairs and pressure grouting	2023 Shutdown (December through March)

Cherry-Eleanor Pumps (Approved Budget \$38.8 Million; Substantial Completion: 2030)

Scope. This project will replace and upgrade pumps in the Cherry Pump Station with units that work with current operating strategies.

Milestones Completed During the Reporting Cycle. The project is scheduled and budgeted to begin in 2025; therefore, no milestones were achieved during this reporting cycle.

Canyon Tunnel – Hetchy Adit Rehabilitation and O'Shaughnessy Bridge (Approved Budget \$30.1 *Million; Substantial Completion:* 2030)

Scope. The scope for this project is to complete the installation of a new reinforced concrete plug downstream of the existing plug at the Hetchy Adit, reducing leakage and increasing the reliability of the system. Included in the scope of this project is rehabilitation of the O'Shaughnessy Adit Access Bridge, including substructure retrofit and superstructure replacement. Currently the O'Shaughnessy Adit Access Bridge project is described and reported in the Watershed, Roads, and Bridges asset classification. However, these two projects will be combined in the subsequent reporting period.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-52. Additionally, milestone updates for the O'Shaughnessy Adit Access Bridge are reported in the Watersheds, Roads, and Bridges asset classification section.

Milestone	Date Complete
Canyon Tunnel boundary correction in Yosemite National Park	September 2022
Hetchy Adit rehabilitation - conceptual engineering report (final)	September 2023
Hetchy Adit rehabilitation - 65% design	October 2022
Hetchy Adit rehabilitation - 95% design	April 2023
Hetchy Adit rehabilitation - independent technical review	May 2024
Hetchy Adit rehabilitation - 98% design submittal draft	June 2024

 Table 4-52: Canyon Tunnel – Hetchy Adit Rehabilitation and O'Shaughnessy Bridge Project

 Milestones Completed During the Current Reporting Cycle

Moccasin Penstock Rehabilitation (Approved Budget \$331.2 Million; Substantial Completion: 2034)

Scope. The scope of this project has been updated during the reporting cycle to now include replacement of the penstocks with a combination of a drop shaft, a tunnel, and above-grade pipes as the preferred alternative to meet established LOS, mitigate potential risks, and avoid potential COFs.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-53.

Table 4-53: Moccasin Penstock Rehabilitation Project Milestones Completed During theCurrent Reporting Cycle

Milestone	Date Complete
NAR final	September 2022
Pulse array ultrasonic testing inspection JOC 87-04	October 2022
Condition assessment technical design memoranda (six total)	January 2023
Alternative evaluation criteria	March 2023
AAR draft	August 2023

Notes:

AAR = Alternatives Analysis Report JOC = job order contract NAR = Needs Assessment Report

Summary of Levels of Service Project Drivers

LOS drivers supporting the water transmission capital improvements are summarized in Table 4-54.

Table 4-54: HHWP Water Transmission Projects - Levels of Service Project Drivers

	Level of Service							
Project	Drinking Water Quality	Regional Seismic Reliability	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
SJPL Valve and Safe Entry Improvements			~			\checkmark		~
SJPL Valve Remote Control and Monitoring			~			✓		~
Mountain Tunnel Improvement Project	~		~			✓		~
Cherry-Eleanor Pumps			~			\checkmark	~	~
Canyon Tunnel – Hetchy Adit Rehabilitation and O'Shaughnessy Bridge			~				~	✓
Moccasin Penstock Rehabilitation			~				~	~

Notes:

HHWP = Hetch Hetchy Water and Power SJPL = San Joaquin Pipeline

4.3.2 Regional Water

WSTD is responsible for the maintenance and operation of the large-diameter transmission pipelines west of AEP to the terminal reservoirs in San Francisco. WSTD's water transmission system comprises pipelines and tunnels that range greatly in terms of installation date, pipeline material, pipeline condition, and operational importance. Current inventory is shown in Table A-6 in Appendix A. Figure 4-2 presents a graphical summary of pipeline and tunnel installations by material and installation date. A graphical representation of cumulative pipeline and tunnel inventory by material and installation date is shown on Figure 4-3.




Figure 4-2: Linear Feet of Pipelines and Tunnels by Material and Installation Decade




Figure 4-3: Cumulative Pipelines and Tunnels Inventory

Transmission projects completed by the Spring Valley Water Company between 1890 and 1930 were constructed using either cast iron or wrought steel. The last reaches of the RWS with cast iron construction were decommissioned in the fall of 2014, after Bay Tunnel was brought into service. Joints for wrought-steel pipelines were riveted, as were the longitudinal seams that sealed the edges of the rolled-steel plates. Active pipelines from this period are a portion of the original SAPL No. 1, the 54-inch portion of CSPL No. 2, and BDPL No. 1.

For a brief period during the 1920s, design for large-diameter pipelines used a longitudinal mechanical "lockbar" that fastened the edges of rolled-steel plates, thus replacing longitudinal rivet courses. Only one such pipeline remains active, the 54-inch SAPL No. 2, constructed in 1928; SAPL No. 2 has riveted joints (except north of Merced Manor, where the pipeline is welded steel). In April 2019, construction replaced approximately 6,500 linear feet of 54-inch lockbar pipeline in the City of San Bruno.

Welded steel pipe (WSP) was developed in the early 1930s, and most construction contracts for the RWS used WSP during this time. Longitudinal or spiral seams are welded in the shop during fabrication with an automatic arc-welding process. Circumferential joints are arc welded in the field by hand.

Also, during the 1930s, RCP was developed: a steel cylinder with high-strength concrete cast on both sides of the cylinder and reinforcing steel bars embedded in the concrete outside the cylinder. Portions of BDPL Nos. 2 and 3, the upstream portion of BDPL No. 1, and Alameda Siphon No. 1 are RCP.

PCCP was developed in the 1950s. The design used less steel in the pipe construction, resulting in a lower material cost. The savings were achieved by relying on high-strength wire wound to a high tension around a concrete core to develop compressive strength in the pipe. In the 1960s, SFPUC began to offer PCCP as an option to bidders for pipeline construction. Two sections of BDPL No. 4, Alameda Siphon No. 3, San Antonio Pipeline, CSPL No. 3, and the Crystal Springs Bypass Pipeline were constructed with PCCP, for a total of 28 miles, all completed by 1988. In addition, HHWP has approximately 6.25 miles of PCCP. Because PCCP can fail suddenly with catastrophic COF, SFPUC no longer considers PCCP as an option for new pipelines.

Based on current condition assessment data, most of the PCCP pipelines are shown to be in good condition and safe to operate; however, SFPUC intends to eventually replace the existing PCCP with WSP. To replace all PCCP in the RWS would be a huge undertaking that will likely cost hundreds of millions of dollars. SFPUC will continue to operate the pipelines with PCCP but will perform inspections every 10 years to monitor for a change in condition.

Appendix A provides other pipeline and tunnel specifications, including length, capacity, and installation date. In addition to this report, SFPUC's "Data Book" (updated in 2011) provides extensive detail on pipelines and tunnels.

WSIP added seven new conveyance facilities: Alameda Siphon No. 4, San Antonio Backup Pipeline (SABPL), New Irvington Tunnel (Irvington Tunnel No. 2), BDPL No. 5, New Crystal Springs Bypass Tunnel, an extension of SAPL No. 3, and SJPL No. 4. Additionally, 16 sections of CSPL No. 2 were repaired. The 10-Year CIP also includes placeholder pipeline R&R projects. To date, these projects include replacement of additional reaches of SAPL No. 2 and additional repairs to CSPL No. 2 not covered under WSIP; additional seismic upgrades to SAPL Nos. 2 and 3 not covered under WSIP; lining repair to BDPL Nos. 1 through 4; and repair or replacement of BDPL No. 4, Sections A and D (PCCP sections).

4.3.2.1 <u>Multi-Asset Maintenance Activities</u>

Pipeline/Tunnel Maintenance Program and Condition Assessments

Regional Water has created a schedule for inspecting approximately 250 miles of pipeline over the next 20 years (see Appendix C: 20-Year Pipeline Inspection Schedule). This schedule was created using a multi-step process based on a pipeline's LOF and the COF model. This process emphasized public safety by prioritizing inspections for pipelines that have the highest possibility of catastrophic failure and are near public or critical infrastructure.

Inspections on the schedule are listed by quarters (generally listing the first day of the quarter as a placeholder for the inspection in that quarter). Once the actual date is determined, the inspection date on the schedule changes accordingly. After pipelines have been inspected, the pipeline condition information from the inspection is used to make an informed decision when prioritizing Capital Improvements projects.

The following scheduled inspections are planned for FY 25 and FY26:

- San Antonio Reservoir Pipeline Adit (Steel), Intake Structure Control House to Y20
- Hillsborough Tunnel and SSPL (Steel), M10 to M50
- Tesla Manifold Pipeline (Steel), Entire pipeline

- SSPL (Steel), M50 to CDD, reinspection due to fire incident
- CSPL1 (Steel), L60 to CDD
- CSPL2 (Steel), K40 to K50, CIP construction and inspection
- BDPL No. 3 (Steel), C26 to C40, warranty inspection
- BDPL No. 4 (Steel), D26 to D40, warranty inspection
- Stanford Tunnel (Steel), C40 to C50
- BDPL No. 1 (Steel), A60 to A70, CIP construction and inspection
- Balancing Reservoir Pipeline (PCCP), Entire pipeline

Valve Maintenance Program and Condition Assessments

The RWS includes more than 350 valves of various sizes, types, functions, and periods of installation. A complete 2022 inventory of main-line valves of the transmission system is shown in Table A-8 in Appendix A (a complete description for valves west of CRT is housed in WSTD's Valve Book Database). Bypass valves and service connection valves are not included. Approximately 50 major valves were added under WSIP. In most cases, valves more than 50 years in age have been rebuilt or replaced.

Many new valve lots were added prior to 2020 (Figure 4-4), just prior to and as part of WSIP. These include the cross-over valve lots on BDPL Nos. 3 and 4, where six facilities were completed, with the final two substantially completed in FY12. These valve lots significantly improve SFPUC's ability to operate around unplanned outages of one of these pipelines. The Paseo Padre and Grimmer valve lots on BDPL Nos. 1, 2, and 5, and the Tissiack/Crawford vaults on BDPL Nos. 3 and 4 support emergency earthquake recovery by enabling the system to be isolated on either side of the Hayward Fault.




Figure 4-4: Number of Valves Installed by Decade

In the San Pedro Valve Lot, two valve vaults were seismically upgraded, electric valve operators were modified, a new air valve was installed, and miscellaneous site drainage improvements were made. Elsewhere, a variety of valves (line and cross-over) were replaced/added in SAPL Nos. 2 and 3.

The valve exercise program was enhanced in 2008 to extend the life of installed valves. It is designed to extend the useful life of valves, increase reliability, and reduce life-cycle costs. The program is based on specifications outlined in the valve manufacturers' O&M manuals, and on best management practices (BMPs). The O&M manuals and BMPs establish the level and frequency of maintenance required. Valves are primarily exercised by utility plumbers and occasionally by the machine shop crew and watershed keepers. The goals are to assess the condition of the valves, actuators, and appurtenances, and to determine operational capabilities and reliability.

The current valve exercise program is structured to be consistent with the American Water Works Association (AWWA) standards; all valves are exercised at least once every 2 years (line valves and cross-over valves). If full operation of the valve does not disrupt system operations, the valve is fully opened and closed in the exercise. If full operation of the valve is not possible due to operational constraints, the valve is "bumped," i.e., opened (or closed, if already open) at approximately 10 to 15 percent, then closed (or returned to fully open).

WSTD owns 368 valves (not including valves at the treatment plants). Figure 4-5 shows that the current target for WSTD is to exercise 184 valves every year, or all 368 valves every 2 years.




Figure 4-5: Number of Valves Exercised at Water Supply and Treatment Division from 2014 through 2024

The other valve exercise program component addresses valves housed in water treatment facilities that are exercised and maintained by the operations staff. Most valves in water treatment facilities are routinely operated as part of normal operations.

Cross-Connection Mitigation for Transmission Pipeline Appurtenances

WQD is responsible for management and implementation of the RWS cross-connection controls program, in compliance with all applicable regulations and standards. The California Waterworks Standards, including cross-connection prevention requirements for air valves and blow off valves, went into effect in 2008. The Waterworks Standards apply to new facilities and existing facilities requiring repairs or replacement (most SFPUC pipelines were built well before the Waterworks Standards, some as far back as the 1920s). Since the Waterworks Standards went into effect, SFPUC has been focused on WSIP implementation. As part of WSIP implementation and Waterworks Standard compliance, SFPUC developed standard drawings for appurtenances (e.g., air valves and blow-offs), referencing them in specifications in WSIP as well as CIP contract documents. With WSIP winding down, SFPUC proactively and voluntarily implemented the RCCCP to address pipeline appurtenances at older RWS facilities (i.e., facilities constructed prior to the adoption of the Waterworks Standards that were not part of WSIP).

RCCCP was initiated in 2016 as a collaborative effort between WQD and WSTD. The project sought to upgrade applicable appurtenances in the RWS – air vacuum valves (AVVs), air release valves (ARVs), blowoff valves (BOs), and the vaults that house these appurtenances – to the latest standards, above and beyond regulatory requirements. Applicable regulations and standards are:

- SWRCB Cross-Connection Control Policy Handbook
- California Code of Regulations, Title 22, Waterworks Standards;
- AWWA Manual of Water Supply Practices M51;
- AWWA Standard C512; and
- WSTD Standard Drawings.

With the implementation of RCCCP, AVVs and ARVs in the RWS will be installed with the vent opening above grade; above the calculated 100-year flood water level; readily accessible for maintenance; constructed and designed to prevent exposure to rainwater or runoff, vandalism, and birds, insects, rodents, or other animals; and fitted with a downward-facing screened vent or a domed and screened cap.

The RWS has more than 250 miles of pipeline and tunnel that transmit potable water to wholesale customers and is fitted with approximately 1,400 installed appurtenances (AVVs/ARVs/BOs) of various sizes, types, functions, and periods of installation throughout the East Bay, South Bay, and Peninsula. The scope of the RCCCP includes:

- review of applicable regulations, and AWWA and SFPUC standards;
- development of checklists and templates for field assessment surveys;
- visual field assessments of all appurtenances and related vaults;
- identification of mitigation requirements and development of recommendations;
- grab field sampling of accumulated water in vaults, as needed;
- identification of inconsistencies in the current database of appurtenances and GIS;
- initial assessment reports for each pipe segment;
- implementation of mitigation measures for identified appurtenances, and revision of documents accordingly; and
- final assessment of mitigated appurtenances for onsite field verification and to document mitigation completion.

Due to the large number of appurtenances and pipelines in the RWS, the pipelines were grouped and prioritized for field assessment starting with the BDPLs, the longest pipeline segments to obtain representative data.


After assessments are completed, the project prioritizes mitigation recommendations using a riskbased approach. In general, appurtenances are deemed high risk when there is a relatively high probability of the water level reaching the valve opening inside the vault. Priority levels are described in the following paragraphs.


- **High Priority:** The AVV is below the riser's vent; the BO blind flange is not installed; or the BO does not have an air gap.
- **Medium Priority:** The AVV overflow rim is in the middle of the riser's vent; or the riser vent does not maintain a minimum of 6 inches of clearance above grade.
- Low Priority: The AVV overflow rim is above the riser's vent but missing items like bug screens; or the gate valve on the BO is not certified by NSF (formerly known as the National Sanitation Foundation).
- **None:** The appurtenance meets current standards.

An initial field assessment of all appurtenances in the RWS pipelines was completed up to the San Francisco County line. In 2022 and 2023, the project team completed an initial assessment of appurtenances in SAPL Nos. 1, 2, and 3, along with PAPL. In previous years of the project, initial assessments were completed for all other pipelines, including BDPL Nos. 1, 2, 3, 4, and 5; CSPL Nos. 1, 2, and 3; SSPL; Sunol Region; and CSSAPL. The initial assessment reports for all RWS pipelines were prepared and delivered to WSTD for mitigation planning and implementation.

The initial assessment reports include appurtenance information; noncompliance findings; FEMA's 100-year flood level, where applicable; and mitigation recommendations. The report also lists appurtenances that do not meet the current standards; that are vulnerable to flooding due to urban development; and that have been added, removed, or modified and do not match reference data from GIS and Maximo used by SFPUC.

The initial site assessment surveys for BDPL Nos. 1, 2, 3, 4, and 5; CSPL Nos. 1, 2, and 3; SSPL; Sunol Region; CSSAPL; SAPL Nos. 1, 2, and 3; and PAPL found that of the 1,382 appurtenances installed, 42 percent of the appurtenances are high priority; 12 percent are medium priority; and 26 percent are low priority. Of the appurtenances installed, 80 percent do not meet current standards, given that most of the pipeline sections of the RWS were constructed from the 1920s through the 1960s. Figure 4-6 shows mitigation priority level breakdowns for the RWS pipelines.





WSTD started implementing mitigation measures for BDPL Nos. 1 through 5 in September 2017. Mitigation work normally requires significant preparation, including site visits to every appurtenance to measure and document required mitigation, such as raising existing vaults; installing and replacing vault covers; raising existing air valves; adding "goosenecks" to existing air valves; lowering surrounding grades; installing bug screens to air vents; sealing below-grade vents; removing all galvanized fittings and piping; and replacing corroded bolts, fittings, and non-NSF certified materials.

Mitigation activities initially started slowly due to WSTD's resource constraints (e.g., plumbers and welders); other higher-priority maintenance work; new hiring and associated training; supply chain issues; and challenges related to the COVID-19 pandemic. In 2021 and 2022, WSTD increased resource allocation to this project, resulting in a higher mitigation rate than prior years. In 2023 and early 2024, mitigation work was delayed due to a high rate of field staff turnover, resulting from reassignments and retirements; extreme and frequent precipitation during the 2022-23 and 2023-24 wet weather seasons that hindered site access and mitigation work; pipeline disinfections; and unforeseen RWS pipeline emergencies that used up staff resources. These weather and staff constraints, and unforeseen events, slowed down mitigation activities. As of December 31, 2023, WSTD has completed 541 mitigations for the BDPLs (83 percent of all BDPL mitigations required), with 110 remaining BDPL mitigations.

In the fall of 2023, WSTD identified 60 existing appurtenances under roadways where permits may be required from various jurisdictions to perform mitigation work such as trenching in public roadways and relocation of appurtenances. Most of the appurtenances to be relocated are expected to require permanent easement acquisition of adjacent private or public properties, which may involve additional utility surveys, outreach to property owners, coordination with other agencies/cities/counties to procure permits, and coordination with SFPUC Real Estate Division and the City Attorney. Permit and easement acquisitions for these appurtenance sites

were unforeseen. In 2024, field visits were conducted to verify site conditions and mitigation requirements for these appurtenances. Upon review of the field surveys and as-built plans, it is expected that at least 43 of 60 appurtenance sites will need to be completed as part of the 10-Year CIP, given easement acquisitions, permitting, engineering drawings/site maps, and associated prep work. These sites will require significant additional budget and resources, with mitigation schedule delays. SFPUC will conduct further evaluation to determine appropriate budgets, alternatives, and a more realistic mitigation schedule for these sites.

Compared to the SRWS 2022 report, the revised mitigation schedule in Table 4-55 indicates about 12 months of delay for listed pipelines due to staffing constraints, weather conditions, and unforeseen pipeline emergencies. These pipelines are grouped by region in the revised schedule, providing more flexibility to perform mitigation work. Sites requiring pipeline shutdown fall under the deferred mitigation category because they depend on WSTD's future shutdown schedule, given operational constraints. The schedule for sites requiring permits and easement acquisitions will be determined depending on SFPUC's review of options and availability of resources. CSSAPL and Sunol Region raw water pipelines are moved to the end of the table because they are raw water-forced mains, not technically subject to cross-connection standards. Once the mitigation measures are implemented for other pipelines, SFPUC will decide whether to proceed with mitigation of raw water appurtenances.

Region or Category	Pipeline Segments ¹	Mitigation – Tentative Schedule
Bay Division	BDPL Nos. 3 and 4	May 2019 through September 2024
	BDPL Nos. 1, 2, and 5	June 2020 through September 2024
Peninsula	CSPL Nos. 1, 2, and 3, and SSPL (non-permit) SAPL Nos. 1, 2, and 3 (includes SSBPL)	October 2024 through September 2026
East Bay	Sunol Region (drinking water pipelines)	October 2026 through January 2027
South Bay	PAPL	February 2027 through April 2027
Deferred Mitigations	Sites requiring pipeline shutdowns, or located at flood zones	TBD ²
Permit Required Mitigations	Sites requiring permanent easement acquisition	TBD ³
Raw Water	CSSAPL and Sunol Region (raw water pipelines)	TBD ⁴

Table 4-55: Prioritization and Schedule for Cross-Connection Pipeline Mitigation

Notes:

¹ Initial field assessments of all appurtenances were completed in 2023.

² Mitigation schedule for sites requiring pipeline shutdown is TBD based on pipeline shutdown schedule.

³ Mitigation schedule for sites requiring permanent easement acquisition is TBD based on SFPUC's review of options and resources availability.

⁴ Mitigation schedule for raw water pipelines is TBD after mitigation of other pipelines is completed.

BDPL = Bay Division Pipeline

CSSAPL = Crystal Springs-San Andreas Pipeline

CSPL = Crystal Springs Pipeline

SAPL = San Andreas Pipeline

SFPUC = San Francisco Public Utilities Commission

SSBPL = Sunset Branch Pipeline

SSPL = Sunset Supply Pipeline

PAPL = Palo Alto Pipeline

TBD = to be determined

With initial assessments completed and mitigations underway, final assessments for validation of mitigated appurtenances began with BDPL Nos. 3 and 4 in 2022. During final inspections, photographs and notes were taken to verify and document the status of the mitigated appurtenances. As of December 31, 2023, final assessments have been completed for 245 appurtenances on BDPL Nos. 3 and 4, or 38 percent of mitigations for BDPL Nos. 1 through 5. Final assessments of mitigated appurtenances will be conducted for all listed pipelines.

The benefit of completing RCCCP goes beyond upgrading AVVs, ARVs, BOs, and vaults to the latest cross-connection standards. WSTD has leveraged this project to also repair damaged lids, add missing ladders, replace unsafe ladders, replace corroded fittings, and relocate appurtenances to more accessible locations away from traffic. As initial and final field assessments are conducted, valve riser and vault locations are updated in GIS and Maximo, effectively updating the asset registry for these assets.

Corrosion Monitoring/Maintenance Program

The corrosion protection program is one of the cornerstones of SFPUC's asset management and PM efforts. Investments in the program are cost-effective, greatly extend the useful life of buried assets, and reduce unplanned outages. In FY10, SFPUC and Schiff Associates updated the corrosion master plan. The primary objectives of the effort were to update the state of the corrosion protection system for buried assets in the Bay Area.

Prioritized projects derived from the plan were then sequenced in the CIP. The master plan first assessed transmission pipelines to determine the adequacy of corrosion protection of the existing system. Then the master plan made recommendations to repair inadequacies and provide improvements for ideal corrosion protection. The cost of repairs and improvements was estimated to be between \$18.3 and \$22.1 million in 2010. WSTD started implementing the recommendations in FY11, and have completed repairs and improvements over the last 14 years. Projects that save the most money and protect the longest stretches of assets are implemented first. The scope of work is implemented over many years to reduce operational, construction, and staffing conflicts. Coordination efforts include acquiring service agreements from the power utilities, determining the ROWs, permit reviews from local City jurisdictions along the Peninsula and East Bay, and outreach to adjacent property owners. Figure 4-7 summarizes the progression over time of CP on WSTD transmission pipelines.




Figure 4-7: Cathodically Protected Transmission Pipeline¹

The 2010 corrosion master plan identified corrosion potential and vulnerabilities from local ground conditions (e.g., corrosive soil or stray current) on 230 miles of transmission pipelines. With these field data, the study determined the adequacy of existing corrosion protection systems. Using those results, the study determined additional corrosion protection projects (including maintenance and monitoring work) that would most effectively and efficiently extend the remaining useful life of pipelines and buried assets.

The condition assessment performed as a part of the master plan found that existing CP systems on the WSTD transmission lines were operating at less-than-adequate levels. Of the cathodically protected pipelines, only 15 percent of the linear length was adequately protected; the remaining 85 percent received only partial to no protection, leaving the pipeline subject to corrosion. Note that since the implementation of the 2010 corrosion master plan, CP of the transmission system has improved 5 to 10 percent annually.

Based on the analysis, many of the pipelines in the Peninsula and South Bay are subject to stray currents. This phenomenon is typically the result of direct current (DC)-powered light-rail transit systems, or one of the numerous other buried utilities applying CP in the vicinity of WSTD pipelines.

The bulk of the pipeline alignments were installed in corrosive soils. The soil corrosivity is of concern due to the age of the infrastructure; specifically, that as pipeline coatings age they begin to deteriorate, exposing pipeline steel where corrosion is likely to occur. The more corrosive the

¹ Does not include SJPLs.

soil, the higher the corrosion rate will likely be, resulting in exacerbated metal loss or loss of pipeline wall thickness.

Remediation of existing CP systems and conducting extensive studies at the areas identified in the report are relatively inexpensive when compared to construction costs of structures such as pipelines and pump stations. Projects were categorized by the type of corrosion protection (for example, electrical isolation) and by pipeline to bring the transmission system to an ideal protected state against corrosion.

Information is gained from planning efforts, such as results of internal pipeline inspections, liquefaction conditions, locations of earthquake fault zones, criticality of particular pipelines to the Bay Area delivery capacity, adopted, and, to some extent, the adjacent land use and associated liabilities (i.e., public safety and claims) in the event of a pipeline leak or failure. This information is then used in conjunction with the results of the corrosion protection program to guide and prioritize maintenance, R&R, and capital planning.

Implementation of corrosion protection projects also requires knowledge of concurrent maintenance or capital projects, because implementation costs are significantly reduced when pipelines are taken out of service for more than one purpose. Similarly, many recommended corrosion protection projects become unnecessary if assets will be replaced under the current capital program, such as the submarine sections of BDPL Nos. 1 and 2.

SFPUC also performed an in-depth analysis of the major external corrosion-related issues for all transmission pipelines identified in the updated corrosion master plan. Detailed recommendations, including preliminary plans and specifications, were provided for all necessary corrective actions.

Active corrosion protection program elements and recent accomplishments from FY22 are listed in the following sections, along with plans for FY24 and beyond.

New Rectifier CP System

Rectifiers are used to convert alternating current (AC) power to DC power for CP systems. The negative terminal of the rectifier is connected to the pipeline, and the positive terminal of the rectifier is connected to the anode bed. A rectifier consists of a circuit breaker, diodes, and a step-down transformer with various coarse and fine taps for voltage adjustment.

In addition to renovating the existing rectifiers, the in-depth analysis identified additional CP systems that would be needed to bring the corrosion protection level of the underground pipelines up to the protection criteria established by the National Association of Corrosion Engineers. The CP system consists primarily of the rectifier and deep anode. In FY15, SFPUC used field survey information obtained from the in-depth analysis to put together a CP plan for installation of additional CP systems. Due to the many different locations identified for additional CP in the Peninsula and East Bay, the plan would be to prepare the construction bid packages in three separate phases by groups of pipelines. Table 4-56 describes the three phases and their corresponding scopes.

Phase #/Contract No.	Fiscal Year	Scope
Phase 1/Contract No. WD-2770	Design: FY15 - FY16 Construction: FY17 - FY19	Provide and improve the level of corrosion protection for the following pipelines: CSPL No. 1, CSPL No. 2, SAPL No. 1, and SAPL No. 2. The pipelines are along San Francisco, Daly City, South San Francisco, San Bruno, and Millbrae. During Phase 1, 10 new rectifiers and approximately 45 new test stations were installed.
Phase 2/Contract No. WD-2845	Planning/Design: FY19 - FY22 Construction: FY23 - FY25	Provide and improve the level of corrosion protection for the following pipelines: Palo Alto; and BDPL Nos. 1, 2, 3, and 4. The pipelines are along Stanford, Menlo Park, Palo Alto, Los Altos, Mountain View, Newark, and Fremont. During Phase 2, there will be 11 new rectifiers and approximately 200 new test stations installed.
Phase 3/Contract No. TBD	Planning/Design: FY23 - FY25 Construction: FY26 - FY28	Provide and improve the level of corrosion protection for the following pipelines: Alameda Siphon No. 2, Calaveras effluent and influent lines, SSPL, and SVWTP effluent line. The pipelines are along Sunol, Fremont, Hillsborough, Burlingame, Millbrae, South San Francisco, Colma, Daly City, and San Francisco. During Phase 3, there will be 19 new rectifiers and approximately 50 new test stations installed.

Table 4-56: Cathodic Protection for Water Supply and Treatment Division Transmission
Pipelines at Various Locations

Notes:

BDPL = Bay Division Pipeline CSPL = Crystal Springs Pipeline FY = fiscal year SAPL = San Andreas Pipeline SSPL = Sunset Supply Pipeline SVWTP = Sunol Valley Water Treatment Plant TBD = to be determined

The first phase provided 10 additional rectifiers with deep anodes to the transmission pipelines between San Francisco and Millbrae. The first phase also included installation of 45 additional test stations along the pipeline alignments; these stations were intended to accommodate the upcoming pipe-to-soil potential surveys (originally, 80 test stations were planned, but local agencies have been reluctant to issue permits along their ROWs). Fewer test stations translate to more time spent on performing corrosion surveys; nonetheless, due to the protection provided by rectifiers and anodes, the overall corrosion protection of the pipelines is not compromised. Construction for the first phase has been completed. The second and third phases will follow with an additional 30 rectifiers and deep anode columns, which will cover transmission pipelines in the Peninsula and the East Bay. It is anticipated that approximately 250 corrosion test stations will be installed as part of the second and third phases.

From FY22 to FY23, SFPUC performed over-the-line pipe-to-soil survey to confirm that the CP system is still providing the expected protection level, and to continue making adjustments to the CP system as needed.

In FY23 and continuing into FY25, CP Phase 2 began. Eleven new rectifiers with deep anodes are being constructed and about 200 test stations are being installed for the BDPL Nos. 1, 2, 3, and 4 along the Peninsula and East Bay, and for PAPL.

For FY24 to FY25, SFPUC will coordinate with Pacific Gas and Electric Company (PG&E) to study the power source locations for 19 new rectifiers, and to develop the design drawings and specifications for the Phase 3. SFPUC staff will be coordinating with local jurisdictions (San Francisco, Daly City, Broadmoor, South San Francisco, Millbrae, Burlingame, Hillsborough, Mountain View, Menlo Park, and Sunol) for permits needed in the public ROWs to install cable connections to the pipeline and power connections to the PG&E source.

New Remote Monitoring Units to Monitor Rectifiers

The remote monitoring units (RMU) allow SFPUC to remotely monitor the entire CP rectifier system via the Internet. Alarm parameters can be set to notify staff via email or text message in case of loss of AC power, out-of-range pipe-to-soil potentials, out-of-range current output, etc. Once the notification is received, staff will be able to remedy issues at each rectifier. Without the RMUs, staff would need to physically visit each site to manually read this information. There are 56 existing RMUs that monitor the existing rectifiers currently providing CP for the transmission pipelines. In FY21 and FY22, SFPUC continued to perform routine maintenance on the RMUs, most notably upgrading the cellular communications modules on each unit to the 4G service and replacing some units with newer antennas. During the Phase 2 construction in FY23 through FY25, there will be 11 additional RMUs installed. The routine maintenance with RMUs is being addressed by corrosion consultants. In general, RMUs have performed in accordance with the design.

CP Test Stations

CP test stations are essential for providing an easily accessible above-ground direct connection point to the pipelines for corrosion surveys. The test station typically consists of two wires, bonded to the pipeline underground and terminating on a test board either in a box flush to grade or on a post. It is important for survey efficiency to have the test stations at regular intervals along the pipeline alignment. SFPUC installed 45 new test stations in the first contract in FY18. Another 200 new test stations will be installed during the second contract in FY23 through FY25.

Pipeline Isolation/Continuity

Pipeline isolation and pipeline continuity are critical elements to establish the limited boundaries of CP. To effectively achieve the adequate levels of CP, protected pipeline segments must have continuity (through welded joints or bonding cables) from one piece of pipe (generally 40 feet long) to the next. The ends of the protected segment must be isolated using insulating flange kits. When these elements are not properly installed or when they fail, repairs (mostly through repairing the insulated flange joint) must be done before CP can be applied effectively. In rare instances, replacement of a gasket is needed, which requires dewatering the pipeline. The continued pipe-to-soil potential corrosion surveys will identify whether additional points of pipeline isolation will need to be added or restored.

Corrosion Surveys

The pipe-to-soil potential survey for each transmission pipeline will be performed every 2 to 3 years and will indicate whether the level of CP is adequate. The survey will also reveal whether field conditions have changed from the previous survey or whether CP interference is occurring in the field. The rectifiers are normally adjusted by changing the coarse and fine taps of the step-down transformer during the pipe-to-soil potential survey, to compensate for changes in the field conditions. After getting the existing CP systems back to an adequate corrosion protection level through the first three contracts, continued pipe-to-soil potential corrosion surveys will be performed to determine how the system is working and what additional CP upgrades or repairs are needed.

Water Meter Maintenance and Testing Program

The RWS relies on numerous flow meters to manage day-to-day operations; these meters are commonly referred to as system meters. WSTD also has meters that measure water deliveries to wholesale customers; these meters are referred to as wholesale meters. WSTD also has retail meters that measure water deliveries to suburban retail customer. Meter data are used for system hydraulics analysis, tracking daily and longer-term water use, and computing system water balances. Meter data are also used for financial purposes to support the computations for wholesale and retail water use, which directly affects cost allocations between these customer classes. In December 2023, WSTD completed the Water Meter Maintenance and Testing Procedures, also referred to as the Procedures Manual, which describes standard operating for the wholesale meters. Wholesale meter testing using the procedures in the Procedures Manual began in January 2024. Bay Area Water Supply and Conservation Agency and SFPUC staff are in discussion regarding the meter calibration and testing frequencies stated in the Procedures Manual. The Procedures Manual is expected to be updated before the next reporting period to reflect results of the discussion and to make further clarifications to the procedures.

RWS meters are generally organized into four categories: system input/output meters, in-line meters, county-line meters, and terminal reservoir level sensors. These meters are discussed in significant detail, including their inventory, required maintenance, and calibration, in the 2021 WSA. All the meters are regularly calibrated through an independent metering consultant. For this reporting cycle, 102 calibrations were performed.

The San Francisco/San Mateo county-line meters are a priority of the program due to their role in wholesale revenue requirement cost allocation. Table 4-57 lists the FY23 and FY24 calibration summary of the county-line meters. During this reporting cycle, all meters were found to be within the ±2 percent requirement of the 2021 WSA. By practice, whether or not a meter is found to exceed the calibration criteria, the independent meter consultant inspects the components, flushes lines, and conducts a repeat test on the same day. Maintenance of the meters includes regular cleaning and replacement of parts, as determined by the meter calibration consultant.

	Fiscal Year	Date	Crystal Springs No. 1	Crystal Springs No. 2	San Andreas No. 2	San Andreas No. 3	Sunset Supply (LMPS)	Sutro Pipeline (LMPS)	Total Per Quarter
		July 2022							
	1st Quarter	August 2022							6
		September 2022	~	✓	✓	✓	✓	✓	
		October 2022							
	2nd Quarter	November 2022							6
FY-23		December 2022	\checkmark	~	✓	\checkmark	\checkmark	\checkmark	
FΥ	3rd Quarter	January 2023							
		February 2023							6
		March 2023	\checkmark	\checkmark	\checkmark	\checkmark	\checkmark	\checkmark	
	4th Quarter	April 2023							6
		May 2023	\checkmark	~	✓	\checkmark	\checkmark	\checkmark	
		June 2023							
		July 2023							
	1st Quarter	August 2023							6
		September 2023	~	~	~	~	~	~	
		October 2023							
	2nd Quarter	November 2023	✓		~	~	~	~	6
24		December 2023		~					
FY-24		January 2024							3
	3rd Quarter	February 2024							
		March 2024	~	~	✓	Х	Х	Х	
		April 2024							
	4th Quarter	May 2024	✓	✓	✓	Х	Х	Х	3
		June 2024							1
	Total Cali For FY23 a		8	8	8	6	6	6	42

 Table 4-57: County Line Calibration Summary for the Current Reporting Cycle

Notes:

✓ = Calibrated

X = Skipped due to Sunset Supply Pipeline Shutdown

FY = fiscal year

LMPS = Lake Merced Pump Station

Each year, meter installations are evaluated for upgrades and improvement as part of the calibration routine. County-line meters are a priority, due to their role in wholesale revenue requirement cost allocation; consistent calibrations and maintenance ensure that meter equipment is upgraded as needed, thereby reducing the frequency of meter failure or poor performance. A summary of equipment replacement during this reporting cycle is presented in Table 4-58.

Table 4-58: Summary of Meter Equipment Replacement, Installation, and Improvement for the
Current Reporting Cycle

FY	Meter	D/P Transmitter and Related Plumbing	Data Logger	Pitot Tap	New Meter	Improve Meter Loop Wiring	Improve Instrument and SCADA Installation
FY23	San Joaquin Pipeline #1 at Albers Road						✓
FY24	BDPL No. 3 at Pulgas Valve Lot	✓					

Notes: BDPL = Bay Division Pipeline D/P = differential pressure FY = fiscal year SCADA = supervisory control and data acquisition

Regional Water System Water Balance Computation

Reliable and accurate meters are necessary to support customer billing and computation of the wholesale revenue requirement. Additional meters are used to compute the system water balance. Measured inflows into the water system were within 1.2 percent and 0.6 percent of the outflows (outflow defined as sales to customers, including San Francisco) for FY23 and FY24, respectively. These results suggest that overall system losses are small. In general, inflow should be slightly higher than outflow because pipelines are drained and flushed during inspection and rehabilitation. This amount is currently not part of the J Table computation but is tracked for regulatory reporting purposes.

Inflow into the system in some years may be less than out outflow; such occurrences are typically within the meter error range.

Automated Meter Infrastructure

Advanced meter infrastructure (AMI) meters have been in wide use at wholesale service connections since 2017. A small percentage of the wholesale service meters are not outfitted with AMI for reasons of either meter incompatibility or poor cellular service due to remote meter location. SFPUC's regional AMI relies on cellular signal for data transmission.

AMI technology enables more immediate evaluation of usage and water balance analysis. AMI data, in combinations with ongoing meter calibrations and maintenance, ensures that potential

sources of data errors are found early on during a data dropout occurrence. Together, analyses of AMI and system meter data lessen the occurrence of potential errors and result in timely corrective actions, as needed.

The AMI program allows customers to log in to a protected webpage to view their own water usage and track water deliveries from SFPUC in near real time. In late 2017, SFPUC retired the use of manual logbooks for recording wholesale customer billing meter reads for meters on AMI and began using AMI-generated meter read reports for billing purposes. Meter reads by manual field observation remains a viable option for obtaining meter reads for meters not on AMI, and as needed when warranted.

FY25 and FY26 Planned Work

In addition to replacing aging equipment, future projects include:

- installing new pitot taps at Irvington Meters 1 and 2;
- replacing pitot taps for Albers Road Meters 1, 2, and 3;
- assessing SA2 meter instrument cabinets for replacement;
- access improvements to the Sunset pitot taps;
- replacing two of the City of Hayward's 16-inch turbine meters with 12-inch ultrasonic meters; and
- replacing select turbine meters with electronic meters at various service connections.

4.3.2.2 Asset Descriptions, Maintenance, and Condition

WSTD is responsible for the maintenance and operation of multiple water transmission assets that work as a system to transport water from AEP to the county line of San Francisco. These assets include:

Alameda East Portal Alameda Siphons	Intertie Pump Stations (East Bay Municipal Utility	Crystal Springs Pipelines Nos. 1, 2, and 3
Calaveras Pipeline	District and Valley Water) Bay Tunnel	Sunset Supply Pipeline
San Antonio Pump Station San Antonio Pipeline and San	Palo Alto Pipeline	Hillsborough Tunnel San Andreas Pipelines Nos. 2
Antonio Backup Pipeline	Stanford Tunnel Dulage Value Let	and 3 Comuching Value Lot
Pond F3 East Alameda West Portal	Pulgas Valve Lot Pulgas Tunnel	Capuchino Valve Lot Baden Pump Station
Irvington Tunnel Nos. 1 and 2	Pulgas Pump Station	Baden Valve Lot
Irvington Portal	Pulgas Balancing Reservoir Crystal Springs Bypass	San Pedro Valve Lot
Bay Division Pipeline Nos. 1, 2, and 5	Tunnel and Pipeline	
Bay Division Pipeline Nos. 3 and 4	Crystal Springs Pump Station	

SFPUC regularly performs internal pipeline inspections as part of maintenance to proactively find potential vulnerabilities in transmission pipelines before major problems occur. A combination of acoustic sounding (with ball peen hammer) and visual inspections is performed

for all pipelines. For PCCP, an additional electromagnetic test is performed by a specialized contractor to determine the number of broken prestressed wires. These methods have been used throughout the industry for more than 10 years and are considered tried-and-true methods.

There are a variety of pipeline types and sizes that require specific inspection techniques to detect defects and assess conditions particular to each pipeline. Each type of defect requires unique repair methods to restore the pipeline. Some defects are significant enough, or extensive enough, to warrant replacement or slip-lining.

Most inspections of pipelines use visual methods to detect defects. The most common category of pipeline is WSP, representing more than half of the total length of transmission pipelines. Riveted pipe, the oldest in the transmission system, also makes up a significant portion of the transmission pipelines. RCP is also inspected visually. It is a rigid pipe but has flexible joints, a unique feature. Steel "lockbar" pipeline develops defects similar to those of WSP. Both RCP and lockbar pipe make up a small portion of the transmission pipelines. A combination of sounding (with a ball peen hammer) and visual inspections is performed for all pipelines. For a pipeline that has access difficulties and/or is not feasible for shutdown, acoustic leak detection inspection has been used in the past while the pipeline is in service.

WSTD performs electromagnetic inspections and visual inspections for PCCP. There are 22 miles of PCCP in RWS still in operation. PCCP modes of failure usually have catastrophic consequences. The concrete cylinder could rupture without warning when there is loss of prestress wiring. Electromagnetic inspections estimate the number of prestress wire breaks (when intact, these wires provide most of the hoop strength).

Potentially explosive gas is present in many SFPUC tunnels and there are long stretches of tunnel without intermediate access. The care that must be taken to ensure safety under these conditions, including safe pipe isolation practices for confined space entry, make tunnel inspections particularly difficult.

WSTD has created a schedule for inspecting approximately 250 miles of pipeline. This schedule was created using a multi-step process based on a pipeline's likelihood to fail, and the COF. This process emphasized public safety by prioritizing inspections for pipelines that have the highest chance of catastrophic failure and are near the public.

As pipelines are taken out of service for construction and O&M activities, associated pipeline appurtenances must be operable to accommodate isolation, dewatering, and disinfection activities. Consequently, all related appurtenance valves, vaults, and drainage paths, and some line valves, are serviced on affected pipelines as required.

After pipelines have been inspected, the pipeline condition information from the inspection will be used to help make an informed decision when prioritizing capital improvements projects for each pipeline segment.

Pipeline inspections that require entry in a dewatered pipeline were halted during the COVID-19 pandemic due to the poor ventilation in confined spaces. Pipeline maintenance inspections have resumed in FY23.

Alameda East Portal

Description. AEP west of CRT is in the hillside to the east of Calaveras Road. The Calaveras Fault Zone lies several hundred feet west of this location. The portal includes a 10.5-foot-diameter steel pipe with four pipe connections that distribute water to the four Alameda Siphons. Additionally, the portal overflow shaft includes a catchment basin and an emergency overflow pipeline discharging to an adjacent quarry pit.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. AEP is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Alameda Siphons

Description. The Alameda Siphons include four pipelines (AS-1 through AS-4) that stretch approximately 3,000 feet across the Sunol Valley, from AEP to AWP. The siphons were constructed from various materials between 1934 and 2011. All four pipelines cross the Calaveras Fault and Alameda Creek. Portions of AS-1 through AS-3 in the fault zone are susceptible to failing due to ground surface rupture. WSIP evaluated alternatives to bring AS-1 through AS-3 up to the latest seismic standards versus building a new siphon; construction of a new siphon was determined to be the best alternative. AS-4, added under WSIP in 2011, has been designed with special provisions to allow it to withstand these seismic forces.

Water flowing through the siphons originates from Hetch Hetchy and/or the SVWTP. The characteristics of the two sources, primarily hardness and alkalinity, vary significantly. The siphons therefore include a mixing manifold, which is designed to blend the water from the two sources and to mix SVCF chemicals to provide water of uniform characteristics downstream.

Maintenance. In May 2023, a leak was reported on the 90-inch AS-2, under Air Gap #1 in Sunol Valley. The failure was at a pipe joint, where the joint had separated, likely caused by creep from the Calaveras Fault. The joint was repaired by welding a 12-inch-wide steel band from inside the pipe. AS-2 was inspected for additional damages during the same shutdown. AS-2 is in good condition.

Condition. AS-1 and AS-3 are in fair condition. It is likely that AS-1 and AS-3 will fail following a 6.8 magnitude earthquake on the Calaveras Fault. AS-2 is in good condition and may survive the earthquake but will likely suffer ovalization. AS-4, designed to withstand a 6.8 magnitude earthquake on the Calaveras Fault, is in good condition. Air Gap Nos. 1 and 3, which connect AS-3 with SAPL and SABPL, have shown signs of upward movement. WSTD surveyors are regularly monitoring the movement. The Alameda Siphons are fit for service; however, the facilities may require capital investment to address pipeline movements at the air gaps at some point.

Calaveras Pipeline

Description. Calaveras Pipeline extends approximately 6 miles from the outlet tower of Calaveras Reservoir northward to SAPS. The pipeline was initially constructed in 1965, with major upgrades in 1992. This WSP pipeline ranges in diameter from 44 to 78 inches. Portions of the pipeline at Calaveras Dam was replaced as part of WSIP. The pipeline has four functions, which include:

- conveying water from Calaveras Reservoir to the SVWTP;
- conveying water from Calaveras Reservoir to the Calaveras Creek discharge point;
- conveying water from Calaveras Reservoir to San Antonio Reservoir by gravity; and
- conveying water from either San Antonio Reservoir or Hetch Hetchy to SVWTP.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Calaveras Pipeline is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

San Antonio Pump Station

Description. SAPS was constructed in 1968 and subsequently modified in 1992 and 2011. The latest modifications in 2012 included the replacement of three of the 1,000-horsepower electrical pump casings, the addition of two 1.5 MW emergency generators, and the seismic retrofit of the building for life safety. In 2015, the Water CIP funded further upgrades at SAPS by replacing one of three diesel-driven motors with an electrically driven one, along with related upgrades. SAPS is integral to the operation of the facilities in the Sunol Valley and operates to transfer water between the various facilities, including the Alameda Siphons, San Antonio Reservoir, and SVWTP.

Future projects under consideration include conversion of the remaining two diesel-driven pumps to electric pumps. Significant capital improvements even beyond what is scoped in the CIP will need to be considered for the Sunol Valley, due to the need for a pump station at that location, the age of the current pump station (built in the 1960s), and the age and condition of the SAPS substation equipment. A new pump station inevitably needs additional power; this may lead to upgrades to Calaveras Substation, which currently powers the entire Sunol Valley. Furthermore, performance requirements will need to be revisited with two criteria in mind: 1) Calaveras Reservoir as a water source; and 2) Hetch Hetchy aqueduct reliability to Sunol Valley. A needs assessment will be initiated along with initial planning discussions. The most obvious considerations would be replacing the diesel pumps, overhauling the electrical system, and possibly relocating the pump station off the Calaveras Fault. Those items would be evaluated in context.

Maintenance. During this reporting cycle, the interior of the pump casing for SAPS Pump #10 was recoated in 2022 due to pitting and corrosion that was discovered during a bearing replacement job. SAPS has also experienced electrical issues, resulting in SAPS being out of service for an extended period. In September 2023, the SAPS substation circuit breaker providing utility power to SAPS failed. Efforts to install a spare breaker and repair the failed breaker were both unsuccessful. A new circuit breaker has been purchased, but due to long lead times, the new breaker is not expected to be delivered and installed until August 2024. In the meantime, the SAPS pumps can be operated on generator power. Construction is also set to begin this year to replace components of the MCC, improve the HVAC system, perform a seismic retrofit of the control room, and install a new 150-kilowatt propane standby generator. Smaller future R&R projects include a monitoring system for the permissive devices to facilitate pump alarm troubleshooting for the SAPS electric pumps.

Condition. SAPS is in fair condition.

San Antonio Pipeline and San Antonio Backup Pipeline

Description. The San Antonio Pipeline was constructed in 1967 to connect San Antonio Reservoir to SAPS and the Hetch Hetchy transmission system at the Alameda Siphons. The SABPL was constructed in 2013 under WSIP. SAPL extends from the Alameda Siphons and SAPS to the outlet structure in San Antonio Reservoir. SABPL extends from the Alameda Siphons to the surface mining permit (SMP) 24 Quarry Pond, also referred to as Pond F3 East.

SAPL and SABPL serve several very important purposes, including:

- transferring water from CRT for storage or discharge;
- transferring water from Calaveras Reservoir to San Antonio Reservoir to optimize storage in the two East Bay reservoirs;
- transferring water from San Antonio Reservoir to SVWTP, either by gravity or via pumping at SAPS, depending on system hydraulics;
- recapturing water discharged to Pond F3 East by transferring to San Antonio Reservoir; and
- releasing water from the reservoir to San Antonio Creek.

SABPL provides SFPUC with greater flexibility in managing water quality while maintaining supply to customers through SVWTP. This function allows SFPUC to meet WSIP LOS during an unplanned outage of the Hetch Hetchy water supply.

Maintenance. Leak detection inspections were performed for SAPL and SABPL in August 2021. Inspections were carried out using Pure Technologies' Sahara acoustic leak detection tool for the 60-inch SAPL and the 66-inch SABPL. No leaks were found. Pipe joints were inspected via closed-circuit television and were found to be normal in appearance for the majority of the sections inspected. No additional work was done since 2021.

Condition. SAPL and SABPL are in fair condition; however, ground fissures, 800 feet in length, had developed between the pipelines and an active mining quarry (SMP 30) operated by Oliver De Silva in the Sunol Valley. Geotechnical investigations concluded that the 800 feet of ground fissures will not lead to pipe failure in the event of a landslide. However, there are signs that these fissures are migrating to the north and will cross the SFPUC pipelines at some point. Additional geotechnical studies are being conducted to assess the risks of pipeline failures with the fissures moving north. SAPL and SABPL are fit for service.

Pond F3 East

Description. Pond F3 East is a facility that provides supplemental storage to discharge, recapture, and/or treat Hetch Hetchy water that does not meet primary and/or secondary drinking water standards. Under normal operation, Pond F3 East is used when CRT has been out of service for an extended period (e.g., Hetch Hetchy shutdown) and needs to be flushed prior to returning Hetch Hetchy supply into the RWS. Water captured in Pond F3 East is then pumped into San Antonio Reservoir or directly to SVWTP, where it can be treated for future use. The operating level of Pond F3 East is 195 to 240 feet and has a storage capacity of approximately 150 million gallons in this elevation range. The current pumping system was not designed to pump lower than 195 feet; however, contractor support has been used in the past to pump below this elevation to create additional storage capacity based on operational needs and projections.

Maintenance. No PM was required or completed during this reporting cycle. Pond F3 East continues to operate in its current form, allowing for noncompliant water and water flushed from CRT after HHWP shutdowns to be recovered. The current operating protocol is to use one of the two submersible pumps to transfer water from Pond F3 East to San Antonio Reservoir. One of the two submersible pumps was replaced in 2021. The performance and reliability of the older pump will be monitored and assessed for future replacement to ensure adequate pumping redundancy. In the next 2 years, the existing supplemental floating barge pumps, which allow for additional storage capacity by lowering the operating level of Pond F3 East to 185 feet, will be rehabilitated. The two floating barge pumps, discharge piping, and electrical equipment will be replaced to enhance performance and reliability.

Condition. Pond F3 East is in good condition and is fit for service.

Alameda West Portal

Description. AWP is on the western hillside of Calaveras Road. The Calaveras Fault Zone lies east of this location. The portal is where all four Alameda Siphons converge into Irvington Tunnel Nos. 1 and 2.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. AWP is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Irvington Tunnels Nos. 1 and 2

Description. There are two Irvington Tunnels; the original Irvington Tunnel No. 1 was constructed in 1934 and Irvington Tunnel No. 2 was completed in 2014 as part of WSIP. All of the water from Hetch Hetchy and SVWTP flows westward through these two tunnels, from the Sunol Valley to the BDPLs.

Irvington Tunnel No. 1 is 18,193 feet long and has a 10.5-foot inside diameter. The tunnel is completely lined with either concrete or gunite.

Irvington Tunnel No. 2 is slightly longer, with a length of 18,300 feet. This tunnel was excavated in a shape resembling a horseshoe and finished with an 8.5-foot-diameter WSP with cement mortar lining (CML).

Although Irvington Tunnel No. 2 was built as a redundancy to Irvington Tunnel No. 1, both tunnels are typically in service under normal operations.

Maintenance. Irvington Tunnel No. 2 was inspected in 2020, using an ASI Marine Falcon remotely operated vehicle (ROV). Visual and sonar data were collected as the tunnel was inspected from AWP to the Irvington Portal. Review of tunnel profiles generated from the sonar data did not reveal any anomalies in the tunnel other than the sediment that was observed visually. These tunnels are inspected every 20 years, and the next inspection will not be needed until 2040.

Condition. Irvington Tunnel No. 1 and Irvington Tunnel No. 2 are in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Irvington Portal

Description. Water from Hetch Hetchy and SVWTP is conveyed from the Sunol Region to the BDPLs through the parallel Irvington Tunnels Nos. 1 and 2. The Irvington Portals provide the ability to isolate each tunnel on its downstream end, distribute water to the five BDPLs, and isolate each pipeline on its upstream end. SFPUC maintains a number of key water quality compliance points, including one at the Irvington Portals. The RWS pH compliance is determined at the Irvington Portals. Other water quality parameters monitored at the Irvington Portals include pH, fluoride, free ammonia, total chlorine, and turbidity.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Irvington Portal is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Bay Division Pipeline Nos. 1, 2, and 5

Description. BDPL Nos. 1, 2, and 5 are aligned in a relatively direct line westward from Irvington Portal in Fremont to Pulgas Valve Lot in Redwood City, a distance of approximately 21.5 miles. BDPL No. 1 was constructed in 1925; BDPL No. 2 in 1935/1936; and BDPL No. 5 in 2016 as part of WSIP, together with the new Bay Tunnel. With the new Bay Tunnel transmitting the combined flow from the three pipelines, the old BDPL Nos. 1 and 2 crossing the Bay have been decommissioned.

BDPL Nos. 1, 2, and 5 cross the Hayward Fault and therefore are especially susceptible to major seismic events on that fault.

The East Bay reach is approximately 37,600 feet (7.1 miles) in length. Seismically resistant crossings of the fault were constructed under WSIP. The initial (easternmost) 6,800 feet of BDPL No. 1 is constructed of 57-inch steel cylinder concrete pipe. The remainder is constructed of 60-inch riveted steel pipe. The first 6,800 feet of BDPL No. 2 is constructed of 62-inch steel cylinder concrete pipe and the remainder with 66-inch wrought steel pipe. BDPL No. 5 is constructed of 72-inch WSP.

The Peninsula reach is approximately 47,900 feet (9.06 miles) in length. BDPL No. 1 is constructed of 60-inch riveted steel pipe. BDPL No. 2 is constructed of a combination of 66-inch wrought steel pipe and 62-inch steel cylinder concrete pipe. BDPL No. 5 is constructed of 60-inch WSP.

Maintenance. Planning and design continue for a capital project to repair lining defects that were identified from previous inspections along BDPL Nos. 1, 2, 3, and 4, and to repair lining defects expected to be identified in future inspections. When this contract is in place, maintenance inspections and lining repairs can be performed within the same shutdown, eliminating the need for a second shutdown to perform repairs.

The scope of work primarily consists of removing corrosion accumulated at pipe joints from spalled CML, applying new cement mortar or dielectric lining, and cleaning debris and sediment found inside the pipe. During this reporting cycle, the Conceptual Engineering Report (CER) was finalized, and the project entered the design phase. New scope was added to this project for safe pipe isolation and entry to support the internal lining repair work. New isolation valves and line

stops were added to this project, which would allow for double block and bleed to safely carry out the work. The CER was amended to capture the additional scope for safe pipe isolation.

Condition. BDPL Nos. 1, 2, and 5 are in good condition and fit for service; however, BDPL Nos. 1 and 2 require capital investment to address maintenance lining defects through the As-Needed Pipeline Repair project.

Bay Division Pipeline Nos. 3 and 4

Description. BDPL Nos. 3 and 4 proceed southward from the Irvington Portals, circling around the southern end of San Francisco Bay, through the northern part of San Jose and Santa Clara, and then northward to the Pulgas Valve Lot in Redwood City. This alignment differs significantly from that of BDPL Nos. 1, 2, and 5, providing increased reliability and the ability to efficiently serve the numerous wholesale customer turnouts. Each pipeline consists of approximately 33.9 miles in length. BDPL No. 3 was constructed in 1952, and BDPL No. 4 was constructed in 1967.

BDPL Nos. 3 and 4 also cross the Hayward Fault and therefore can be particularly impacted by major seismic events on that fault. The diameters of the pipelines range from 72 to 96 inches, and the pipelines materials include steel-RCP, PCCP, and WSP. Before 2015, the distance between crossover points on these two pipelines spanned approximately 8 miles. This large distance made it difficult to take segments of pipe out of service for planned inspections and maintenance. The BDPL Nos. 3 and 4 Crossovers project added three additional isolation/crossover facilities, so that the distance between crossover points is approximately 4 miles. This makes the system easier to maintain and repair, and increases the number of customers that would likely receive water within 24 hours following a major seismic event. The three crossover facilities constructed under WSIP are near the Guadalupe River, Barron Creek, and Bear Gulch.

BDPL Nos. 3 and 4 cross the Hayward Fault near the intersection of Mission Boulevard and Interstate 680 (I-680). The maximum credible seismic event would have resulted in probable failure of both pipelines. For BDPL No. 3, a new 300-foot-long concrete vault with articulating sections was constructed under Mission Boulevard. The vault houses a section of 72-inch WSP, with ball joints and slip joints that can accommodate pipeline displacement during a seismic event. BDPL No. 4 is designed to fail in a controlled manner that does not cause failure to BDPL No. 3. The seismic upgrade of BDPL Nos. 3 and 4 provides a seismically reliable conduit crossing the Hayward Fault.

BDPL Nos. 3 and 4 converge into the Stanford Tunnel. This tunnel is 810 feet long and 90 inches in diameter and is constructed of cement-lined and coated-steel pipe.

Maintenance. In response to Union Pacific Railroad's (UPRR's) plan to add a second track over BDPL Nos. 3 and 4 in Santa Clara, a R&R project was initiated to address pipe protection from loading of the second track system. The scope of work includes sliplining 75 feet of pipe across the railroad's ROW, adding new manholes to improve access, and making improvements to the appurtenances to meet current water quality standards. The construction was completed in June 2024.

UPRR notified SFPUC that additional tracks will be added over BDPL Nos. 3 and 4 on another parcel of land in Milpitas. Temporary load mitigation measures will be implemented to protect

the existing BDPL pipelines. A new R&R project will be initiated for the permanent load mitigation measures for BDPL Nos. 3 and 4 across the UPRR's tracks.

The PCCP segment of BDPL No. 4, between valves D60 and D70, had developed several leaks at the mid-Peninsula region. In 2017, an inspection found numerous circumferential cracks in the last 1.5 miles that parallel Edgewood Road in Redwood City. These cracks were mostly small, with only a few were as wide as 0.125 inch. Although the circumferential cracks are not currently posing a structural risk, leaks have developed over time due to corrosion of the inner steel cylinder. This is believed to be a result of the circumferential cracks. In August 2020, an external condition assessment was performed for certain pipe segments to verify the number of broken prestressed wire wraps found in the 2017 inspection. That same assessment was performed to verify the accuracy of the electromagnetic method of determining wire breaks, with positive confirmation of accurate results.

In March 2021, BDPL No. 4 was shut down to repair leaks caused by the circumferential cracks. WEKO-seals were installed to seal the leaks. Condition assessment findings and leaks confirmed that both the broken prestressed wires and circumferential cracks need to be addressed. In September 2021, another leak was found in the same stretch, immediately downstream of a previously repaired leak. Suspecting that new leaks may have been developing as the pipeline went through wet and dry cycles, staff decided against another pipeline shutdown. Staff implemented BMPs by diverting the leak to a nearby storm drain. It was noted that since its initial discovery, the leak has remained low and stable. The leak is being dechlorinated and monitored.

Condition. BDPL Nos. 3 and 4 are in fair condition. However, a more comprehensive study of the segment between Valve D60 and D70 will be needed to analyze the cause of failure and determine a strategy for remediation. A capital project is currently underway to address pipes with a large number of broken prestressed wire wraps and leaks with mitigation under Phase 1 repair. Phase 2 will investigate the root cause of the leaks and determine next steps for rehabilitation and replacement of the BDPL No. 4 PCCP.

BDPL Nos. 3 and 4 are fit for service. However, the PCCP segment requires active monitoring and capital investment to address both the broken prestressed wires and the circumferential cracks through the BDPL No. 4 PCCP Repair project.

Intertie Pump Stations (East Bay Municipal Utility District and Valley Water)

Description. SFPUC co-owns an intertie in Hayward with East Bay Municipal Utility District (EBMUD). The facility is operated by the City of Hayward in accordance with a Joint Exercise of Powers Agreement between SFPUC, City of Hayward, and EBMUD. SFPUC also co-owns an intertie with Valley Water in Milpitas. Each intertie offers the principal parties access to other regional water suppliers in emergencies or during planned maintenance of a critical facility. The EBMUD-SFPUC intertie was completed in 2007, and the SFPUC-Valley Water intertie was completed in 2000.

Maintenance. The City of Hayward is the designated lead for O&M at the EBMUD-SFPUC intertie. Beginning July 1, 2024, and for the next 5 years, Valley Water is designated as the lead O&M party for the SFPUC-Valley Water intertie. The intent is for Valley Water to remain the lead O&M party going forward. However, staff from the two agencies will confer every 5 years to confirm that this designation is still appropriate. The O&M lead designation and other changes to the longterm O&M agreement are captured in the second amendment to the O&M agreement executed in June 2024.

Condition. The EBMUD-SFPUC and SFPUC-Valley Water intertie pump stations are in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Bay Tunnel

Description. Bay Tunnel has a 9-foot-finished-diameter WSP with CML. The tunnel is approximately 26,200 feet (4.96 miles) in length. The tunnel, which is 70 to 110 feet below sea level, extends from Newark Valve Lot and Tunnel Portal to the Ravenswood Valve Lot and Tunnel Portal.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Bay Tunnel is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Palo Alto Pipeline

Description. PAPL starts at Redwood City Valve Lot and follows a southeast alignment toward Palo Alto, a distance of approximately 5.35 miles. PAPL transports water from the BDPL Nos. 1, 2, and 5 to four wholesale customers: California Water Service, Stanford University, City of Menlo Park, and City of Palo Alto. The pipeline was built in 1937; it is 36 inches in diameter and constructed of WSP with coal tar lining.

PAPL traverses the urban corridor of Redwood City, Atherton, Menlo Park, Stanford, and Palo Alto. Most of the pipeline resides within public domain, making maintenance and repair difficult. Moreover, because PAPL does not have service redundancy in the RWS, making shutdowns for repair very disruptive to these wholesale customers.

Maintenance. PAPL was shut down for inspection in April 2024. Inspection was carried out using an ultrasonic technology tool. Inspection results, including remaining steel wall thickness, corrosion hot spot, and out-of-roundness measurements, are needed to plan for a repair and replacement project.

Condition. PAPL is in fair condition and fit for service. The 2024 inspection results will be used to inform any future capital project.

Stanford Tunnel

Description. BDPL Nos. 3 and 4 converge at Stanford Tunnel Valve House East, travel for the 810-foot length of Stanford Tunnel, and diverge and continue on again as separate pipelines at Stanford Tunnel Valve House West. Stanford Tunnel was constructed in 1952. It is approximately 810 feet long and 7.5 feet in diameter. The entire length of the tunnel is lined with steel pipe.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Stanford Tunnel is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Pulgas Valve Lot

Description. Pulgas Valve Lot, near the intersection of Edgewood and Crestview Roads in Redwood City, is the western terminus of the BDPLs. The purposes of this facility are to: 1) combine the flows from the five pipelines just upstream of the Pulgas Tunnel; 2) maintain pressure in the upstream reach of pipe; 3) provide isolation for the upstream reaches of pipe; and 4) measure and totalize the flow rate for reporting purposes.

Maintenance. Routine PMs, such as monthly facility safety and security inspections, quarterly water quality analyzer maintenance, and monthly emergency generator testing, were completed during this reporting cycle. Recent improvements completed at the Pulgas Valve Lot include upgrades to provide standby generator running status signals and position of the automatic transfer switch for remote monitoring and data trending to SCADA.

Condition. Pulgas Valve Lot is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Pulgas Tunnel

Description. Pulgas Tunnel was constructed in 1924. Its original purpose was to transmit water from the BDPLs at Pulgas Valve Lot to the Peninsula reservoirs. In 1969, Crystal Springs Bypass System was constructed to enable water from Pulgas Tunnel to be diverted northward directly to the low-pressure zone pipelines on the northern portion of the Peninsula. Pulgas Overflow Channel is the release point for excess water in the RWS, discharging water from the tunnel to UCSR. It is also the first "daylight" point for Hetch Hetchy water downstream of Moccasin Reservoir.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Pulgas Tunnel is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Pulgas Pump Station

Description. Pulgas Pump Station was constructed in 1975. The facility, together with the Pulgas Balancing Reservoir, functions to dampen pressure fluctuations and maintain the hydraulic grade line in the upstream Pulgas Tunnel and Crystal Springs Bypass Tunnel. The pump station wetwell also serves as the diversion point for water to be released to the Peninsula reservoirs. Pulgas Pump Station includes five large-capacity pumps that pump from the wet well into the Pulgas Balancing Reservoir. The pump station also includes two flow-control valves that operate to allow reservoir water to flow back into the wetwell and subsequently the tunnel. The wetwell also includes two overflow weirs that allow water to flow either into the downstream Pulgas Dechloramination Facility before discharge to the UCSR, or directly to UCSR.

Maintenance. Routine periodic PMs were performed during this reporting period to maintain operation of the vertical turbine pumps, valves, actuators, and ancillary systems. Much of the facility has equipment dating back to the original construction. Proposed long-term improvements for the next few years include a full rehabilitation, including the replacement of all electrical switchgear and medium-voltage starters, replacement of the existing slide gate and knife gate valves, and replacement of the five vertical lift pumps.

Condition. Pulgas Pump Station is in fair condition and fit for service. However, the facility requires capital investment to address the aging equipment and deficiencies described above.

Pulgas Balancing Reservoir

Description. The Pulgas Balancing Reservoir was constructed in 1975. The Pulgas Balancing Reservoir is connected to the Pulgas Pump Station with a single 96-inch PCCP. The reservoir has a 60-million-gallon capacity, which can augment water supply in the Peninsula during peak demands.

Maintenance. Reservoir cleaning was initiated under contract by Liquivision Technology Diving Services in September of 2020 and completed by Underwater Resources, Inc., in March 2021.

Condition. Pulgas Balancing Reservoir is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Crystal Springs Bypass Facilities

Description. Crystal Springs Bypass Facilities, which include Crystal Springs Bypass Tunnel, New Crystal Springs Bypass Tunnel, and Crystal Springs Bypass Pipeline, allow water to be transmitted by gravity directly to the low-pressure zone pipelines on the northern portion of the Peninsula, thereby bypassing the Peninsula reservoirs and HTWTP. Crystal Springs Bypass Tunnel and Pipeline were constructed and put into service in 1969. The New Crystal Springs Bypass Tunnel, constructed in 2011 under WSIP, is a continuation of the Crystal Springs Bypass Tunnel, providing redundancy to Crystal Springs Bypass Pipeline.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Crystal Springs Bypass Facilities are in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Crystal Springs Pump Station

Description. CSPS and its associated valve lot are below LCSD. The primary purpose of these facilities is to transfer water from LCSR to San Andreas Reservoir approximately 4.5 miles north. Because LCSR has a maximum water surface elevation of 288 feet, compared to 449 feet for San Andreas Reservoir, pumping is necessary to transfer water to San Andreas Reservoir. The pump station includes four large-capacity pumps that are used in transferring water between the reservoirs. Each of these pumps is 2,250 horsepower and rated at 48 mgd. The maximum pump station capacity is 192 mgd. Water at San Andreas Reservoir is used to supply HTWTP. CSPS was completely replaced in September 2014 as part of WSIP. The project scope included upgrading for seismic performance, switchgear and starters, and variable-speed pumps. Collectively, the operational upgrades permit more off-peak pumping, lowering power and operating costs.

Maintenance. In FY21, warranty repair work was completed on two of four existing flow-control check valves that were showing premature wear and failure. In FY24, the flow-control valves are again starting to show signs of premature wear and will be evaluated for repair or possible replacement or redesign. The operational issues with the new UPS discussed in the last reporting period have been resolved after technical assistance from the equipment vendor and additional testing. Recently, circuit board failures in the VFD units that control speed for two of the pumps have led to pumps being out of service while awaiting parts and repair. Maintenance and improvements completed during this reporting period include the preventive maintenance of

electrical switchgear equipment in late 2023 and the installation of a new built-up roof for the pump station building in August 2023.

Condition. CSPS is in fair condition. The facility requires capital investment to address the maintenance deficiencies described above.

Crystal Springs Pipelines Nos. 1, 2, and 3

Description. CSPL Nos. 1, 2, and 3 transport Hetch Hetchy and/or Sunol water to customers along the Peninsula and to the potable water terminal storage reservoirs in the City of San Francisco. CSPL No. 1 is currently not in service, except for a small, rehabilitated section. CSPL Nos. 2 and 3 both carry Hetch Hetchy water north to the City of San Francisco, across approximately 20 miles, by gravity. University Mound Reservoir is the terminus for CSPL Nos. 1, 2, and 3. The operating portions of CSPL No. 1 were replaced with 44-inch-diameter WSP in 1956. CSPL No. 2 ranges in diameter from 54 to 60 inches. Construction materials include WSP and riveted wrought iron with a sliplined WSP. CSPL No. 3 is a 60-inch PCCP.

Maintenance. CSPL No. 2, between valves K10 and K30, is a 60-inch welded steel pipeline with coal tar lining. Some of it traverses steep terrain with narrow access, making maintenance and repair difficult. An ongoing capital project will realign 1.5 miles of the pipeline, replace the existing coal tar lining, add new manholes to improve access, and make improvements to appurtenances to meet current water quality standards.

CSPL No. 2, between valves K40 and K50, is a 60-inch welded steel pipeline with coal tar lining. An ongoing capital improvement project will replace the existing coal tar lining, add new in-line isolation valves to allow for greater operational flexibility, add new manholes to improve access, and improve appurtenances to meet current water quality standards.

Condition. CSPL Nos. 1, 2, and 3 are in fair condition and fit for service. CSPL No. 3 was inspected in November 2017 and found to be in good condition. However, CSPL No. 2 requires capital investment to address lining and access deficiencies through the CSPL No. 2 Reaches 2 and 3 Rehabilitation project and CSPL No. 2 Reach 5 Lining Replacement project.

Sunset Supply Pipeline

Description. SSPL transports Hetch Hetchy water north to the City of San Francisco, across approximately 20 miles, by gravity. The pipeline is 60 inches in diameter and constructed of WSP. SSPL delivers water to the Sunset Reservoir ("high zone") after being pumped at the LMPS. Flow through SSPL is controlled at several valves and valve lots along its alignment. SSPL can also receive pressure-reduced high zone flow from the 60-inch SSBPL via the Capuchino Pressure-Reducing Valve.

Maintenance. SSPL between Baden Valve Lot and Lake Merced Pump Station was shut down for inspection in February 2024. During the inspection, the electromagnetic tool caught on fire due to a short on the battery. No one was injured from the fire, but the pipeline was damaged. SFPUC continues to work with the inspection contractor to: 1) perform tasks including metal testing to confirm that structural integrity of the steel has not been affected; and 2) remove and replace the damaged coal tar lining so SSPL can be returned to service. The inspection will need to be rescheduled.

Condition. SSPL is in good condition and fit for service. From the available electromagnetic inspection result, most of the pipeline is in good condition. Only two locations with wall loss up to 80 percent were noted. These defects will be repaired prior to returning SSPL to service.

Hillsborough Tunnel

Description. Hillsborough Tunnel, collinear with SSPL, was constructed in 1957. It is approximately 5,200 feet long and 7.5 feet in diameter. The entire length of tunnel is lined with steel pipe.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Hillsborough Tunnel is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

San Andreas Pipelines Nos. 2 and 3

Description. SAPL Nos. 2 and 3 are the primary high zone transmission lines for the SFPUC water system. From HTWTP, SAPL Nos. 2 and 3 parallel each other up to San Pedro Valve Lot and supply water to high zone service locations in the northern Peninsula and the City of San Francisco. The terminus of SAPL No. 2 is at Sunset Reservoir. With the extension of SAPL No. 3, constructed under WSIP, SAPL No. 3 terminates at Merced Manor Reservoir. Completion of the Peninsula Pipelines Seismic Upgrade project addressed seismic vulnerabilities along SAPL Nos. 2 and 3 and provided an operational work-around to ensure delivery of high-zone water to terminus reservoirs after a seismic event.

SAPL Nos. 2 and 3 are interconnected at both Baden Pump Station and San Pedro Valve Lot. At San Pedro, R60, a 42-inch butterfly valve, is throttled remotely from HTWTP to regulate high zone flow to San Francisco. SAPL No. 2 is made of 54-inch lockbar steel. SAPL No. 3 is made of 66-inch PCCP sliplined with steel, and a 36-inch steel extension from San Pedro Valve Lot to Merced Manor Reservoir.

Maintenance. SAPL No. 2 was replaced, between valves R12 and R20, in 2021. Approximately 6,500 linear feet of 54-inch-diameter lockbar steel pipe was replaced with WSP.

Condition. SAPL Nos. 2 and 3 are in fair condition. However, additional segments of lockbar steel in SAPL No. 2 are being considered for replacement due to concerns regarding corrosion. SAPL Nos. 2 and 3 are fit for service.

Capuchino Valve Lot

Description. Capuchino Valve Lot is one of two valve lots designed to reduce pressure from the high- to low-pressure zone pipelines (the other pressure-relief valve [PRV] location is at Baden). The rated capacity of the facility is 80 mgd.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Capuchino Valve Lot is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Baden Pump Station

Description. Baden Pump Station allows for the transfer of water from the low-pressure zone (SSPL and CSPL No. 2) into the high-pressure zone (SAPL Nos. 2 and 3) to supplement water supply from HTWTP. The pump station includes three large pumps, each rated at approximately 16.5 mgd at 255 feet discharge head. The pumps are driven by 1,000-horsepower, variable-frequency motors. Surge control vessels are provided on both the suction and discharge sides of the pump station.

Maintenance. Routine PM activities on the pumping system, compressors, backup generators, and other functions have maintained the operational reliability of Baden Pump Station. In 2024, electrical switchgear maintenance was performed, and the diesel storage and day tanks were inspected and cleaned to remove tank sediment. There are no capital investments planned for this pump station at this time.

Condition. Baden Pump Station is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

Baden Valve Lot

Description. Baden Valve Lot includes the interconnecting valves and pumps necessary to isolate pipeline reaches, transfer between the high-pressure and low-pressure zones, and transfer between pipelines of the same pressure zone.

The facility includes multiple interconnections between the two high-pressure service zone pipelines (SAPL No. 2 and SAPL No. 3) and between the four low-pressure service zone pipelines (SSPL, CSPL No. 2, CSPL No. 3, and SAPL No. 1). There is also a special energy-dissipating Monovar valve, part of the PRV station, that allows transfer of water from the high-pressure zone to the low-pressure zone.

Maintenance. No PM was required or completed during this reporting cycle.

Condition. Baden Valve Lot is in good condition and fit for service. No deficiencies in condition were noted during this reporting cycle.

San Pedro Valve Lot

Description. San Pedro Valve Lot includes interconnecting valves necessary to isolate pipeline reaches, transfer between the high-pressure and low-pressure zones, and transfer between pipelines of the same pressure zone.

The facility includes multiple interconnections between the two high-pressure service zone pipelines (SAPL No. 2 and SAPL No. 3) and between the low-pressure service zone pipeline (SSPL).

Maintenance. No PM was required or completed during this reporting cycle.

Condition. San Pedro Valve Lot is in good condition and fit for service. No deficiencies were noted during this reporting cycle.

4.3.2.3 <u>Capital Improvements</u>

Regional Water currently has capital projects in its water transmission program, representing a total capital investment of \$426.4 million. Regional Water also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

As-Needed Pipeline Repair Project (Approved Budget \$16.49; Substantial Completion: 2029)

Scope. This project will increase system reliability by reducing the duration and number of outages because a prequalified, as-needed contractor will be available to complete repairs immediately following inspections or in emergencies. This project will repair/replace regional pipeline segments that will be inspected over the next 5 years, including any emergency repairs that may be needed. In addition, this project will install new valves to provide for safe pipeline entry for the construction contractor and for future operational needs. The initial construction contract will be 4 years and will be combined with project 10036840, BDPL Nos. 1 through 4 lining repair. Subsequent projects and construction contracts may be initiated to parallel WSTD's inspection program. The scope of work for the initial construction contract includes: 1) pipeline replacement by open trench; 2) pipeline repair work; 3) protection of sensitive (wetland and creek) areas; 4) protection of utilities and infrastructure; 5) traffic control; 6) site/vegetation restoration; 7) paving restoration; and 8) installation of seven large-diameter valves for safe pipeline. Any significant replacement needs will be addressed in subsequent expansions of this project or other independent projects.

Milestones Completed During the Reporting Cycle. The milestone achieved during this reporting cycle is summarized in Table 4-59.

Table 4-59: As-Needed Pipeline Repairs Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete		
35% design	February 29, 2024		

Corrosion Control (Approved Budget \$36.5 Million; Substantial Completion: 2028)

This project will implement the corrosion protection and control program recommended in the 2010 Corrosion Control Master Plan and the comprehensive report completed in 2013. Sites identified with the worst levels of corrosion were bundled up in the master plan in three phases. Phase 1 construction work for 10 sites was completed and accepted on August 27, 2019. Phase 2 has 11 sites and is currently in the design phase. Phase 3 is anticipated to include work on as many as 19 sites.

Scope. The Corrosion Control project includes three phases. Phase 1 was completed on August 27, 2019, and Phase 2 is currently in construction phase for 11 sites. The scope of work for Phases 1, 2, and 3 includes: 1) furnishing and installation of CP systems; 2) installation of rectifiers and anodes at a depth of approximately 300 feet; 3) installation of testing stations for pipelines; 4) installation of specialized galvanic and impressed current CP systems; 5) installation of RMUs; and 6) installation of isolation protection systems.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-60.

Table 4-60: Corrosion Control (Phase II) Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete
NTP	March 13, 2023
Design phase	April 30, 2022
Bid and award	March 2023
50% construction	June 2024

Note:

NTP = Notice to Proceed

San Antonio Pump Station Motor Control Center Upgrades Project (Approved Budget \$15.62 Million; Substantial Completion: 2027)

Scope. SAPS is one of the key facilities in Sunol Valley. It was constructed in 1965 and modified in 1990 and 2009. The existing MCCs (MCC-A, MCC-B, and MCC-C) have been in service since the 1960s and are approaching the end of their useful life. To maintain reliable operation at SAPS, the existing MCCs are being replaced, and facility walls not previously upgraded are being seismically retrofitted. In addition, a new propane generator will replace the existing diesel generator to provide reliable backup power for the facility. The scope of work includes the following: 1) replacement of the existing diesel generator with a new 150-kilowatt propane generator; 2) installation of a new fire suppression system; 3) replacement of the existing lighting system and installation of new exit lighting; 4) replacement of the existing HVAC system; 5) architectural design that accommodates clean agent fire suppression; 6) seismic retrofit of east wing walls and foundation; 7) installation of temporary MCCs; 8) demolition and replacement of existing MCCs; 9) demolition of the existing main control panel and pump status control panel; 10) replacement of the existing underground power and control conductors; 11) installation of new RTU with UPS; and 12) replacement of existing communication system for Control and SCADA room.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-61.

Table 4-61: San Antonio Pump Station Motor Control Center Upgrades Project MilestonesCompleted During the Current Reporting Cycle

Milestone	Date Complete		
CEQA categorical exemption	January 3, 2023		
Bid advertisement	June 29, 2023		

Notes:

Conceptual Engineering Report not required for San Antonio Pump Station Motor Control Center.

CEQA = California Environmental Quality Act

BDPL Nos. 1 through 4 Lining Repair Project (Approved Budget \$22.17 Million; Substantial Completion: 2029)

Scope. This project will repair the lining in segments of BDPL Nos. 1 through 4 and other regional pipelines over the next 5 years. The initial construction contract period will be 3 years; combined with Project 10035029, As-Needed Pipeline Repair, it will provide a sufficient guaranteed scope. Subsequent construction contract(s) will be issued to parallel WSTD's inspection program. Work for this project includes: 1) CML repair; 2) dielectric lining repair, including the removal, handling, and disposal of coal tar lining; and 3) dewatering and installing seven large-diameter valves for safe pipeline entry.

Milestones Completed During the Reporting Cycle. The milestone achieved during this reporting cycle is summarized in Table 4-62.

Table 4-62: BDPL Nos. 1 through 4 Lining Repair Project Milestones Completed During the Current Reporting Cycle

Milestone	Date Complete		
35% design	February 29, 2024		

Note:

BDPL = Bay Division Pipeline

BDPL No. 4 PCCP Repair Project (Approved Budget \$54.75 Million; Substantial Completion: 2027)

Scope. In recent inspections of BDPL No. 4 Segment D, constructed of PCCP, a large number of wire breaks and circumferential cracks were found in the last 1.25 miles of pipeline that parallels Edgewood Road in Redwood City. In addition, several leaks have surfaced at circumferential cracks and where the pipeline transitions from PCCP to steel. Phase 1 of this project will increase system reliability by rehabilitating approximately 650 feet of 84-inch-diameter BDPL No. 4 PCCP in Redwood City. The project scope includes: 1) excavation, shoring, backfilling, and compaction; 2) demolition of PCCP; 3) replacement of approximately 530 feet of pipeline by open trench; 4) sliplining approximately 120 feet of pipeline; 5) protection of sensitive (wetland and creek) areas and utilities/infrastructure; 6) traffic control; and 7) site/vegetation and paving restoration. The Phase 2 project will analyze and address the remaining 1.25 miles of Segment D.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-63.

Table 4-63: BDPL No. 4 PCCP Repair Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete		
PCCP failure risk analysis report	August 15, 2022		
Exploratory geotechnical work	December 31, 2023		
AAR draft	May 8, 2024		

Notes:

AAR = Alternative Analysis Report

BDPL = Bay Division Pipeline

PCCP = prestressed concrete cylinder pipe

CSPL No. 2 Reach 5 Lining Replacement Project (Approved Budget \$41.4 Million; Substantial Completion: 2027)

Scope. CSPL No. 2 runs from CSPS to University Mound Reservoir. It delivers potable and emergency water supply to San Francisco and to several cities along the Peninsula. The 60-inchdiameter Reach 5 of CSPL No. 2, in the cities of South San Francisco and San Bruno between Millbrae Yard and Baden Pump Station, is more than 80 years old and has extensive lining failures. The project scope includes: 1) replacement of approximately 3.8 miles of coal tar lining with cement mortar or dielectric lining; 2) upgrades for about 34 appurtenances to meet current standards; and 3) improvements to access and shutdown flexibility for maintenance by installing five manway structures and one 48-inch-diameter valve on SAPL No. 1 near Baden Pump Station.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-64.

Table 4-64: CSPL No. 2 Reach 5 Lining Replacement Project Milestones Completed During theCurrent Reporting Cycle

Milestone	Date Complete		
35% design	September 30, 2023		
65% design	April 11, 2024		

Note:

CSPL = Crystal Springs Pipeline

CSPL No. 2 Reaches 2 and 3 Rehabilitation Project (Approved Budget \$82.81 Million; Substantial Completion: 2028)

Scope. CSPL No. 2 spans from CSPS to University Mound Reservoir. It delivers potable water supply to San Francisco and several cities along the Peninsula. Reaches 2 and 3 of CSPL No. 2 in the Town of Hillsborough, unincorporated areas of San Mateo County, the City of San Mateo, and the City of Burlingame are more than 80 years old and deteriorated in some locations; Reach 2 is on slopes that are eroding and Reach 3 has extensive lining failures. This project scope includes: 1) realignment of Reach 2 to the existing abandoned CSPL No. 1 alignment; 2) replacement of the coal tar lining of Reach 3; and 3) improvement for access to the pipeline entry.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-65.

Table 4-65: CSPL No. 2 Reaches 2 and 3 Rehabilitation Project Milestones Completed Duringthe Current Reporting Cycle

Milestone	Date Complete		
Final conceptual engineering report	April 17, 2023		
GIR	October 25, 2022		

Notes:

CSPL = Crystal Springs Pipeline

GIR = Geotechnical Investigation Report

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-66.

	Level of Service							
Project	Drinking Water Quality	Regional Seismic Reliability	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
As-Needed Pipeline Repair Project			~					
Corrosion Control			~					
SAPS MCC Upgrades Project			~					
BDPL Nos. 1 through 4 Lining Repair Project	~		\checkmark					
BDPL No. 4 PCCP Repair Project	~		~			~		
CSPL No. 2 Reach 5 Lining Replacement Project	~		~					
CSPL No. 2 Reaches 2 and 3 Rehabilitation Project	~		~					

Table 4-66: RWS Water Transmission Projects – Levels of Service Project Drivers

Notes:

BDPL = Bay Division Pipeline

CSPL = Crystal Springs Pipeline

MCC = motor control center

PCCP = prestressed concrete cylinder pipe

RWS = Regional Water System

SAPS = San Antonio Pump Station

4.4 Water Distribution Assets

4.4.1 Hetch Hetchy Water

HHWP owns and operates a network of water distribution assets that treat and distribute water to its upcountry offices, shops, and residences. These include:

Cherry Water Distribution System O'Shaughnessy Water Distribution System Early Intake Water Distribution System Moccasin Water Distribution System

4.4.1.1 Asset Descriptions, Maintenance, and Condition

Cherry Water Distribution System

Description. The Cherry Water Distribution System provides fresh drinking water to 10 to 20 SFPUC and United States Forest Service (USFS) employees and families working and living in the Cherry Compound. The system consists of two storage tanks; a Memcor filtration system (replaced in 2023); and a water distribution system consisting of water lines, pipes, and valves of various sizes. Water is sourced from a small diversion dam on Cottonwood Creek.

Maintenance. Table 4-67 summarizes maintenance work.

Table 4-67: Cherry Water Distribution System Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Water Sampling	Completed weekly	Sampled for chemistry and bacterial agents
Instrument	Completed weekly	Instruments verified weekly
Verification and Calibration	Completed monthly	Instruments recalibrated monthly
Inspection	Completed weekly	Facility inspected by HHWP Stationary Engineer
Surveillance and Monitoring	Continuously monitored	Plant monitored continuously via internal dataloggers

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance

Condition. Cherry Water Distribution System is in good condition and fit for service.

O'Shaughnessy Water Distribution System

Description. O'Shaughnessy Water Distribution System provides fresh drinking water to one to five SFPUC and National Park Service (NPS) employees and families working and living in the O'Shaughnessy Compound, as well as visitors to four rental cottages in the compound. The system consists of two storage tanks; a UV facility; and a water distribution system consisting of water lines, pipes, and valves of various sizes. Water is sourced directly from Hetch Hetchy Reservoir at O'Shaughnessy Dam.

Maintenance. Table 4-68 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Water Sampling	Completed weekly	Sampled for chemistry and bacterial agents
Instrument	Completed weekly	Instruments verified weekly
Verification and Calibration	Completed monthly	Instruments recalibrated monthly
Inspection	Completed twice weekly	Facility inspected by HHWP Stationary Engineer
Surveillance and Monitoring	Continuously monitored	Plant monitored continuously via SCADA alarms

Table 4-68: O'Shaughnessy Water Distribution System Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. O'Shaughnessy Water Distribution System is in fair to good condition and fit for service; however, given the age of the water distribution piping, an updated condition assessment is recommended.

Early Intake Water Distribution System

Description. Early Intake Water Distribution System provides fresh drinking water to five to 15 SFPUC, NPS, and USFS employees and families working and living at Early Intake; Kirkwood Powerhouse; and visitors to the Early Intake Bunkhouse. The system consists of two storage tanks; a UV facility; and a water distribution system consisting of water lines, pipes, and valves of various sizes. Water is sourced from Hetch Hetchy Reservoir via Kirkwood Powerhouse.

Maintenance. Table 4-69 summarizes maintenance work.

Table 4-69: Early Intake Water Distribution System Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Water Sampling	Completed weekly	Sampled for chemistry and bacterial agents
Instrument	Completed weekly	Instruments verified weekly
Verification and Calibration Completed mo	Completed monthly	Instruments recalibrated monthly
Inspection	Completed thrice weekly	Facility inspected by HHWP Stationary Engineer
Surveillance and Monitoring	Continuously monitored	Plant monitored continuously via SCADA alarms

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Early Intake Water Distribution System is in fair to good condition and fit for service; however, given the age of the water distribution piping, an updated condition assessment is recommended.

Moccasin Water Distribution System

Description. Moccasin Water Distribution System provides fresh drinking water to approximately 300 SFPUC employees and residents who work or reside in the town of Moccasin. The system consists of three storage tanks; a UV facility; and a water distribution system that consists of water lines, pipes, and valves of various sizes. Water is sourced from Hetch Hetchy Reservoir via Moccasin Penstock.

Maintenance. Table 4-70 summarizes maintenance work.

Table 4-70: Moccasin Water Distribution System Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Water Sampling	Completed daily	Sampled for chemistry and bacterial agents
Instrument	Completed weekly	Instruments verified weekly
Verification and Calibration Completed mor	Completed monthly	Instruments recalibrated monthly
Inspection	Completed daily	Facility inspected by HHWP Stationary Engineer
Surveillance and Monitoring	Continuously monitored	Plant monitored continuously via SCADA alarms

Notes:

HHWP = Hetch Hetchy Water and Power

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Moccasin Water Distribution System is in fair to good condition and fit for service; however, given the age of the water distribution piping, an updated condition assessment is recommended.

4.4.1.2 <u>Capital Improvements</u>

There are no capital improvements for HHWP's Water Distribution assets included in the current 10-year capital plan.

4.4.2 Regional Water

In addition to the maintenance and operations of the large-diameter transmission pipelines, Regional Water provides retail water service to a small number of individual residential and commercial customers outside of San Francisco. Retail operations in the RWS are limited to distribution systems in Sunol.

4.4.2.1 Asset Descriptions, Maintenance, and Condition

Town of Sunol

Description. Sunol, with an approximate population of 250 people, receives their potable and raw water from SFPUC via two 12-inch pipelines. These are the only sources of water into Sunol and cannot be shut down for a significant period of time.

The Sunol potable water pipeline is 12 inches in diameter and consists of transmission and distribution lines. The transmission line runs in the south-to-north direction, starts at the western end of the mixing chamber on AWP, parallels Calaveras Road for the most part, crosses I-680, and ends at the Town of Sunol Pump Station in Sunol Yard. The 12-inch Sunol raw water pipeline is fed by the San Antonio Pipeline. It starts at Valve Y-35 (an isolation valve on the San Antonio Pipeline) and follows the same alignment as the potable pipeline that ends at Sunol Yard.

The Sunol potable water distribution pipeline varies in size. Beginning at the Town of Sunol Pump Station, it runs uphill to feed two 120,000-gallon storage tanks. The main pressure zone,

which serves the majority of the population of Sunol, is gravity-fed, supplied by the tanks. The secondary pressure zone, along Kilkare Road in the upper elevation (north of the primary zone), requires the assistance of the Kilkare Booster Pump Station to service water through a 6-inch steel line to the residences in this zone.

The majority of the 12-inch Sunol potable and raw water pipelines were replaced with new mortar-lined ductile iron pipe in 2000 and 2013, from AWP to Sunol Yard. A completed WSIP project, the Sunol Fire Suppression System project (2016), upgraded segments of the distribution system and added a dedicated pipeline for firefighting purposes. A separate project completed by WSTD in 2017 added a dedicated fire pump to boost firefighting pressure to the secondary pressure zone. With the new Town of Sunol Fire Pump in place, both the primary and secondary pressure zones now have adequate firefighting volume and pressure.

Segments of the Sunol's water system have been upgraded through a succession of projects in the past, but there are segments of pipeline from the original construction that are still operable today.

Maintenance. The 12-inch Sunol pipeline, which crosses Arroyo de la Laguna in Sunol, was originally installed below the creek bed. However, with erosion, the pipeline is now completely exposed. This section of the pipeline feeds both the potable and firefighting waterlines to Sunol. A capital project has been initiated to replace the section of the pipeline crossing the creek.

A portion of the 12-inch Town of Sunol potable and raw waterlines conflicts with Alameda County Transportation Commission's (ACTC) project to widen I-680. A partial replacement would introduce a potential point of failure in Caltrans' ROW. In consideration of this, SFPUC requested a complete replacement across the freeway and funded a portion of the replacement outside of ACTC's work limit. The construction for the replacement section began in 2021.

In November 2021, two leaks were reported on the Town of Sunol 12-inch raw water line. The leaks occurred in the construction site of ACTC's project to widen I-680. The leaks, caused by corrosion, were repaired with leak clamps. To minimize point loads, ACTC has since installed steel plates over the 12-inch potable and raw waterlines. The corroded sections of the 12-inch raw waterline were replaced in spring of 2024.

Condition. Sunol potable and raw waterlines are in good condition and fit for service. However, the facilities require capital investment to replace the segments across the creek and I-680 through the Town of Sunol Pipeline Improvement project.

4.4.2.2 <u>Capital Improvements</u>

Regional Water currently has capital project in its water distribution program, representing a total capital investment of \$12.27 million.

Town of Sunol Pipeline Improvement Project (Approved Budget \$12.27 Million; Substantial Completion: 2026)

Scope. Since the Year 2000, SFPUC has replaced all but two segments of the Town of Sunol pipeline system through the Town of Sunol Fire Suppression project. This project will complete the replacement of the last two segments, replacing sections of the pipeline that cross the Arroyo de Laguna Creek (Creek Crossing) and under I-680. The upstream section of pipeline, which feeds

both the potable line and fire suppression line to Sunol, is exposed under the creek and in danger of failing under I-680. Pipeline failure at either location has significant consequences because all fire and potable water in Sunol is dependent on the rehabilitation of this 12-inch line. This project will reduce unplanned outages from pipe breaks and improve on delivery reliability.

This project is broken up into two portions. The scope of work is summarized in the following paragraphs.

Creek Crossing

- Replace approximately 550 feet of 12-inch-diameter pipeline crossing Arroyo de Laguna Creek with 12-inch-diameter Ductile Iron Pipe (DIP), class 53
- Open-cut trench across the creek
- New tie-in points with gate valves
- Creek restoration and tree removal in pipeline alignment

I-680 Crossing

• MOU agreement with ACTC to replace existing 12-inch-diameter Town of Sunol pipelines under I-680 for \$1.3 million

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-71.

Table 4-71: Town of Sunol Pipeline Improvement Project Milestones Completed During theCurrent Reporting Cycle

Milestone	Date Complete
Completed MND	October 25, 2023
95% design	September 30, 2023
100% design	December 31, 2023
CEQA	December 31, 2023

Notes:

CEQA = California Environmental Quality Act MND= Mitigation Negative Declaration

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-72.

Table 4-72: RWS Water Distribution Projects – Levels of Service Project Drivers

		Level of Service					
Project	Water	Regional Seismic Reliability	Delivery		In-City Delivery Reliability	Environ. Steward.	Sustain- ability
Town of Sunol Pipeline Improvement Project			\checkmark				

Note:

RWS = Regional Water System

4.5 **Buildings and Grounds**

SFPUC owns and operates multiple buildings and grounds facilities that are spread over a large geographical area to support the O&M of RWS.

4.5.1 Hetch Hetchy Water

HHWP is responsible for the O&M of multiple buildings and grounds assets throughout its operational territory. Staff-assigned reporting facilities include:

Moccasin Compound	Oakdale Yard
South Fork Yard	Warnerville Yard

In addition to the above-listed facilities, HHWP also operates and maintains smaller-scale buildings and grounds facilities at Eleanor, Cherry, O'Shaughnessy, Early Intake, and Rock River.

4.5.1.1 Asset Descriptions, Maintenance, and Condition

Moccasin Compound

Description. Moccasin Compound is the main corporate yard for HHWP. Staff in Moccasin includes Management, Engineering, Business Services, Water and Power Operations, Asset Management Services, Strategic Capital Planning and Special projects, and Power Compliance groups. All groups at the compound are housed in either the administration facility, building, shop, or trailers. Staff support for the larger working groups are discussed in the following paragraphs.

- Engineering staff: Operating groups include Maintenance Engineering, Renewal and Replacement Projects, and Information Technology (IT) Services. Maintenance Engineering comprises the civil, mechanical, and electrical disciplines, including drafting and surveying support. IT Services includes operating technology, IT, and SCADA staff.
- Business Services: Operating groups include Budget and Finance for Operating and Capital; Contracts; Records; Property Management; and Personnel, Training, and Recruitment.
- Water and Power Operations: Staff includes power system operators (who also perform dispatch); power transmission system east linemen, who maintain overhead electrical lines from O'Shaughnessy to Don Pedro Reservoir; operation transmission planning engineers; water and power planning staff; watershed management staff; plumbers shop staff; equipment maintenance shop staff; carpenter shop staff; electrical shop staff; paint shop staff; tech shop staff; ROW crew for the area from Priest Watershed to Newark; and vegetation management crew for the entire project area.
- Asset Management Services: Staff includes planners, schedulers, asset services, and materials procurement and management. Security is also included in this work team.

In addition to HHWP staff, multiple trailers house infrastructure teams, water quality staff and labs, and NRLMD staff who support HHWP maintenance and programs.

Maintenance. Table 4-73 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed monthly	Security inspection
	Completed monthly	Safety inspection
	Completed monthly	Spill prevention control and countermeasures
	Completed annually	Facility fire suppression testing
Maintenance	Completed monthly	Backup generator maintenance
	Completed annually	Defensible space vegetation clearing
	Completed every 3 years	Domestic water tanks maintenance

Table 4-73: Moccasin Compound Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. There are many offices and storage facilities in Moccasin Compound. The condition of these facilities varies greatly; the use of some buildings is limited due to their condition (e.g., the Old Moccasin Powerhouse). Needs continue to be addressed and capital projects identified.

South Fork Yard

Description. South Fork Yard is east of the town of Groveland. The yard is occupied by the South Fork ROW maintenance crew. This crew maintains HHWP facilities from O'Shaughnessy to the eastern side of the Priest Reservoir watershed.

Maintenance. Table 4-74 summarizes maintenance work.

Name of PM	Completion Date(s)	Description	
Inspection	Completed monthly	Security inspection	
	Completed monthly	Safety inspection	
	Completed monthly	Spill prevention control and countermeasures	
	Completed bi-annually	Facility fire suppression testing	
Maintenance	Completed annually	Defensible space vegetation clearing	

Table 4-74: South Fork Yard Preventive Maintenance Summary(July 1, 20220, through June 30, 2024)

Note:

PM = preventive maintenance

Condition: The South Fork Yard is fit for service.

Oakdale Yard

Description. Oakdale Yard is in the city of Oakdale. The yard is occupied by maintenance engineering staff dedicated to the HHWP facilities west of Don Pedro Reservoir.

Maintenance. Table 4-75 summarizes maintenance work.

Table 4-75: Oakdale Yard Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed monthly Security inspection	
	Completed monthly	Safety inspection
	Completed monthly	Spill prevention control and countermeasures
Maintenance	Completed annually	Defensible space vegetation clearing

Note:

PM = preventive maintenance

Condition: The Oakdale Yard is fit for service.

Warnerville Yard

Description. Warnerville Compound is east of the city of Oakdale. The yard is occupied by power transmission system west linemen who maintain overhead electrical lines from Don Pedro Reservoir to Newark. It should be noted that the power transmission system west linemen also support maintenance of overhead electrical lines owned by WSTD.

Maintenance. Table 4-76 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed monthly Security inspection	
	Completed monthly	Safety inspection
	Completed monthly	Spill prevention control and countermeasures
	Completed bi-annually	Facility fire suppression testing
Maintenance	Completed annually	Defensible space vegetation clearing

Table 4-76: Warnerville Yard Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition The Warnerville Yard is fit for service.

4.5.1.2 <u>Capital Improvements</u>

HHWP currently has capital projects in its buildings and grounds program, representing a total capital investment of \$128.5 million. HHWP also has multiple R&R projects that are smaller in

scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

Moccasin Old Powerhouse Hazard Mitigation (Approved Budget \$13.5 Million; Substantial Completion: 2031)

Scope. Moccasin Old Powerhouse is in Moccasin Compound. The scope for this project is to design and install mitigation measures to prevent the building from collapsing due to multiple structural and nonstructural issues, and to prevent hazardous materials (such as lead-based paint and asbestos) from contaminating the water in Moccasin Reservoir.

Milestones Completed During the Reporting Cycle. The milestone achieved during this reporting cycle is summarized in Table 4-77.

Table 4-77: Moccasin Old Powerhouse Hazard Mitigation Project Milestones Completed During the Current Reporting Cycle

Milestone	Date Complete
AAR	May 2024

Note:

AAR = Alternatives Analysis Report

Moccasin Engineering and Records Building (Approved Budget \$88.7 Million; Substantial Completion: 2028)

Scope. This project will replace three trailers at Moccasin Compound. These three trailers provide office space for Records and Engineering staff. Project scope includes is to complete design and construction of a 25,000-square-foot building for Records and Engineering office space, as well as records archive and a controlled/secure location space for business servers.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-78.

Table 4-78: Moccasin Engineering and Records Building Project Milestones Completed Duringthe Current Reporting Cycle

Milestone	Date Complete
Design Memorandum of Understanding for public works executed	February 2023
Job initiation form approved	March 2023
Programming with design team completed	March 2023
Concept design package completed	June 2024

Moccasin Warehouse Building (Approved Budget \$26.3 Million; Substantial Completion: 2030)

Scope. The scope of this project is to construct a new 9,000-square-foot warehouse in the Moccasin Compound to store large equipment and critical spare components for the HHWP project. The building will include office space for warehouse staff, including records retention for warehouse and materials documentation.

Milestones Completed During the Reporting Cycle. The project is scheduled and budgeted to begin in 2025; therefore, no milestones were achieved during this reporting cycle.

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-79.

 Table 4-79: HHWP Buildings and Grounds Projects – Levels of Service Project Drivers

		Level of Service						
Project	Drinking Water Quality	Seismic	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
Moccasin Old Powerhouse Hazard Mitigation	~		~					
Moccasin Engineering and Records Building			~					
Moccasin Warehouse Building			~					

Note:

HHWP = Hetch Hetchy Water and Power

4.5.2 Regional Water

WSTD owns and operates multiple buildings and grounds facilities, spread over a large geographical area, that support the O&M of RWS.

4.5.2.1 Asset Descriptions, Maintenance, and Condition

Sunol Yard

Description. Sunol Yard is an East Bay corporation yard. It has an Administration Building occupied by WSTD and NRLMD; the rest of the yard is shared by utility plumbers, electricians, electronic maintenance technicians, and the auto, welding, painting, and buildings and grounds, and NRLMD shops. It is also the operational hub for East Bay gardeners, carpenters, house plumbers, custodians, stationary engineers, watershed keepers, and biologists. Sunol Yard is surrounded by the Water Temple, the Alameda Creek Watershed Center, the Sunol Native Plant Nursery, and the shared Hetch Hetchy Yard used for storage.

Maintenance. Between July 1, 2022, and June 30, 2024, WSTD performed PM throughout Sunol Yard on the HVAC system compressors. R&R projects for the paint/blast booths, emergency generator, HVAC system, and main entrance and exit gates will be addressed in FY25 and FY26. Protection over the chemical totes and oil barrels, along with embassy-style fencing, will be in construction in FY25.

Condition. The Sunol Yard is in very good condition.

Millbrae Yard

Description. Millbrae Yard is the main corporate yard for WSTD. The Administration Building is occupied by WSTD management; engineering; administration; water treatment; distribution

operations; maintenance; 24-hour dispatch; planners; IT; and water quality labs, offices, and cubicles. There is a warehouse for supplies, auto shop, gardener shop, carpenter shop, electrician shop, house plumber shop, welding shop, paint shop, and a utility plumbers shop. NRLMD has a cottage and a trailer.

Maintenance. WSTD performed PM between July 1, 2022, and June 30, 2024. The Administration Building was built in the late 1960s, and its mechanical equipment is nearing the end of its useful life. Both the yard security upgrade and building HVAC system repairs will begin in FY25. In FY24, the fueling system was upgraded.

Condition. The Millbrae Yard Administrative Building is seismically deficient and requires retrofitting to meet current safety standards. Additionally, the mechanical and electrical systems throughout the yard, though still operational, are approaching the end of their useful lifespan. The capital project will rebuild the entire yard to ensure that it remains an operational, essential facility following an earthquake. This redevelopment will also consolidate staff from WSTD, WQD, and NRLMD into a single, unified location, improving efficiency.

Rollins Road

Description. Rollins Road is the administrative headquarters for the WQD. This facility is occupied by the WQD Administration, Engineering, and Field Services sections, as well a variety of NRLMD staff (planners, biologists, etc.), and WSTD surveyors. In addition to office space and cubicles, the facility serves is the operational hub of the sample monitoring group, storing cars and field monitoring equipment.

Maintenance. WSTD and various vendors performed preventive and as-needed maintenance for this facility between July 1, 2022, and June 30, 2024. In FY22, a security upgrade was started, adding fencing and access control; this upgrade was completed in late FY23. Also in FY23, renovations began to increase the number of work spaces for staff, and two HVAC units were replaced.

A separate scope of work was developed to refresh the previously tenant-occupied space on the northern end of the facility. This included minor demolition, new carpets, paint, wiring, and furniture to make usable an additional 10,000 square feet of office space for 22 staff, as well as a training room, lactation room, two kitchen areas, and three bathrooms. This work was completed in August 2024.

Additionally, in FY24, work began on designing an electric vehicle (EV) charging network for 10 vehicles. Notice to Proceed was issued in June 2024, and construction will begin in early FY25.

In FY24, due to age and the increasing occurrence of leaks, the roof was replaced. Ongoing efforts to improve employee safety included the purchase and installation of portable air cleaners for use in common areas in which social distancing cannot be maintained. Planned upgrades to the Millbrae Corporation Yard include space into which Rollins Road staff may eventually relocate. Such plans have balanced management decisions between short-term remedies and major investments in this facility.

Condition. Rollins Road building is aging but in fair condition.

4.5.2.2 <u>Capital Improvements</u>

Regional Water currently has capital projects in its buildings and grounds program, representing a total capital investment of \$437.7 million. Regional Water also has multiple R&R projects that are smaller in scope and budget, and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

Rollins Road Building Renovation (Approved Budget \$4.01 Million; Substantial Completion: 2023)

Scope. SFPUC purchased a property on Rollins Road in September 2017, securing an additional 10,000 square feet of office space for SFPUC WE. In June 2020, the project scope for 1657 Rollins Road was decreased significantly, and the scope of the Millbrae Yard Lab and Shop project was increased. The program for Rollins Road Building Renovation project will be achieved at the Millbrae Yard by adding an additional floor to the laboratory building as part of its Phase 1 project. The expanded laboratory building will accommodate the Rollins Road building staff. As a result of the scope change, personnel at 1657 Rollins Road will relocate to Millbrae Yard campus following the completion of the Millbrae Yard Lab and Shops project. The project at 1657 Rollins Road has implemented exterior security improvements, including: 1) 800 linear feet of 8-foothigh chain link fencing; 2) two pedestrian and two vehicular gates with card readers; 3) new security lighting for the parking lot west of the building; 4) electrical work to support new exterior lighting and security infrastructure; 5) eight exterior and three interior security cameras; and 6) integration of new security devices with existing Galaxy and Milestone software.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-80.

Table 4-80: Rollins Road Building Renovation Project Milestones Completed During theCurrent Reporting Cycle

Milestone	Date Complete
Construction final completion – security improvements	December 31, 2022

Millbrae Warehouse Settlement and Administration Building HVAC (Approved Budget \$7.14 Million; Substantial Completion Scope I: 2021 (done); Substantial Completion Scope II: 2024)

This project covers the cost of construction repairs for two buildings—the Millbrae Warehouse and the Administration Building—in the Millbrae Yard facility. Capital work for the Millbrae Warehouse was completed in the last reporting cycle.

Scope. For the Millbrae Administration Building HVAC upgrades, this project will provide a longterm reliable and economical solution to heating and cooling demands. The scope of work for Millbrae Administration Building HVAC upgrades includes: 1) removal of the outdated main HVAC units from the mezzanine level; 2) placement of the main components of the new HVAC system outside of the building; 3) installation of the duct work system through the existing louver openings; and 4) leasing of the mobile laboratory trailer during construction.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-81.

Table 4-81: Millbrae Administration Building HVAC Project Milestones Completed During the Current Reporting Cycle

Milestone	Date Complete		
Scope: bid advertisement	January 5, 2024		
Scope: construction notice to proceed	February 9, 2024		

Note:

HVAC = heating, ventilation, and air conditioning

Millbrae Yard Laboratory and Shop Improvements (Approved Budget \$427.74 Million; Substantial Completion: 2031)

SFPUC has determined that the existing Millbrae Administration Building must remain operational following a major earthquake, and therefore needs to be retrofitted or replaced to meet essential facility requirements. SFPUC also wants to expand the existing Millbrae Administration Building to merge and house WE staff and equipment from the Rollins Road Facility, together with some laboratory functions from the Southeast Wastewater Treatment Plant. This project is necessary to provide WE personnel with a long-term and sustainable campus, and to allow the consolidation of work groups for increased staff efficiency. This project will also alleviate the shortage of program space; increase efficiency of operations; improve employee working environment with improved HVAC; improve employee health and safety; and enhance site and building security.

A recent planning study has identified several alternatives to meet the project goals. The selected alternative for the Millbrae Yard campus improvements as part of the planning study was to be implemented in three phases. However, all three phases or "scopes" will be performed as a single construction contract.

The scope of work includes the following:

- Scope 1: A new laboratory and new south shop building will be constructed to alleviate the WE's undersized and outdated workspaces and relocate mission-critical functions to code-compliant structures. A new laboratory building is needed to meet current operational, safety, and regulatory requirements for testing and processing water samples. The new laboratory building will also provide space for all personnel currently located in the Rollins Road building. The new south shop building will provide updated workspaces for WE personnel to perform work safely and efficiently.
- Scope 2: The existing Administration Building will be demolished, and a new consolidated Administration Building will be constructed adjacent to the new laboratory building to accommodate other WE staff.
- Scope 3: A new covered storage for materials and equipment will be constructed.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-82.

Table 4-82: Millbrae Yard Campus Improvements Project Milestones Completed During the Current Reporting Cycle

Milestone	Date Complete
Project planning in progress	Pending

Sunol Long-Term Improvements (Approved Budget \$114.49 Million; Substantial Completion Scope I: 2020; Scope II: 2025)

Scope. The project includes redevelopment of the existing Sunol Yard and construction of the Alameda Creek Watershed Center near the Sunol Water Temple. The construction work was separated into two phases, with the Sunol Yard under Phase A and the Center under Phase B. The Sunol Yard construction work was completed on September 5, 2020. The Phase B construction notice to proceed was issued March 9, 2020, under WD-2794B, for a contract amount of \$27,577,000. Some owner-requested scope was identified during and after construction to improve facility operation and functionality. The deferred and owner-requested scope for the Sunol Yard included backup generator improvements, constriction of a shade structure, replacement of the watershed cottage, truck wash improvements, temple road and entry gate improvements, and construction of covered storage facilities. The deferred and owner-requested scope for the Watershed Center included installation of a backup generator, construction of a 100-space parking lot, installation of an outdoor Muwekma exhibit, picnic area restoration and fixtures, installation of composting toilets, and conversion of temporary construction areas to permanent areas for WSTD and NRLMD use. Because the ownerrequested scope resulted in higher anticipated costs, the scope is being deferred to new projects: Sunol Yard Phase 2 and Alameda Creek Watershed Center Phase 2. Some additional work and scope changes under the Watershed Center contract increased the contract cost and duration, including berm settlement, exhibit redesign and associated delays, sinkhole repair, and bluestone stencils and etching. Some of the budget planned for the deferred and ownerrequested scope will be used for the additional work and scope changes identified under the Watershed Center contract and soft costs. Some budget is being used to cover priority scope, including yard entry gate improvements, sinkhole investigation and repair, and initial planning for select owner-requested scope.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-83.

Table 4-83: Sunol Long-Term Improvements Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete		
Construction	Ongoing		

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-84.

		Level of Service						
Project	Drinking Water Quality	Seismic	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
Rollins Road Building Renovation			~					
Millbrae Administration Bldg. HVAC			~					
Millbrae Yard Campus Improvements			~					
Sunol Long-Term Improvements			~				~	~

 Table 4-84: RWS Buildings and Grounds Projects – Levels of Service Project Drivers

Notes:

HVAC = heating, ventilation, and air conditioning RWS = Regional Water System

4.6 **Power Generation Assets**

SFPUC owns and operates multiple power generation assets, including high-head and low-head hydropower houses. These assets are all operated and maintained within the Hetch Hetchy Water system.

4.6.1 Hetch Hetchy Water

HHWP is responsible for the maintenance and operation of multiple power generation assets, most of which are integral to its water delivery system. These assets include:

Holm Powerhouse	Moccasin Powerhouse
Kirkwood Powerhouse	Moccasin Low Head Powerhouse

4.6.1.1 Asset Descriptions, Maintenance, and Condition

Asset descriptions, maintenance, and condition for the HHWP power generation assets are provided in the following sections, organized from upstream to downstream. A summary of the assets organized by classification is included in Table A-12 of Appendix A.

Holm Powerhouse

Description. Holm Powerhouse has two generating units, with a combined maximum output of 171 MW at a maximum flow of 1,010 cfs. The distributor floor, turbine floor, and generator floor are inside the powerhouse. The turbines are vertical, impulse type, with six jets and deflectors directing water to the exposed, non-submerged runner. The turbine discharges into an open waterway that daylights into the tailrace area and into Cherry Creek.

Each generating unit has three single-phase, 230:13.8-kilovolt (kV) step-up transformers installed outdoors on the transformer deck adjacent to the generator floor. The transformers are connected

to the indoor 13.8 kV switchgear and the Early Intake Switchyard. Holm Powerhouse is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-85 summarizes maintenance work.

Name of PM	Completion Date(s)	Description		
Inspection	Completed weekly	Operator walkthroughs		
	Completed monthly	Security inspections		
	Completed annually Annual vegetation inspection			
Maintenance	Completed annually	Annual maintenance shutdown for generating units 1 and 2		

Table 4-85: Holm Powerhouse Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. Holm Powerhouse and its systems are in good condition. Many of the plant's auxiliary systems and controls were recently replaced and/or updated during the HH-989 Contract. The generators each have had a rewind project to refurbish and extend their useful life. The generator step-up transformers are in good condition and should be monitored for condition and performance. The turbine shut-off valve (TSOV) for each unit is in only fair condition due to its age; this has required HHWP to increase its nonroutine maintenance activities.

Kirkwood Powerhouse

Description. Kirkwood Powerhouse has three generating units, with a combined maximum output of 123 MW at a maximum flow of 1,350 cfs. The distributor floor, turbine floor, generator floor, and control room are inside the powerhouse. The turbines are vertical, impulse-type, with six jets and deflectors directing water to the exposed, non-submerged runner. The turbine discharges into an enclosed waterway connecting to Early Intake Bypass Tunnel.

Each generating unit has three single-phase, 230:13.8 kV step-up transformers installed outdoors on the transformer deck adjacent to the generator floor. The transformers are connected to the indoor 13.8 kV switchgear and Early Intake Switchyard.

Kirkwood Powerhouse has a water bypass and energy dissipation system used to convey water supply from the penstock to the bypass chamber and onto Mountain Tunnel if the powerhouse/ transmission system is de-energized. Kirkwood Powerhouse is in a Tier 2 High Fire Threat District

Maintenance. Table 4-86 summarizes maintenance work.

Name of PM	Completion Date(s)	Description		
Inspection	Completed weekly	Operator walkthroughs		
	Completed monthly	Security inspections		
	Completed annually	Annual vegetation inspection		
Maintenance	Completed annually	Annual maintenance shutdown for generating units 1, 2, and 3		

Table 4-86: Kirkwood Powerhouse Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive

Condition. Kirkwood Powerhouse, and its associated systems, are in fair condition due to the overall age of the powerhouse and because some of the systems have reached the end of their useful life. In 2009-2010, a generator rewind performed on units 1 and 2, which are still within their expected useful life. Capital investment will be required to update and overhaul unit 3 and the plant auxiliaries. Additionally, the water bypass and energy dissipation system is in poor condition and has required extensive repairs over the past 10 years, even with limited use. Capital investment will be required to upgrade or replace the system for long-term, reliable service. There is a capital project to address the water bypass and energy dissipation system.

Moccasin Powerhouse

Description. Moccasin Powerhouse has two generating units, with a combined maximum output of 110 MW at a maximum flow of 1,340 cfs. The distributor floor, turbine floor, and control room are inside the powerhouse, with the generator housing exposed to the outdoors. The turbines are impulse-type, with six jets and deflectors directing the water to the exposed, non-submerged runner. The turbine discharges into an open waterway, which daylights into the tailrace area.

The 115/230:13.8 kV step-up transformers are just outside the powerhouse. The transformers are connected to the indoor switchgear and the Moccasin Switchyard adjacent to the powerhouse.

Moccasin Powerhouse has two water bypass and energy dissipation systems used to convey water supply from the penstocks to the tailrace when the generation units or the transmission system are de-energized. Moccasin Powerhouse is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-87 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed weekly	Operator walkthroughs
	Completed monthly	Security inspections
	Completed annually	Annual vegetation inspection
Maintenance	Completed annually	Annual maintenance shutdown for generating units 1 and 2

Table 4-87: Moccasin Powerhouse Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. Multiple capital projects have improved the condition of Moccasin Powerhouse, including replacement of both generator step-up transformers and upgrade and refurbishment of Unit 2. Upgrade and refurbishment of Unit 1 will be completed in the spring of 2025. However, further upgrades are needed to improve reliability, including refurbishing plant auxiliary systems, TSOVs, and the water bypass and energy dissipation system. There are ongoing capital projects to update and replace these systems.

Moccasin Low Head Powerhouse

Description. Moccasin Low Head Powerhouse has one horizontal unit with a generator rated at 3,750 kilovolt-amperes. The turbine is a Francis type that discharges into a draft tube connected to the tailrace. The powerhouse has three levels: the mezzanine, turbine floor, and generator pit.

The generator has a three-phase 13.8:4.16 kV step-up transformer outside near the powerhouse. The transformer is connected to the indoor 4.16 kV breaker and the Moccasin Switchyard. Moccasin Low Head Powerhouse is in a Tier 2 High Fire Threat District.

Maintenance. No PM was required or completed during this period.

Condition. Moccasin Low Head Powerhouse has not been operational since the March 2018 flood. A project is underway to remediate the damage and have the powerhouse operational by March 2025. Additional capital investment may be required at a later date to modernize the powerhouse systems for reliable operations.

4.6.1.2 <u>Capital Improvements</u>

HHWP currently has capital projects in its power generation program, representing a total capital investment of \$158.4 million. HHWP also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

Kirkwood Powerhouse Bypass Upgrades (Approved Budget \$16.8 Million; Substantial Completion: 2035)

Scope. This project will provide a reliable hydraulic bypass and energy dissipation system, conveying water around the turbines to the Kirkwood Powerhouse Bypass Chamber and Mountain Tunnel. The scope includes upgrading/replacing the high-pressure energy dissipating valves, control systems, and associated structures to absorb 1,245 feet of pressure head and a flow of 430 cfs without damage.

Milestones Completed During the Reporting Cycle. The project is scheduled and budgeted to begin in 2027; therefore, no milestones were achieved during this reporting cycle.

Moccasin Powerhouse Bypass Upgrade (Approved Budget \$41.1 Million; Substantial Completion 2027)

Scope. This project will provide a reliable hydraulic bypass and energy dissipation system, conveying water around the turbines to the Moccasin Powerhouse Tailrace. The scope includes upgrading/replacing the high-pressure energy dissipating valves, control systems, and associated structures to absorb 1,147 feet of pressure head and a flow of 430 cfs without damage.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-88.

Table 4-88: Moccasin Powerhouse Bypass Upgrade Project Milestones Completed During theCurrent Reporting Cycle

Milestones	Completion Date
CER (draft)	December 2022
CER (final)	March 2023
35% design	March 2024

Note:

CER = Conceptual Engineering Report

Moccasin Powerhouse and Generator Step-Up Rehabilitation (Approved Budget \$100.6 Million; Substantial Completion: 2028)

Scope. The project is broken down into three components: 1) Generator Rehabilitation – replace the entire generator and associated equipment, including new stator cores and coils, rotor poles, relays, and rotor rim; 2) Generator Step-Up (GSU) Replacement – replace two of the three existing GSU transformers, new foundations and oil containment, and relay upgrades; and 3) Power Plant Systems Upgrades – replace the 480 volt (V) switchgear, 13.8 kV switchgear, MCCs, main control boards, protective relays, and cooling water piping, and improve oil containment systems.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-89.

Phase	Milestones	Completion Date
Phase 1	DB-121R2 – Postponement of Outage #1 (1 year)	November 2022
	DB-121R2 – Mobilization for Construction	July 2023
	DB-121R2 – Start of Outage #1 (MPH Unit #2, MS2)	December 2023
	DB-121R2 – MPH Unit #2 Partial Utilization (MS3)	April 2024
Phase 2	HH-1003 – GSU2 Partial Utilization	March 2023
	HH-1003 – Contract Closeout	March 2024
Phase 3	System Upgrades – Alternative Analysis and Conceptual Engineering Report (Combined) Signed (10% Design)	February 2023
	System Upgrades – 35% Design	June 2023
	System Upgrades – 65% Design	June 2024

Table 4-89: Moccasin Powerhouse and GSU Rehabilitation Project Milestones CompletedDuring the Current Reporting Cycle

Notes:

GSU = generator step-up (transformer)

MPH = Moccasin Powerhouse

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-90.

		Level of Service						
Project	Drinking Water Quality	Seismic	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
Kirkwood Powerhouse Bypass Upgrades			\checkmark			~		~
Moccasin Powerhouse Bypass Upgrade			√			~		~
Moccasin Powerhouse and GSU Rehabilitation			\checkmark			~		\checkmark

Table 4-90: HHWP Power Generation Projects - Levels of Service Project Drivers

Notes:

GSU = generator step-up (transformer) HHWP = Hetch Hetchy Water and Power

4.7 **Power Transmission Assets**

SFPUC owns and operates multiple power transmission assets, including high-voltage transmission lines, towers, substations, and switchyards. These assets are all operated and maintained within the Hetch Hetchy Water system.

4.7.1 Hetch Hetchy Water

HHWP is responsible for the maintenance and operation of multiple power transmission assets, most of which are integral to its water delivery system. HHWP performs 5-year inspection on all transmission towers (climbing each tower) and prepares maintenance as needed. These inspections are not included in the maintenance tables. Transmission assets include:

Power Transmission Lines 1 and 2 Power Transmission Lines 3 and 4 Power Transmission Lines 5 and 6 Power Transmission Lines 7 and 8 Power Transmission Lines 9, 10, and 11 Intake Switchyard Moccasin Switchyard Warnerville Substation Calaveras Substation

4.7.1.1 Asset Descriptions, Maintenance, and Condition

Asset descriptions, maintenance, and condition for the HHWP power transmission assets are provided in the following sections.

Power Transmission Lines 1 and 2

Description. Power Transmission Lines 1 and 2 are used to transmit power from Holm Powerhouse to the Intake Switchyard. This asset consists of 1.55 miles of two three-phase conductors that transmit power at a voltage of 230 kV, with 1.5 miles traversing a Tier 2 High Fire Threat District. Supporting the towers is a series of seven lattice steel towers.

Maintenance. Table 4-91 summarizes maintenance work.

Table 4-91: Transmission Lines 1 and 2 Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
Vegetation Inspection and Removal	Completed annually	Vegetation treatment in accordance with the Transmission Vegetation Management Plan
Maintenance	Completed annually	Completed as needed

Note:

PM = preventive maintenance

Condition. Transmission Lines 1 and 2 are in good condition and fit for service; however, given the asset's age, an updated condition assessment is planned to be completed by late 2025. Additionally, there is one site that requires remediation for a "hard clearance" detection.²

Power Transmission Lines 3 and 4

T 11 4 01 T

Description. Power Transmission Lines 3 and 4 are used to transmit power from Moccasin Powerhouse to Calaveras Substation, as well as TID's Oakdale Substation and PG&E's Newark Substation. This asset consists of 98.6 miles of two three-phase conductors that transmit power at a voltage of 115 kV; with 0.5 mile traversing a Tier 1 High Fire Threat District and 17.4 miles traversing a Tier 2 High Fire Threat District. Supporting the towers is a series of 515 lattice steel towers and two steel monopoles.

Maintenance. Table 4-92 summarizes maintenance work.

Table 4-92: Power Transmission Lines 3 and 4 Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	5-year inspection	Completed 287 tower inspections
Vegetation Inspection and Removal	Completed annually	Vegetation treatment in accordance with the Transmission Vegetation Management Plan
Maintenance	Completed annually	Completed as needed

Note:

PM = preventive maintenance

Condition. Power Transmission Lines 3 and 4 are in only fair condition, and it is anticipated that the lines will need capital investment soon. An updated condition assessment is planned to be completed by late 2025. Originally, HHWP identified 90 hard clearance detections on Lines 3 and 4. Work continues to remediate these detections. The remaining 56 detections will be remediated by the end of 2029.

² "Hard clearance" detection is defined as insufficient safety clearance for roads, buildings, other wires, etc.

Power Transmission Lines 5 and 6

Description. Power Transmission Lines 5 and 6 are used to transmit power from the Intake Switchyard to Warnerville Substation. This asset consists of 48.4 miles of two three-phase conductors that transmit power at a voltage of 230 kV; with 22.2 miles traversing a Tier 2 High Fire Threat District and 3.3 miles traversing a Tier 3 High Fire Threat District. Supporting the towers is a series of 513 lattice steel towers and two steel monopoles.

Maintenance. Table 4-93 summarizes maintenance work.

Table 4-93: Power Transmission Lines 5 and 6 Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	5-year inspection	Completed 48 tower inspections
Vegetation Inspection and Removal	Completed annually	Vegetation treatment in accordance with the Transmission Vegetation Management Plan
Maintenance	Completed annually	Completed as needed

Note:

PM = preventive maintenance

Condition. Power Transmission Lines 5 and 6 are in good condition and fit for service; however, given the asset's age, an updated condition assessment is planned to be completed by late 2025. Additionally, Originally, HHWP identified 82 hard clearance detections on Lines 5 and 6. Work continues to remediate these detections. The remaining 70 detections will be remediated by the end of 2029.

Power Transmission Lines 7 and 8

Description. Power Transmission Lines 7 and 8 are used to transmit power from Warnerville Substation to MID's Standiford Substation. This asset consists of 12.5 miles of two three-phase conductors that transmit power at a voltage of 115 kV. Supporting the towers is a series of 78 lattice steel towers. This asset is not in a High Fire Threat District.

Maintenance. Table 4-94 summarizes maintenance work.

Table 4-94: Transmission Lines 7 and 8 Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	5-year inspection	Completed 48 tower inspections
Vegetation Inspection and Removal	Completed annually	Vegetation treatment in accordance with the Transmission Vegetation Management Plan
Maintenance	Completed annually	Completed as needed

Note:

PM = preventive maintenance

Condition. Lines 7 and 8 were upgraded in 2023/24, increasing line ampacity to mitigate the impacts of new generation being added to the electrical grid that had an adverse impact on reliability. In addition, 18 sites were rehabilitated to address hard clearance issues. Originally, HHWP identified 34 hard clearance detections on Lines 7 and 8. Work continues to remediate these detections. The remaining two detections will be remediated by the end of 2025.

Power Transmission Lines 9, 10, and 11

Description. Power Transmission Lines 9, 10, and 11 are used to transmit power from Kirkwood Powerhouse to the Intake Switchyard. This asset consists of 1.46 miles of three three-phase conductors that transmit power at a voltage of 230 kV; with 1.4 miles traversing a Tier 2 High Fire Threat District. Supporting the towers are series of four (Lines 9 and 10) and four (Line 11) lattice steel towers.

Maintenance. Table 4-95 summarizes maintenance work.

Table 4-95: Transmission Lines 9, 10, and 11 Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	5-year inspection	Completed six tower inspections
Vegetation Inspection and Removal	Completed annually	Vegetation treatment in accordance with the Transmission Vegetation Management Plan
Maintenance	Completed annually	Completed as needed

Note:

PM = preventive maintenance

Condition. Power Transmission Lines 9, 10, and 11 are in good condition; however, given its age, an updated condition assessment is recommended during the next reporting cycle. Originally, HHWP identified two hard clearance detections on these lines. The detections will be remediated by the end of 2029.

Intake Switchyard

Description. Intake Switchyard aggregates power generated from both Holm and Kirkwood powerhouses for transmission to Lines 5 and 6. During outages of both Kirkwood Powerhouse and/or Holm Powerhouse, power can be back-fed from Power Transmission Lines 5 and 6 to either powerhouse. Integral to the switchyard is a series of eight sulfur hexafluoride (SF6) breakers, switches, and a control room, all serving operating and protection functions. The Intake Switchyard is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-96 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed weekly	Operator walkthroughs
	Completed monthly	Operator site security inspection
Vegetation Control	Completed annually	Vegetation removal
Maintenance	Completed annually	Annual maintenance

Table 4-96: Intake Switchyard Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. Intake Switchyard is in good condition and is fit for service. Two of the eight circuit breakers were replaced in 2007 (CBs 310 and 330); the remaining circuit breakers (CBs 300, 320, 340, 350, 360, and 370) were replaced in 2013. All breakers are well within their expected useful life. A condition assessment for the control room equipment (installed circa 1960s) is recommended.

Moccasin Switchyard

Description. Moccasin Switchyard is used to provide protection to Power Transmission Lines 5 and 6 and is also a termination point for Power Transmission Lines 3 and 4. Moccasin Switchyard is adjacent to Moccasin Powerhouse and includes two 115 kV oil circuit breakers (OCBs); two 230 kV OCBs; and ancillary equipment such as two 2.4 kV distribution transformers, one 480 V distribution transformer, two 13.8 kV isolation transformers, bus work, switches, and grounding. Moccasin Switchyard is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-97 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed weekly	Operator walkthroughs
	Completed monthly	Operator site security inspection
Vegetation Control	Completed annually	Vegetation removal
Maintenance	Completed annually	Annual maintenance

Table 4-97: Moccasin Switchyard Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. Moccasin Switchyard is in fair condition and fit for service. The equipment in the switchyard is approaching or has exceeded its expected useful life and requires capital investment. There is a project to address these deficiencies in our capital plan.

Warnerville Substation

Description. Warnerville Substation serves as a termination point for Power Transmission Lines 5 and 6 and Power Transmission Lines 7 and 8. It is also a critical connection point to the bulk electric system, where HHWP is typically connected to PG&E's power transmission system. Warnerville Substation includes seven SF6 breakers, four OCBs, two auto transformers, multiple switches, and two control rooms. Warnerville Substation is in a non-High Fire Threat District.

Maintenance. Table 4-98 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	Completed weekly	Operator walkthroughs
	Completed monthly	Operator site security inspection
Vegetation Control	Completed annually	Vegetation removal
Maintenance	Completed annually	Annual maintenance

Table 4-98: Warnerville Substation Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. Warnerville Substation is in fair condition and is fit for service. The autotransformers and the 230 kV OCBs were replaced in 2020; however, the original 115 kV OCBs remain in service and have exceeded their expected useful life. The remaining OCBs are scheduled for replacement and included in the Warnerville Rehabilitation capital project.

Calaveras Substation

Description. The Calaveras Substation is a small substation that serves as a termination point for Power Transmission Lines 3 and 4. The primary function of Calaveras Substation is to serve the power that is required to operate multiple Regional Water facilities, including the SAPS, Chlorination Plant, and Sunol Filter Plant. Calaveras Substation includes a single transformer, as well as other electrical equipment such as breakers and switches. Calaveras Substation is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-99 summarizes maintenance work.

Table 4-99: Calaveras Substation Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed monthly	Operator site security inspection
Vegetation Control	Completed annually	Vegetation control
Maintenance	Completed annually	Annual maintenance

Note:

PM = preventive maintenance

Condition. Calaveras Substation is in good condition; however, due to growing power demands from Regional Water, along with redundancy concerns, capital investment is recommended.

4.7.1.2 <u>Capital Improvements</u>

HHWP currently has capital projects in its power transmission program, representing a total capital investment of \$178.1 million. HHWP also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

Transmission Lines 7 and 8 Upgrades (Approved Budget \$37.3 Million; Substantial Completion 2024)

Scope. The Transmission Lines 7 and 8 Upgrades project includes replacing the conductors to mitigate the impacts of new power flows across the HHWP power transmission system due to power generators that are approved to connect to the grid by the California Independent System Operator. The project's scope also includes multiple tower raises to remediate hard clearance detections. This project is complete.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-100.

Table 4-100: Transmission Lines 7 and 8 Upgrades Project Milestones Completed During theCurrent Reporting Cycle

Milestones	Completion Date
Construction contract HH-1007 NTP	September 28, 2022
HH-1007 substantial completion	March 7, 2024
HH-1007 final completion	June 5, 2024

Note:

NTP = Notice to Proceed

Transmission Lines Clearance Mitigation (Approved Budget \$83.7 Million; Substantial Completion 2029)

Scope. The Transmission Lines Clearance Mitigation project will provide funding to implement remediate clearance detections. Remediation options include but are not limited to new towers/ tubular poles, new intervening poles, tower raises, ground lowering, and other structural improvements to the lattice towers.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-101.

Table 4-101: Transmission Lines Clearance Mitigation Project Milestones Completed Duringthe Current Reporting Cycle

Milestones	Completion Date
TLCM – Moderate/Low-Risk Project – Planning Task Order NTP	June 2024
TLCM - Moderate/Low-Risk Project - Environmental Task Order NTP	April 2024

Notes:

NTP = Notice to Proceed

TLCM = transmission lines clearance mitigation

Warnerville Substation Rehabilitation (Approved Budget \$37.4 Million; Substantial Completion: 2025)

Scope. Phase 1 construction was completed under DB-127R. Remaining work includes the replacement of four oil circuit breakers, bushings, surge arrestors, disconnect switches, current voltage transformer, insulators, relay protection, and other ancillary equipment.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-102.

Table 4-102: Warnerville Substation Rehabilitation Project Milestones Completed During theCurrent Reporting Cycle

Milestones	Completion Date
Phase 2 AAR/CER final	February 6, 2023
Phase 2 65% design	June 30, 2023
Phase 2 95% design	March 30, 2024

Notes:

AAR = Alternatives Analysis Report CER = Conceptual Engineering Report

Moccasin Switchyard Rehabilitation (Approved Budget \$19.7 Million; Substantial Completion: 2029)

Scope. The project will entail rehabilitating Moccasin Switchyard by replacing the 115 kV disconnect switches, 115 kV bus configuration, 230 kV disconnect switches, 230 kV bus configuration, and 115 kV circuit breakers; adding surge arresters; performing a fault and grounding study; improving switchyard grading; and replacing fencing.

Milestones Completed During the Reporting Cycle. The project just kicked off and has one milestone during this reporting period, as summarized in Table 4-103.

Table 4-103: Moccasin Switchyard Rehabilitation Project Milestones Completed During theCurrent Reporting Cycle

Milestones	Completion Date
NTP for planning phase professional service task order	May 2024

Note: NTP = Notice to Proceed

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-104.

Level of Service								
Project	Drinking Water Quality	Seismic	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
Transmission Lines 7 and 8 Upgrades			~			✓		~
Transmission Lines Clearance Mitigation			~			~		~
Warnerville Substation Rehabilitation			\checkmark			~		✓
Moccasin Switchyard Rehabilitation			~			~		~

Table 4-104: Power Transmission Projects – Levels of Service Project Drivers

4.8 **Power Distribution Assets**

SFPUC owns and operates multiple power distribution assets, including pole-mounted transformers, switches, reclosures, and conductors in the HHWP project that are in Tier 2 and 3 High Fire Threat Districts.

4.8.1 Hetch Hetchy Water

HHWP is responsible for the maintenance and operation of multiple power distribution assets. These assets include:

Holm Powerhouse to Cherry (HP-CH) Cherry Dam to Cherry Valve House (CD-CV) Kirkwood Powerhouse to O'Shaughnessy (KP-OS) Mather to Cafeteria (MA-CA) Mather to Evergreen (MA-EV) Moccasin Powerhouse to Low Head (MP-LH) Moccasin Powerhouse to Sewer Treatment Plant (MP-ST) O'Shaughnessy to O'Shaughnessy Compound (OS-OC)

4.8.1.1 Asset Descriptions, Maintenance, and Condition

Asset descriptions, maintenance, and conditions for HHWP power distribution assets are provided in the following sections. In addition to annual equipment inspections, HHWP also performs 1) detailed inspections on all distribution poles every 5 years; and 2) distribution pole intrusive/integrity testing on all poles every 10 years. Five- and 10-year inspections are only reported in the preventive maintenance summaries when they are performed within the reporting cycle.

Holm Powerhouse to Cherry (HP-CH)

Description. The HP-CH line distributes power from Holm Powerhouse to the Cherry Lake Compound and consists of 9.5 miles of 22.9 kV overhead conductors in the Stanislaus National Forest. The line also includes one 13.8 kV to 22.9 kV transformer at Holm Powerhouse. The HP-CH lines are in a Tier 2 High Fire Threat District (HFTD).

Maintenance. Table 4-105 summarizes maintenance work.

Table 4-105: Holm Powerhouse to Cherry Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspections (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and May 2024	Pole 4292 vegetation clearance
	March 2023 and February 2024	Herbicide application on ROW

Notes:

PM = preventive maintenance ROW = right-of-way

Condition. The HP-CH distribution line is in good condition. Most of this distribution line was replaced in 2013 following the Rim Fire. The line is fit for service; however, other improvements are required.

Cherry Dam to Cherry Valve House (CD-CV)

Description. The CD-CV line is a 1.3-mile branch off the HP-CH line and comprises overhead and underground conductors, both operating at 22.9 kV. The overhead segment is approximately 0.6 mile, distributing power to the Cherry Valve House at the base of Cherry Lake Dam. The remaining 0.76 mile is underground and supplies 22.9 kV power to the Cherry-Eleanor Pumps and Cherry-Eleanor Pump Station, all in the Stanislaus National Forest. The CD-CV line is in a Tier 2 HFTD.

Maintenance. Table 4-106 summarizes maintenance work.

Table 4-106: Cherry Dam to Cherry Valve House Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and May 2024	Pole 4292 vegetation clearance
	March 2023 and May 2024	Herbicide application on ROW

Notes:

PM = preventive maintenance ROW = right-of-way

Condition. The CD-CV distribution line is in good condition. The line is fit for service; however, other improvements are required.

Kirkwood Powerhouse to O'Shaughnessy (KP-OS)

Description. The KP-OS line is a 22.9 kV overhead distribution line that begins at Kirkwood Powerhouse, in the Stanislaus National Forest. It provides power to HHWP facilities at Hetch Hetchy Reservoir in Yosemite National Park. The KP-OS line spans approximately 17.4 overhead conductor miles through a Tier 2 High Fire Threat District.

Maintenance. Table 4-107 summarizes maintenance work.

Table 4-107: Kirkwood Powerhouse to O'Shaughnessy Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and February 2024	Pole 4292 vegetation clearance
	March 2023 and May 2024	Herbicide application on ROW

Notes:

KP-OS = Kirkwood Powerhouse to O'Shaughnessy PM = preventive maintenance ROW = right-of-way

Condition. The KP-OS distribution line is in good condition, having been mostly replaced in 2013 after the Rim Fire. The line is fit for service; however, other improvements are required.

Mather to Cafeteria (MA-CA)

Description. The MA-CA line is a 2.4 kV overhead line that branches off the 22.9 kV KP-OS line. The MA-CA line is in the Stanislaus National Forest and feeds the Camp Mather Cafeteria building. The MA-CA line consists of approximately 0.6 mile of overhead conductor and is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-108 summarizes maintenance work.

Table 4-108: Mather to Cafeteria Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and February 2024	Pole 4292 vegetation clearance
	July 2022, March 2023, and February 2024	Herbicide application on ROW

Notes:

PM = preventive maintenance ROW = right-of-way

Condition. Upgrades and repairs were made to this line in 2023. The MA-CA distribution line is fit for service.

Mather to Evergreen (MA-EV)

Description. The MA-EV line is a 2.4 kV overhead line that branches off the 22.9 kV KP-OS line. The MA-EV line is in the Stanislaus National Forest. It feeds power to the Evergreen Lodge, a privately owned facility adjacent to Camp Mather. The MA-EV line consists of approximately 0.9 mile of overhead conductor and is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-109 summarizes maintenance work.

Condition. The MA-EV distribution line is in good condition. The line is fit for service; however, other improvements are required.

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and May 2024	Pole 4292 vegetation clearance
	July 2022 and February 2024	Herbicide application on ROW

Table 4-109: Mather to Evergreen Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Notes:

PM = preventive maintenance ROW = right-of-way

Moccasin Powerhouse to Low Head (MP-LH)

Description. The MP-LH overhead line distributes power from Moccasin Powerhouse to Moccasin Low Head Powerhouse via the Moccasin Switchyard 13.8 kV cabinet. It provides 2.4 kV power distribution to the upper cottages in Moccasin camp, Moccasin UV building, Moccasin maintenance shops, the Moccasin peak radio tower, Moccasin spray fields, Priest Reservoir gate house, Priest butterfly valves, West Portal cottage, Priest cottage, and the California Department of Fish and Wildlife Fish Hatchery and residences. The MP-LH line consists of approximately 7.4 miles of overhead conductor and is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-110 summarizes maintenance work.

Table 4-110: Moccasin Powerhouse to Low Head Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and May 2024	Pole 4292 vegetation clearance
	December 2022 and February 2024	Herbicide application on ROW

Notes:

PM = preventive maintenance ROW = right-of-way

Condition. The MP-LH distribution line is in good condition. The line is fit for service; however, other improvements are required.

Moccasin Powerhouse to Sewer Treatment Plant (MP-ST)

Description. The MP-ST line is a 2.4 kV overhead line in the town of Moccasin. It provides 120/240 V power to Moccasin cottages 1-18, Engineering, Records, Energy Services, and the Moccasin Administration Building. Underground segments provide the power to light poles around the Moccasin Reservoir and Administration. The MP-ST line consists of approximately 1.5 miles of overhead conductor, and the underground portion length is unknown. The MP-ST line is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-111 summarizes maintenance work.

Condition. The MP-ST distribution line is in good condition. The line is fit for service; however, other improvements are required.

Table 4-111: Moccasin Powerhouse to Sewer Treatment Plant Preventive MaintenanceSummary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and May 2024	Pole 4292 vegetation clearance
	December 2022 and February 2024	Herbicide application on ROW

Notes:

PM = preventive maintenance ROW = right-of-way

O'Shaughnessy to O'Shaughnessy Compound (OS-OC)

Description. The OS-OC line is a 2.4 kV line off the 22.9 kV KP-OS line in Yosemite National Park. It provides overhead power to the O'Shaughnessy Cottages 1, 2, 3, and 4, NPS buildings, chlorination building, UV building, and water tanks. The underground portion provides power to O'Shaughnessy Chalet, the sewer pump station, emergency generators, lift station pumps, and O'Shaughnessy Dam Gallery 1. The OS-OC line consists of approximately 0.5 mile of overhead conductor, with 0.1 mile underground, and is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-112 summarizes maintenance work.

Condition. The OS-OC line is in good condition. The line is fit for service; however, other improvements are required.

Table 4-112: O'Shaughnessy to O'Shaughnessy Compound Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Aerial inspection (vegetation and equipment)
	Completed annually	Visual ground inspection of equipment
Maintenance	March 2023 and February 2024	Pole 4292 vegetation clearance
	March 2023 and February 2024	Herbicide application on ROW

Notes:

PM = preventive maintenance ROW = right-of-way

4.8.1.2 Capital Improvements

Capital improvements to the Power Distribution system are defined in the HHWP's R&R Program.

4.8.2 Regional Water

NRLMD and WSTD own multiple power distribution assets and maintain them in part through HHWP staff. Delineation of power distribution assets between NRLMD and WSTD will occur in the next reporting cycle. These assets include:

Calaveras Dam Power Pole Line (CDL)	Pulgas Power Pole Line (PUL)
Calaveras Substation Power Pole Line (CSL)	San Andreas Lake Power Pole Line (SAL)
Crystal Springs Power Pole Line (CYL)	Sawyer Camp Power Pole Line (SCL)
Pilarcitos Power Pole Line (PPL)	Sunol Water Temple Power Pole Line (STL)

4.8.2.1 Asset Descriptions, Maintenance, and Condition

Asset descriptions, maintenance, and condition for Regional Water power distribution assets are provided in the following sections. In addition to annual equipment inspections, detailed inspections on all distribution poles are performed every 5 years, and distribution pole intrusive/ integrity testing on all poles are performed every 10 years. Five- and 10-year inspections are only reported in the preventive maintenance summaries when they are performed within the reporting cycle.

Calaveras Dam Power Pole Line (CDL)

Description. CDL is a 120/240 V overhead distribution line in Alameda County that provides power to the Calaveras Reservoir watershed keepers cottage. CDL is approximately 0.1 overhead mile long and is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-113 summarizes maintenance work.

Table 4-113: Calaveras Dam Power Pole Line Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	January 2023	Visual ground inspection
Maintenance	December 2022	Replace rotten pole, POLCDL-05

Note:

PM = preventive maintenance

Condition. As of the last reporting cycle, CDL was in fair condition. The line is fit for service; however, other improvements are being evaluated.

Calaveras Substation Power Pole Line (CSL)

Description. CSL is a 21.6 kV overhead distribution line in Alameda County that provides power to SVWTP, SAPS, Sunol Valley Chloramines facility, the AEP Station, the AWP Station, and the San Antonio Backup Pipeline Discharge Facility. CSL is approximately 3.8 overhead miles in length and is in a Tier 2 High Fire Threat District.

Maintenance. Table 4-114 summarizes maintenance work.

Table 4-114: Calaveras Substation Power Pole Line Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	December 2023	Visual ground inspection
Maintenance	December 2022	Replace fuses, POLCSL-02
	December 2023	Annual hot wash maintenance of Calaveras Substation

Note:

PM = preventive maintenance

Condition. As of the last reporting cycle, CSL was in good condition. The line was fit for service; however, other improvements are being evaluated.

Crystal Springs Power Pole Line (CYL)

Description. CYL is a 7.2 kV overhead distribution line in San Mateo County. CYL provides power to the Crystal Springs watershed keeper's cottage and the reservoir entrance gates. CYL is 0.7 overhead mile in length and is within a Tier 2 High Fire Threat District.

Maintenance. Table 4-115 summarizes maintenance work.

Table 4-115: Crystal Springs Power Pole Line Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	December 2022	Visual ground inspection
	March 2023	Visual ground inspection
	July 2022	10-year intrusive testing on all distribution poles
Maintenance	March 2023	Tighten guy wire, POLCYL-01

Note:

PM = preventive maintenance

Condition. As of the last reporting cycle, CYL was in good condition. The line was fit for service; however, other improvements are being evaluated.

Pilarcitos Power Pole Line (PPL)

Description. PPL is a 4.16 kV overhead distribution line in San Mateo County. PPL provides power to the Davis Tunnel watershed keeper's cottage, the Pilarcitos watershed keeper's cottage, the Pilarcitos Adit, and the forebay metering and gate valves on the Pilarcitos Dam. PPL is 9.5 overhead miles in length and is in a Tier 3 High Fire Threat District.

Maintenance. Table **4-116** summarizes maintenance work.

Table 4-116: Pilarcitos Power Pole Line Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	December 2023	Visual ground inspection
Maintenance	July 2022	Tighten loose guy wires, POLPPL-03-1 and POLPPL-03-3
	December 2023	Replace corroded jumper connectors POLPPL-12
	December 2023	Replace pole with woodpecker hole 6 feet off the ground, POLPPL-24
	December 2023	Re-sag conductor, center phase is low, POLPPL-31
	December 2023	Install vibration dampers on pole, POLPPL-23

Note:

PM = preventive maintenance

Condition. As of the last reporting cycle, PPL was in fair condition. The line was fit for service; however, other improvements are being evaluated.

Pulgas Power Pole Line (PUL)

Description. The PUL is a 4.16 kV overhead distribution line in San Mateo County. PUL provides power to the Pulgas Valve Lot, the control building, and small water quality sampling stations in the valve lot. PUL is approximately 0.6 overhead line mile long and in a Tier 2 High Fire Threat District.

Maintenance. Table 4-117 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Inspection	December 2022	Visual ground inspection
	March 2023	Visual ground inspection
	December 2023	Visual ground inspection
Maintenance	December 2022	Straighten and key pole, POLPUL-01
	December 2023	Troubleshoot and repair power issues
	January 2024	Pole 4292 vegetation clearance, POLPUL-04 and POLPUL-05

Table 4-117: Pulgas Power Pole Line Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Note:

PM = preventive maintenance

Condition. As of the last reporting cycle, PUL was in fair condition. The line was fit for service; however, other improvements are being evaluated.

San Andreas Lake Power Pole Line (SAL)

Description. SAL is a 4.16 kV overhead distribution line in San Mateo County. SAL provides power to the North San Andreas watershed keeper's cottage and is approximately 0.6 overhead mile long. This line is in a Tier 3 High Fire Threat District.

Maintenance. Table 4-118 summarizes maintenance work.

Table 4-118: San Andreas Lake Power Pole Line Preventive Maintenance Summary
(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	December 2022	Visual ground inspection
	March 2023	Visual ground inspection
Maintenance	December 2022	Straighten and key pole, POLSAL-01

Note:

PM = preventive maintenance

Condition. As of the last reporting cycle, SAL was in fair condition. The line was fit for service; however, other improvements are being evaluated.

Sawyer Camp Power Pole Line (SCL)

Description. SCL is a 4.16 kV overhead distribution line in San Mateo County. SCL provides power to the Sawyer Camp watershed keeper's cottage and a small storage facility near Sawyer Camp Lake. SCL is approximately 0.5 overhead line mile in length and is in a Tier 3 High Fire Threat District.

Maintenance. Table 4-119 summarizes maintenance work.

Condition. As of the last reporting cycle, SCL was in fair condition. The line was fit for service; however, other improvements are being evaluated.

Table 4-119: Sawyer Camp Power Pole Line Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	December 2023	Visual ground inspection
Maintenance		No maintenance reported

Note:

PM = preventive maintenance

Sunol Water Temple Power Pole Line (STL)

Description. STL is a 480 V overhead distribution line in Alameda County. STL provides power to the Sunol Water Temple and smaller facilities surrounding it. STL is approximately 0.1 overhead mile long and in a Tier 2 High Fire Threat District.

Maintenance. Table 4-120 summarizes maintenance work.

Table 4-120: Sunol Water Temple Power Pole Line Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	December 2022	Visual ground inspection
Maintenance		No maintenance reported

Note:

PM = preventive maintenance

Condition. As of the last reporting cycle, STL was in good condition. The line was fit for service; however, other improvements are being evaluated.

4.8.2.2 <u>Capital Improvements</u>

Currently, there are no capital projects planned for these assets.

4.9 Watersheds, Roads, and Bridges

To access the RWS facilities, SFPUC maintains various roads and bridges across the region. SFPUC also maintains and manages watersheds that feed their Bay Area reservoirs. The responsibility for O&M of these assets is divided geographically between both HHWP and NRLMD. A map of the SFPUC watersheds is included as Appendix D.

4.9.1 Hetch Hetchy Water

HHWP is responsible for the maintenance and operation of a series of roads and bridges along its system, including almost 40 miles of paved roads, 12 bridges, and about 120 miles of unpaved access roads. Many of the roads and bridges are also used by USFS and NPS personnel to access federal assets and resources. Additionally, these assets are used by the public to access the Stanislaus National Forest and Yosemite National Park.

4.9.1.1 Asset Descriptions, Maintenance, and Condition

Cherry Lake Road

Description. Cherry Lake Road is a 23.5-mile-long paved road that extends from Highway 120, east of Groveland, to Lake Lloyd (aka Cherry Lake). Cherry Lake Road was formerly referred to as Cherry Oil Road.

Maintenance. Table 4-121 summarizes maintenance work.

Table 4-121: Cherry Lake Road Preventive Maintenance Summary (July 1, 2022, throughJune 30, 2024)

Name of PM	Completion Date(s)	Description
Maintenance	Completed annually	Clean ditches and grade right-of-way roads
	Completed annually	Road improvements and paving
	Completed seasonally	Culvert cleaning
	Completed seasonally	Snow removal

Note:

PM = preventive maintenance

Condition. Cherry Lake Road is in good condition and is fit for service. Portions of the road surface were patched and chip-sealed, and roadside drainage culverts were cleared during the reporting cycle. This road suffered damage during the 2022-23 storm event. Improvements included gabion walls, excavation and recompaction, lagging walls with H-Piles, and rock buttresses with drainage. Refer to Section 4.9.1.2 regarding improvement locations.

Hetch Hetchy Road

Description. Hetch Hetchy Road is a 17-mile-long paved road. It extends from Cherry Lake Road (at approximate mile post 5) to O'Shaughnessy Dam and Hetch Hetchy Reservoir and has uses similar to those of Cherry Lake Road; however, it also serves as a redundant route to Camp Mather.

Maintenance. Table 4-122 summarizes maintenance work.

Condition. Hetch Hetchy Road is in good condition and is fit for service. Portions of the road surface were patched and chip-sealed, and roadside drainage culverts were cleared during the reporting cycle. This road suffered damage during the 2022-23 storm event. Improvements included gabion walls, excavation and recompaction, lagging walls with H-Piles, and rock buttresses with drainage. Refer to Section 4.9.1.2 regarding improvement locations.

Table 4-122: Hetch Hetchy Road Preventive Maintenance Summary (July 1, 2022, throughJune 30, 2024)

Name of PM	Completion Date(s)	Description
Maintenance	Completed annually	Clean ditches and grade right-of-way roads
	Completed annually	Road improvements and paving
	Completed seasonally	Culvert cleaning
	Completed seasonally	Snow removal

Note:

PM = preventive maintenance

O'Shaughnessy Adit Access Bridge

Description. O'Shaughnessy Adit Access Bridge (aka the Hetchy Adit Bridge) is a four-span, simply supported bridge with timber stringers and deck, and reinforced concrete piers. The bridge has a total length of 136 feet, spanning the Tuolumne River, and is downstream of O'Shaughnessy Dam. The primary function of the bridge is to provide access to Canyon Tunnel's Hetchy Adit.

Maintenance. Table 4-123 summarizes maintenance work.

Table 4-123: O'Shaughnessy Adit Access Bridge Preventive Maintenance Summary (July 1, 2022,
through June 30, 2024)

Name of PM	Completion Date(s)	Description
Maintenance	Completed annually	Cleaning and inspection of bridge

Note:

PM = preventive maintenance

Condition. O'Shaughnessy Adit Access Bridge is in fair condition and is currently meeting access needs. However, access to Hetchy Adit for the upcoming bulkhead construction project requires increased loading on O'Shaughnessy Adit Access Bridge; improvements are being planned.

Cherry Lake Road Bridge at Early Intake

Description. Cherry Lake Road Bridge at Early Intake (aka Early Intake Bridge) is a two-span, simply supported bridge with rolled steel beams, timber deck, and reinforced concrete piers. The bridge has a total length of 24 feet, spanning the Tuolumne River, and is downstream of Early Intake Dam. The primary function of the bridge is to provide access to multiple critical assets in the Stanislaus National Forest.

Maintenance. Table 4-124 summarizes maintenance work.

Table 4-124: Cherry Lake Road Bridge at Early Intake Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description	
Inspection	Completed annually	Bridge inspection	
Maintenance	Completed annually	Intake wooden bridge cleaning	

Note:

PM = preventive maintenance

Condition. Cherry Lake Road Bridge at Early Intake is in fair condition and is fit for service for some activities. However, weight limitations have impacted HHWP's operations at times.

Cherry Lake Road Bridge at Cherry Creek

Description. Cherry Lake Road Bridge at Cherry Creek (aka Cherry Creek Bridge) is a three-span, continuous bridge with steel beams, reinforced concrete deck, steel bents, and reinforced concrete piers. The bridge has a total length of 27 feet, spanning Cherry Creek, and is upstream of Holm Powerhouse. The primary function of the bridge is to provide continuity of Cherry Lake Road over Cherry Creek, establishing access to multiple water and power assets in the Stanislaus National Forest.

Maintenance. Table 4-125 summarizes maintenance work.

Table 4-125: Cherry Lake Road Bridge at Cherry Creek Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Bridge inspection

Note:

PM = preventive maintenance

Condition. Cherry Lake Road Bridge at Cherry Creek is in fair condition and is fit for service.

Holm Access Bridge

Description. Holm Access Bridge (aka Holm Intake Bridge) is a three-span, continuous bridge with reinforced concrete beams, deck, and piers. The bridge has a total length of 136 feet, spanning Cherry Creek, and is downstream of Holm Powerhouse. The primary function of the bridge is to provide access to Holm Powerhouse.

Maintenance. Table 4-126 summarizes maintenance work.

Table 4-126: Holm Access Bridge Preventive Maintenance Summary (July 1, 2022, throughJune 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed annually	Bridge inspection for Holm Powerhouse Bridge
	Completed annually	Bridge inspection for Holm Powerhouse Bridge Vegetation

Note:

PM = preventive maintenance

Condition. Holm Access Bridge is in fair condition and is fit for service.

South Fork Siphon Access Bridge

Description. South Fork Siphon Access Bridge (aka South Fork Bridge) is a single-span, welded truss bridge with reinforced concrete deck and abutments. The bridge has a total length of 220 feet, spanning the Middle Fork of the Tuolumne River, and is north of Highway 120 near its intersection with Cherry Lake Road. The primary function of the bridge is to provide access to Mountain Tunnel's South Fork Siphon.

Maintenance. No PM was required or completed during this period.

Condition. South Fork Siphon Access Bridge is in good condition and is fit for service.

Cherry Lake Road Bridge at Middle Fork

Description. Cherry Lake Road Bridge at Middle Fork (aka Middle Fork Bridge) is a three-span bridge with a pre-stressed box girder main span, reinforced concrete slabs for the remaining spans, and reinforced concrete piers and abutments. The bridge has a total length of 102 feet, spanning the Middle Fork of the Tuolumne River, and is north of South Fork Yard, near the intersection of Cherry Lake Road and Highway 120. The primary function of the bridge is to provide access to multiple water and power assets in the Stanislaus National Forest.

Maintenance. No PM was required or completed during this period.

Condition. Cherry Lake Road Bridge at Middle Fork is in good condition and is fit for service.

Moccasin Creek Debris Deflector Bridge

Description. Moccasin Creek Debris Deflector Bridge (aka Moccasin Creek Bridge) is an eightspan, continuous bridge with timber stringers and deck, steel piers, and reinforced concrete abutments. The bridge has a total length of 136 feet, spanning Rattlesnake Creek, and is upstream of Moccasin Reservoir. The primary function of the bridge is to serve as a debris barrier to help keep debris from entering the Moccasin Diversion Pipe during medium- and high-flow events.

Maintenance. Table 4-127 summarizes maintenance work.

Table 4-127: Moccasin Creek Debris Deflector Bridge Preventive Maintenance Summary(July 1, 2022, through June 30, 2024)

Name of PM	Completion Date(s)	Description
Inspection	Completed bi-annually	Inspect for debris

Note:

PM = preventive maintenance

Condition. The Moccasin Creek Debris Deflector Bridge is in good condition and is fit for service.

California Aqueduct Bridges 1 and 2

Description. California Aqueduct Bridges 1 and 2 (aka Hetch Hetchy Maintenance Bridges 1 and 2) are both two-span, continuous bridges with reinforced concrete beams, decks, and piers. The bridges each have a length of 144.5 feet, spanning the California Aqueduct in the Central Valley. The primary function of the bridge is to provide access for HHWP personnel performing O&M activities along the SJPLs and power transmission system.

Maintenance. No PM was required or completed during this period.

Condition. California Aqueduct Bridges are in serviceable condition.

Oakdale Irrigation District Bridges 1 and 2

Description. Oakdale Irrigation District Bridges 1 and 2 (aka OID 1 and OID 2) are single-span bridges with rolled steel beams, timber decks, and reinforced concrete abutments. OID 1 has an overall length of 102 feet, spanning the Brichetto Lateral Canal; OID 2 has an overall length of 83.5 feet, spanning the Claribel Lateral Canal. The primary function of the bridges is to provide access for HHWP personnel performing O&M activities along the SJPLs and power transmission system.

Maintenance. No PM was required or completed during this period.

Condition. The surface deck of California Aqueduct Bridge 1 needs to be replaced but is currently meeting access needs; repairs are being planned. California Aqueduct Bridge 2 is in serviceable condition, with no planned repairs.

4.9.1.2 <u>Capital Improvements</u>

HHWP currently has capital projects in its watersheds, roads, and bridges program, representing a total capital investment of \$69.7 million. HHWP also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of these active large capital projects are provided in the following sections.

2023 January Winter Storm (Approved Budget \$10.6 Million; Substantial Completion: 2026)

Scope. Beginning on December 27, 2022, and over a 3-week period, severe winter storms related to a series of atmospheric river systems swept across the state of California. The storms brought high winds, substantial precipitation, and flooding to HHWP facilities, equipment, and access roads in Tuolumne County, San Joaquin County, and Alameda County. This project addressed emergency actions and repairs to assets along the HHWP system that were damaged during the

storm event, including debris removal activities to provide access; and emergency protective measures to address immediate threats to human health, assets, and the environment. The project also included design and repair of damaged roads and other assets. Repair methods include gabion walls, excavation and recompaction, lagging wall with H-Piles, and rock buttresses with drainage. The January winter storm locations include Cherry Lake Road mileposts (MPs) 1.3, 3.1, 5.85, 10.8, 13.4, and 21.2; and various additional sites around HHWP access roads and ROW in Sunol, Livermore, Tracy, and Groveland. The emergency repairs have been separated into three phases: 1) minor repairs on Hetch Hetchy Road and Cherry Lake Road; 2) major repairs on Hetch Hetchy Road and Cherry Lake Road; 2) major repairs on Hetch Hetchy Road and Cherry Lake Road; 3) all remaining storm damage sites. Construction for Phases 1 and 2 is complete, and Phase 3 is in the planning stages.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-128.

Table 4-128: 2023 January Winter Storm Project Milestones Completed During the CurrentReporting Cycle

Milestones	Completion Date
Emergency declaration	March 22, 2023
Substantial completion for minor sites	June 15, 2023
Final completion for minor sites	June 23, 2023
Substantial completion for major sites	April 30, 2024
Planning and design – issued a notice to proceed for professional services for remaining storm damage sites	April 2, 2024

2023 March Winter Storm (Approved Budget \$42.1 Million; Substantial Completion: 2026)

Scope. During February and March 2023, a series of winter storms continued across the state of California, bringing high winds, substantial precipitation, and flooding in addition to what had been encountered in January 2023. These additional storm events had an impact to several HHWP facilities, equipment, and access roads in Tuolumne County, San Joaquin County, and Alameda County. This project will address emergency actions and repairs to joint assets along the HHWP system that were damaged during the storm event, including debris removal activities to provide access; and emergency protective measures to address immediate threats to human health, assets, and the environment. In addition, design and repair of damaged roads and other assets will be provided. Repair methods include gabion walls, excavation and recompaction, lagging wall with H-Piles, and rock buttress with drainage. The March winter storm locations include Cherry Lake Road MPs 2.7, 5.0, 5.8, 5.9, 6.1, 6.2, 6.3, 6.5, 6.8, 6.9, 7.8, 8.2, 8.9, 9.5, 10.2, 12.3, 12.4, 12.6, 12.7, 13.3, 13.45, 13.5, 14.3, 14.4, 15.1, 17.3, 19.1, 20.0, and 21.5; Hetch Hetchy Road MPs 0.8, 1.0, 1.1, 2.8, 2.9, 4.6, 6.7, 13.2, 13.3, 13.5, 13.6, 13.7, 14.4, and 15.5; and various additional sites around HHWP access roads and ROW in Livermore and Groveland. The emergency repairs have been separated into three phases: 1) minor repairs on Hetch Hetchy Road and Cherry Lake Road, 2) major repairs on Hetch Hetchy Road and Cherry Lake Road; and 3) all remaining storm damage sites. Construction for Phases 1 and 2 is complete, and Phase 3 is in the planning stages.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-129.

Table 4-129: 2023 March Winter Storm Project Milestones Completed During the CurrentReporting Cycle

Milestones	Completion Date			
Emergency declaration	March 22, 2023			
Substantial completion for minor sites	June 15, 2023			
Final completion for minor sites	June 23, 2023			
Substantial completion for major sites	April 30, 2024			
Planning and design – issued a notice to proceed for professional services for remaining storm damage sites	April 2, 2024			

Holm Bridge Rehabilitation (Approved Budget \$11.7 Million; Substantial Completion: 2036)

Scope. The project includes replacing the 136-foot, three-span, continuously supported bridge over Cherry Creek that provides the only access to Holm Powerhouse. Bridge replacement will address seismic and current Caltrans design standard deficiencies (e.g., T-beam steams, end diaphragms, and lateral struts).

Milestones Completed During the Reporting Cycle. There were no milestones achieved during this reporting cycle. The Holm Bridge Rehabilitation project is scheduled to kick off in 2030.

Bridge Replacement (Approved Budget \$5.2 Million; Substantial Completion: Not Applicable)

Scope. This project originally included rehabilitation and/or replacement of O'Shaughnessy Adit Access Bridge and Lake Eleanor Dam Bridge. O'Shaughnessy Adit Access Bridge is the only access to Canyon Tunnel Hetchy Adit. The proposed work relating to the bridge and adit will be implemented under a single construction contract. Accordingly, SFPUC decided to combine the rehabilitation of O'Shaughnessy Adit Access Bridge with the Canyon Tunnel Hetchy Adit (Project #10014108). At the same time, Eleanor Dam Bridge is an integral part of the Eleanor Dam. Accordingly, Eleanor Dam Bridge replacement will be included as part of the scope of Eleanor Dam Rehabilitation (Project #10030759). The current proposed budget for the Bridge Replacement project will cover the planning efforts performed on these two bridge subprojects so far. The planning efforts of O'Shaughnessy Adit Access Bridge and Eleanor Dam Bridge will continue under Canyon Tunnel Hetchy Adit (Project #10014108) and Eleanor Dam Rehabilitation (Project #10030759), respectively.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-130.

Table 4-130: Bridge Replacement Project Milestones Completed During the Current ReportingCycle

Milestones	Completion Date			
Lake Eleanor Dam Bridge - NTP for interim repairs and AAR kickoff	November 2023			
Lake Eleanor Dam Bridge - Drone survey and inspection of dam	May 2024			
Lake Eleanor Dam Bridge – Draft AAR/CER	June 2024			
O'Shaughnessy Adit Access Bridge – Geotechnical interpretive evaluation and geotechnical data report	April 2022			
O'Shaughnessy Adit Access Bridge – AAR	October 2022			
O'Shaughnessy Adit Access Bridge – Draft CER	February 2023			
O'Shaughnessy Adit Access Bridge - Structural analysis and load rating	April 2024			
O'Shaughnessy Adit Access Bridge – Hydraulic analysis of flow clearance	May 2023			
O'Shaughnessy Adit Access Bridge – Draft wetlands delineation submitted	December 2023			
O'Shaughnessy Adit Access Bridge – Design criteria report	June 2024			
O'Shaughnessy Adit Access Bridge – 65% design	June 2024			

Notes:

AAR = Alternatives Analysis Report CER = Conceptual Engineering Report NTP = Notice to Proceed

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-131.

Table 4-131: Watershed, Roads, and Bridges – Levels of Service Project Drivers

	Level of Service							
Project	Drinking Water Quality	Regional Seismic Reliability	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
2023 January Winter Storm	~		~			~	~	
2023 March Winter Storm	~		~			~	~	
Holm Bridge Rehabilitation			~					
Bridge Replacement			~					

4.9.2 Regional Water

4.9.2.1 Asset Maintenance

NRLMD is responsible for the O&M of the SFPUC Alameda and Peninsula watersheds, including the roads, fences, fuel breaks, and culverts in those watersheds. PM activities for these assets are determined and scheduled by NRLMD. The maintenance is performed by other WE divisions, contractors overseen by NRLM staff, or NRLM staff themselves. Some of these assets are in Maximo, but many are not. Work being performed in the watershed includes:

- Maintenance of the watersheds:
 - Ingress/egress, including gates, locks, and fencing
 - Vegetation management for roadside clearance, fuels management, and hazard tree removal
 - Maintenance of rangeland management infrastructure, including solar groundwater pumps, troughs, piping, and spring boxes
 - Maintenance and monitoring of the Bioregional Habitat Restoration mitigation sites
 - Habitat restoration and protection, including invasive plant and wildlife control, flagging and fencing of sensitive habitat areas, erosion control, and planting or seeding native species
- Maintenance of roads and culverts:
 - Grading, rocking, and/or repaving roads
 - Clearing roadside ditches or drainage ditches of seasonal debris
 - Cleaning and repairing culvert inlet and outlet structures
 - Culvert repair, replacement, and installation
- Maintenance of the transmission pipeline ROWs:
 - Vegetation management for state weed abatement compliance, fuels management, and hazard tree removal
 - Removal of trash, debris, and other materials for health and safety and code compliance

4.9.2.2 <u>Capital Improvements</u>

Regional Water currently has capital projects in its watersheds, roads, and bridges program, representing a total capital investment of \$58.3 million. Regional Water also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

2022-23 Winter Storms

The Alameda and Peninsula watersheds experienced unprecedented winter storms in the 2022-23 wet season. Runoff from high-intensity and extended-duration rainfall damaged watershed roads, culverts, and other infrastructure. Both watersheds experienced road prism failures, destroyed culverts, and other damages that impacted watershed operations and access to critical facilities. Repairs are guided by BMPs and include increased surface drainage (road out sloping, rolling dips, etc.) and erosion control (riprap at the culvert inlet/outlet).

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

NRLMD funded storm damage repairs through its existing capital and programmatic budgets, in addition to meeting regulatory and environmental requirements. NRLMD is pursing reimbursement through FEMA's Public Assistance program for eligible damages that are grouped into approximately 20 projects, totaling \$15 million. Most of the small projects are complete, with the large projects currently in design and/or construction.

East Bay Regional Park District Water System (Approved Budget \$5.5 Million; Substantial Completion: 2022)

Scope. As a mitigation for the Calaveras Dam Replacement project, SFPUC agreed to construct new potable water distribution facilities for the Sunol Regional Wilderness Park (SRP), managed by the East Bay Regional Park District (EBRPD). EBRPD owns and maintains a water system at SRP headquarters, which previously supplied potable water to four park facilities, as well as drinking water fountains and picnic areas interspersed throughout the park. Currently, the water system serves non-potable water for use by EBRPD employees only. Since the system stopped producing potable water due to supply and sanitary deficiencies, EBRPD has been supplying park visitors with bottled water trucked in by a contracted vendor. The project purpose is to provide a reliable water supply for potable use at the EBRPD facilities and to provide potable uses at the SRP. Project work includes: 1) modification of the existing High Valley water system; 2) installation of new High Valley pipeline and appurtenances; 3) modification of the existing headquarters water system; 4) installation of a new fire suppression system; 5) installation of a new control system; 6) replacement and installation of new solar panels; 7) micro-surfacing of Geary Road from the entrance park sign to the entrance of the Ohlone Bridge; 8) pavement and site restoration along locations where the project requires trench excavation; 9) setup of wildlife exclusion fencing and environmental mitigation/monitoring; and 10) site restoration, including hydroseeding, hiking trail, asphalt pavement, grading, and fences.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-132.

Milestone	Date Complete		
Substantial completion	August 16, 2022		
Construction phase complete	May 30, 2023		

Table 4-132: EBRPD Water System Project Milestones Completed During the CurrentReporting Cycle

Note:

EBRPD = East Bay Regional Park District

Sneath Lane Gate/San Andreas (Approved Budget \$12.4 Million; Substantial Completion: 2035)

Scope. The 2001 Peninsula Watershed Management Plan identified the need for a new trail connection between San Mateo County's Crystal Springs Regional Trail (North San Andreas) to Golden Gate National Recreation Area's (GGNRA) Sweeney Ridge property at the Sneath Lane Gate. The trail is a critical connection among existing regional trails at the northern end of the Peninsula watershed and will serve hikers, bikers, and equestrians. The project includes construction of a multi-modal, 6-foot-wide trail that would be approximately 1.25 miles long and would include a new trailhead, south of GGNRA's parking lot at the end of Sneath Lane in

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Pacifica. The project will include the following related construction tasks: 1) tree removal; 2) installation of wildlife-friendly security fencing; 3) grading and drainage work; 4) paving of one trailhead parking areas with educational signage; 5) protection of sensitive habitat; and 6) site/vegetation restoration.

This project is an example of investing in watershed management compatible with protecting the watershed lands and providing an opportunity to educate the public about the SFPUC water system and watershed land management.

Milestones Completed During the Reporting Cycle. The milestone achieved during this reporting cycle is summarized in Table 4-133.

Table 4-133: Sneath Lane Gate/San Andreas Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete	
Project planning in progress	Pending	

Southern Skyline Blvd Ridge Trail Extension (Approved Budget \$37.98 Million; Substantial Completion: 2025)

Scope. The Bay Area Ridge Trail project was started in 1987 by the Bay Area Ridge Trail Council to create an approximately 550-mile continuous trail for hikers, mountain bicyclists, and equestrians along the ridgelines overlooking San Francisco Bay. The objectives of the project are to provide access to the Peninsula watershed, enhance educational opportunities, and ensure watershed protection. South of Route 92, this proposed extension project includes a 6-mile-long trail on the Peninsula Watershed in San Mateo County between Highway 92 and GGNRA's Phleger Estate. North of Route 92, the project includes a 1-mile-long segment adjacent to the Fifield Cahill Trail that is compliant with the Americans with Disabilities Act. South of Route 92, the trail will be 6 feet wide, with an all-weather surface; north of Route 92, the trail will be 10 feet wide. In addition, the project involves the following improvements: restrooms (three total); 9.3 miles of wildlife-friendly security fencing; grading and drainage work; 2,000 linear feet of soldier pile retaining walls; two parking lots; interpretive signs; and habitat protection. In addition, the project includes the following construction and construction-related work: 1) removal of 160 trees; 2) installation of 9.3 miles of wildlife-friendly security fencing; 3) grading and drainage work; 4) installation of 2,000-linear-foot soldier pile retaining walls; 5) paving of two trailhead parking areas with educational signage; 6) protection of sensitive habitat; 7) traffic control; and 8) site/vegetation restoration.

This project is an example of investing in watershed management compatible with protecting the watershed lands and providing an opportunity to educate the public about the SFPUC water system and watershed land management. The project will provide public access to the Peninsula Watershed while providing an essential link of the Bay Area Ridge Trail.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-134.

Table 4-134: Southern Skyline Boulevard Ridge Trail Extension Project Milestones Completed
During the Current Reporting Cycle

Milestone	Date Complete
Bid advertisement	June 9, 2023
Construction NTP	January 8, 2024 Substantial Completion: July 2025

Note:

NTP = Notice to Proceed

SA-1 Service Road/Ingoing Road (Approved Budget \$18.06 Million; Substantial Completion: 2026)

Scope. SFPUC has identified erosion damage that has destabilized watershed access roads in three locations on Peninsula Watershed along the San Andreas Reservoir in San Mateo County. The project entails repairing the damage and implementing long-term solutions for SFPUC staff and contractors to continue to use the roads to access, operate, and maintain SFPUC facilities and watershed lands. This project would also include installation of a new anchor system for the new floating debris boom in San Andreas Reservoir upstream of the dam. The scope of work includes the following: 1) grade and backfill the slopes at the San Andreas Service Road (north), from the access road to the reservoir's eastern shoreline, to reestablish the embankment (slope that has eroded); 2) install shoreline riprap at all San Andreas Service Road erosion repair locations; 3) at the ingoing road (San Andreas dam gate) location, where the slope from the access road is eroded steeply to the shoreline, install a 475-linear-foot soldier pile retaining wall with tiebacks, and restore the embankment from the retaining wall to the shoreline with engineered backfill and/or riprap; 4) grind and overlay the roadway surface for the ingoing road; 5) install two new 35-footlong to 40-foot-long culverts with associated concrete storm inlet structures; and 6) replace and install a new anchorage system for the floating debris boom that stretches across San Andreas Reservoir.

This project provides funding to support investments in watershed assets under SFPUC management and improves the ability to cost-effectively manage access to and protect water system infrastructure by maintaining roads in good condition.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-135.

Table 4-135: SA-1 Service Road/Ingoing Road Project Milestones Completed During the Current Reporting Cycle

Milestone	Date Complete		
Construction NTP	March 4, 2024		

Note:

NTP = Notice to Proceed

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Watershed and ROW Protection – Land Acquisition (Approved Budget \$2.16 Million; Substantial Completion: 2034)

The Watershed and Environmental Improvement Program (WEIP) includes the comprehensive identification and protection of critical watershed lands and ecosystem restoration needs within the hydrologic boundaries of the Alameda Creek, Peninsula (San Mateo and Pilarcitos Creeks), and Tuolumne River watersheds; and prioritizes the protection and/or restoration of these lands. Projects under this program will protect source water quality; protect native species and their habitat; and identify critical watershed lands for protection by purchasing fee title and/or perpetual conservation easements from willing landowners. Initial funding for this program came from WSIP bond funds (\$20 million); now that these funds have been expended, funding will come from CIP bond funds. Staff is working on a 4,600-acre acquisition in the Alameda Creek watershed. It is anticipated that the purchase will be considered by SFPUC in late 2024 or early 2025.

Milestones Completed During the Reporting Cycle. The project milestone achieved during this reporting cycle is summarized in Table 4-136.

Table 4-136: Watershed and ROW Protection Project Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete		
Project planning in progress	Pending		

Note:

ROW = right-of-way

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-137.

	Level of Service							
Project	Drinking Water Quality	Seismic	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability	Water Supply	Environ. Steward.	Sustain- ability
EBRPD Water System			✓					
Sneath Lane Gate/San Andreas							~	~
Southern Skyline Blvd Ridge Trail Extension							~	~
SA-1 Service Road/ Ingoing Road			~					~
Watershed and ROW Protection - Land Acquisition	~						~	~

Notes:

EBRPD = East Bay Regional Park District ROW = right-of-way RWS = Regional Water System

4.10 Wastewater Treatment Assets

4.10.1 Hetch Hetchy Water

HHWP is responsible for the maintenance and operation of small wastewater systems that serve its buildings and ground assets at multiple upcountry locations. These wastewater systems include:

O'Shaughnessy Wastewater System	Moccasin Wastewater System
Early Intake Wastewater System	

4.10.1.1 Asset Descriptions, Maintenance, and Condition

O'Shaughnessy Wastewater System

Description. The sewage system leading to the lift station is made up of iron pipe coming from the cottages and gravity, feeding a main sewer line running along O'Shaughnessy Camp Road. At the lift station, the main sewer pipe feeds a grinder to ensure that only solids are deposited into the wet well sewage tank. In the lift station, pumps maintain proper levels in the sewage tank through float switches and a control panel. The station pumps transfer sewage from the wet well to the main septic tanks on the opposite end of O'Shaughnessy Camp next to the restrooms near the exit loop. These septic tanks also handle sewage from nearby restrooms. Effluent from these septic tanks continues to a final holding tank fitted with a siphon to regulate discharge.

The original design included a 36,000-square-foot spray field infrastructure. Based on operations over the last 11 years, it has been determined that the function operates appropriately without the spray field. The spray field infrastructure has been retired.

Maintenance. Table 4-138 summarizes maintenance work.

Name of PM	Completion Date(s)	Description
Wastewater Sampling	ng N/A Sampling of wastewater not required un permit	
Inspection	Completed daily	Facility inspected by Stationary Engineer
	Continuously monitored	Audible alarm system on site
Monitoring	Completed daily	Plant visually monitored for proper operation of equipment and treatment processes
	Completed annually	Effluent flows and operational data reported by Stationary Engineering Crew

Table 4-138: O'Shaughnessy Wastewater System Preventive Maintenance Summary (July 1,2022, through June 30, 2024)

Notes:

PM = preventive maintenance

N/A = not applicable

Condition. A condition assessment for the O'Shaughnessy lift station was performed, and a project is scheduled to rehabilitate the facility.

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Early Intake Wastewater System

Description. The Early Intake facility consists of the Kirkwood Powerhouse and its related O&M complex. Wastewater is generated from domestic uses of the various residential and facility-related structures, including seven cottages, a bunkhouse, a dining hall, offices, a pool, bathrooms, and a switchyard bathroom. The Kirkwood Powerhouse generates industrial wastewater consisting of water that seeps into the powerhouse and general operations. This water is collected by a drainage and sump system, incorporating an oil/water separator system to remove potential food grade grease and oil. The wastewater system collects and transports wastewater to the established leachfield west of the switchyard, using sewers, pipes, pumps, and lift stations. To prevent breakage during potential flood events, the sewer line crosses the Tuolumne River through a double contained line that is securely attached to the decking and framework of the vehicular bridge that crosses the river. The engineered leachfield contains 16 observation wells that are systematically spaced to monitor the wastewater levels.

Maintenance. Table 4-139 summarizes maintenance work.

Table 4-139: Early Intake Wastewater System Preventive Maintenance Summary (July 1, 2022,
through June 30, 2024)

Name of PM	Completion Date(s)	Description	
Wastewater Sampling	Completed quarterly	Sample plant effluent for suspended solids, biology, and chemistry	
Inspection	Completed daily	Facility inspected by Stationary Engineer	
	Continuously monitored	Plant monitored continuously via SCADA alarms	
Monitoring	Completed quarterly	Effluent flows and operational data reported by Stationary Engineering Crew	

Notes:

PM = preventive maintenance

SCADA = supervisory control and data acquisition

Condition. Early Intake Wastewater System is operational; however, due to its age, a condition assessment is recommended to determine whether capital investments are needed.

Moccasin Wastewater System

Description. Moccasin Sewage Treatment Plant (MSTP) consists of an extended aeration package plant, with disposal by means of spray irrigation and periodic sludge removal. The MSTP collection system consists of approximately 1 mile of sewer main line and various laterals to structures receiving wastewater service. The collection system operates primarily under gravity, with a lift station providing final delivery. Wastewater originates from a complex of residences, a maintenance complex, small water quality laboratory, and administrative offices. Flows to the MSTP typically range between 5,000 gallons and 20,000 gallons per day. There are three monitoring wells (M-1, M-2B, and M-3) installed around the effluent pond; they are purged and sampled on a quarterly basis to monitor potential groundwater impacts from MSTP operations.

Maintenance. Table 4-140 summarizes maintenance work.

Condition. A condition assessment was completed, and a capital project was approved to replace MSTP.

Table 4-140: Moccasin Wastewater System Preventive Maintenance Summary (July 1, 2022,
through June 30, 2024)

Name of PM	Completion Date(s)	Description		
Wastewater Sampling	Completed biweekly	Sample plant effluent for dissolved and suspended solids and chemistry		
Inspection	Completed daily	Facility inspected by Stationary Engineer		
Surveillance and	Continuously monitored	Plant monitored continuously via SCADA alarms		
Monitoring	Completed daily	Sampling of pH, DO, and flow rates are performed by Stationary Engineering Crew		

Notes:

DO = dissolved oxygen

PM = preventive maintenance

SCADA = supervisory control and data acquisition

4.10.1.2 <u>Capital Improvements</u>

HHWP currently has capital projects in its wastewater treatment program, representing a total capital investment of \$15.4 million. HHWP also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

Moccasin Wastewater Treatment Plant (Approved Budget \$15.4 Million; Substantial Completion: 2027)

Scope. The project will entail replacing the existing Moccasin Wastewater Treatment Plant with a package two-train sequencing batch reactor (SBR) plant with grit removal and screening facilities, upgraded electrical and flow monitoring systems, flow equalization, SCADA instrumentation and automation features, and related site improvements.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in the Table 4-141.

Table 4-141: Moccasin Wastewater Treatment Plant Project Milestones Completed During the Current Reporting Cycle

Milestones	Completion Date
HH-1010 95% design workshop	February 2023
Construction contract advertised	October 2023
HH-1010 bid award	February 2024
HH-1010 construction NTP	June 2024

Note:

NTP = Notice to Proceed

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-142.

	Level of Service							
Project	Water		Delivery		In-City Delivery Reliability		Environ. Steward.	Sustain- ability
Moccasin Wastewater Treatment Plant			~					

 Table 4-142: HHWP Wastewater Treatment Project – Levels of Service Project Drivers

Note:

HHWP = Hetch Hetchy Water and Power

4.11 Communications and Control Assets

This category includes assets related to field communications, telephone, SCADA, and facility security. WE communication infrastructure includes microwave, fiber, and cable. SCADA system platforms include Wonderware, eDNA, and OSI. Phone system platforms include Avaya. The security system platform is Lenel. Cellular phone service providers also provide valuable service beyond voice communications. 4G and LTE systems allow transmission of data such as equipment nameplates and drawings.

4.11.1 Hetch Hetchy Water Upcountry Communication Sites

Description. HHWP's communication sites interconnect water transmission assets, hydroelectric assets, electric transmission assets, and common infrastructure. There are currently 27 relevant microwave radio sites in the HHWP communication system. The communication system begins at O'Shaughnessy Dam in Yosemite National Park and extends southwest to Calaveras Substation near Sunol and the San Antonio Reservoir.

A series of communication sites support the communication system; their sole function is to connect the assets described elsewhere in this report. They are:

Moccasin Peak Communication Site	Cherry Tower Site
Mt. Allison Communication Site	Intake Radio Site
Burn Out Ridge Communication Site	Poopenaut Pass Radio Site

Condition. These assets are in fair condition and fit for service; however, reliability can be improved by 1) replacing obsolete equipment with readily available and supported equipment; 2) constructing a backup fiberoptic path between Moccasin Control and Warnerville Switchyard; and 3) increasing spare parts inventories. Also, given the age of the microwave towers, a condition assessment of the lattice steel structures and foundations is recommended.

4.11.2 Radio

The WE radio system is made up of three separate radio systems, using different frequencies, and spans seven counties. Communication with field staff relies on three separate dispatch centers, vehicle-mounted radios, hand-held radios, and vehicle-mounted repeaters. These legacy systems have exceeded their life expectancy, have incomplete coverage, and lack many features needed

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

in today's utility business. This presents a challenge to maintain efficient operations and poses a safety risk when crews are working in locations where communications are unreliable. A project is underway to replace the legacy systems with a Project 25 standard, digital, modern, trunked (system selects the channel), Motorola high-band radio system. The new system will significantly improve coverage. This system will be fully integrated with, and be technically part of, the Department of Emergency Management's radio system. Once the project is complete in 2025, all SFPUC staff (along with most of CCSF staff) will be on the same radio system and technology, and operations outside of cellular coverage will be able to rely on radio as their primary means of communication.

It should be noted that cellular service reception is available in some areas. SFPUC staff continues to work with cell service providers to improve coverage by installing additional cell towers along RWS.

4.11.3 Telephone

SFPUC's telephone systems primarily use Virtual Private Networks through AT&T, using the Avaya platform. These systems are used for daily business communications and are not considered reliable or available during or following a disaster. SFPUC IT Services is piloting Voice over Internet Communications for self-reliance and cost savings reasons. HHWP recently completed an upgrade, replacing old cables with networked VoIP systems running on a fiber backbone.

4.11.4 SCADA

SCADA systems continue to operate reliably and effectively, providing process automation, operational visibility, and remote control.

The Water SCADA system (which covers Regional and Local Water Operation) continued to be responsive and reliable in meeting the operational needs of the RWS 24/7. Upgrades to Water SCADA system hardware and software infrastructure focused on reliability, performance, and security. Process automation, monitoring, and control continued to be enhanced at existing facilities throughout the RWS. Water SCADA underwent a significant enhancement with the SCADA software upgrade from the Wonderware 2014 platform to the new AVEVA 2020 System Platform. Water SCADA is undertaking a hardware modernization effort and upgraded controllers to the newer product platforms at sites such as Sunol Water Treatment Plant and Pleasanton Wells. There were significant enhancements to security with the implementation of enhanced network threat detection monitoring and asset management tools, decommissioning of legacy systems, and deployment of newer thin client hardware.

HHWP uses OSI Monarch for managing power assets and Wonderware for the water assets. Both systems require hardware and software updates. In coordination with SFPUC IT Services, HHWP plans to update both systems to the OSI platform by the end of 2025, updating both software and hardware as needed. The system will continue to be compatible with the SFPUC systems.

4.11.5 On-Line Monitoring Program Review

In May 2021, SFPUC WE began a comprehensive review of its on-line water monitoring system for the RWS. The project scope covered treated water remote monitoring SCADA sites from Moccasin Gate Tower down to the City's terminal reservoirs. Treatment facilities were not included in the review. The objective was to review the current monitoring sites and parameters, and identify recommendations to encourage sustainability, reliability, accuracy, and consistency. The study was delivered in February 2022 and identified 594 online sensors/signals at 81 remote monitoring locations in the treated system. There are seven regulatory sites and 22 operational monitoring sites with water-quality targets. Many sites are redundant and have been installed for purposes that are no longer needed. The recommendations from the study will continue as a second phase through 2024 and will further review maintenance records/needs, industry standards, travel time criteria, and emergency grab sampling capabilities, and make recommendations for the on-line monitoring system.

4.11.6 Capital Improvements

WE currently has capital projects in its communications and control program, representing a total capital investment of \$22.4 million. WE also has multiple R&R projects that are smaller in scope and budget and are reported annually. Summaries for each of the active large capital projects are provided in the following sections.

Radio Communication (Approved Budget \$20.8 Million; Substantial Completion: 2025)

Scope: The radio project replaces three WE low-frequency land mobile radio systems. The lowband radio systems are antiquated and no longer supported by the manufacturer. The goal of this project is to provide one unified interoperable land mobile radio system for business and emergency communications. CDD's, WSTD's and HHWP's low-band radio communication systems will be replaced with one public safety high-band (800 MHz, P25) radio system. Projects 10015119 and 10015120 will be consolidated into Project 10015118 because they each fall under the scope of providing radio communications improvements.

Milestones Completed During the Reporting Cycle. Milestones achieved during this reporting cycle are summarized in Table 4-143.

Milestone	Date Complete
Site Development – Cedar Ridge	May 17, 2024
Land mobile radio installations complete at seven sites	September 23, 2023
Environmental – NEPA/CEQA Reviews – Skyline Ridge	May 22, 2024

Table 4-143: Radio Communication Milestones Completed During the Current Reporting Cycle

Notes:

CEQA = California Environmental Quality Act

NEPA = National Environmental Policy Act

Section 4 – Asset Description, Maintenance and Condition, and Capital Improvements 2024 State of the Regional Water System Report

Regional SCADA PLC Upgrades (Approved Budget \$11.7 Million; Substantial Completion: 2028)

Scope: The Water SCADA system provides mission-critical automation, monitoring and control of SFPUC's RWS operations. PLCs are the critical component of the SCADA system that enable local process automation, and remote monitoring and control. The existing PLCs do not support the current industry security standards and will be replaced with PLCs that comply with the latest regulatory and industry security standards. In addition, the associated programming and configuration software runs on older versions of the Windows Operating System which are no longer supported by Microsoft (and SFPUC) and, therefore, expose the Water SCADA system to increased security risk. Project funding is spread across 10 years (2024 through 2033) to accommodate the end of manufacturer support while recognizing the limitations on concurrent operational outages to critical facilities. A prioritized list is available that provides location but is not published here for security reasons. This project will upgrade about 93 SCADA system PLCs that are or will be discontinued and will no longer be supported by manufacturers.

Milestones Completed During the Reporting Cycle. One milestone is pending completion during this reporting cycle, as summarized in Table 4-144.

Table 4-144: Regional SCADA PLC Upgrades Milestones Completed During the CurrentReporting Cycle

Milestone	Date Complete
Project planning in progress	Pending

Notes:

PLC = programmable logic controller

SCADA = supervisory control and data acquisition

Summary of Levels of Service Project Drivers

LOS drivers supporting these capital improvements are summarized in Table 4-145.

Table 4-145: Communication	System	Projects -	Levels of S	Service Project Drivers
	5	,	,	J

		Level of Service						
Project	Water	Seismic	Regional Delivery Reliability	In-City Seismic Reliability	In-City Delivery Reliability		Environ. Steward.	
Radio Communication	~		~					
Regional SCADA PLC Upgrades	~		~					

Notes:

PLC = programmable logic controller

SCADA = supervisory control and data acquisition

5. Regulatory Compliance

SFPUC is required to comply with federal and state regulations. This section will cover requirements applicable to the RWS assets. All federal and state primary drinking water standards were met within the RWS in the reporting period.

5.1 Federal and State Drinking Water Regulations

SFPUC tracks a variety of regulatory measures associated with O&M activities to ensure compliance. In addition to complying with the existing regulatory requirements, SFPUC has also been keeping track of, and actively involved in, the regulatory development of drinking water regulations at the federal and state levels that may have impacts on RWS operations.

The pace of new regulations is increasing, with several new regulations finalized already in 2024 (California SWRCB hexavalent chromium, United States Environmental Protection Agency [U.S. EPA] per- and polyfluoroalkyl substances [PFAS], U.S. EPA Consumer Confidence Report Rule). The Lead and Copper Rule Improvements (LCRI) is expected to be finalized by October 2024 and microbial/disinfection byproducts (M/DBPs) proposed by the end of July 2024. Most recently, on April 26, 2024, U.S. EPA published the final National Primary Drinking Water Regulation for six PFAS; and on May 24, 2024, U.S. EPA published the final revised Consumer Confidence Rule.

SFPUC maintains various EAPs related to drinking water regulations. EAPs maintained by SFPUC are included in Appendix B, Table B-2.

5.1.1 LCRR/LCRI

In January 2021, U.S. EPA adopted the Lead and Copper Rule Revision (LCRR), which became effective starting on December 16, 2021. The LCRR includes a suite of actions requiring water systems to further reduce lead exposure to customers through drinking water. It emphasizes six key areas: identifying the most impacted area; strengthening treatment requirements; replacing lead service lines (LSLs); increasing sampling reliability; improving risk communication; and protecting children in schools. The LCRI proposal was published in the Federal Register on December 6, 2023; comments were due on February 5, 2024; and U.S. EPA plans to finalize the LCRI by October 2024 (compliance is 3 years after promulgation). Implementing the LCRI will take significant resources, require new business practices, and increase public attention on lead.

The LCRI proposed changes include the following:

- Removal of all LSLs and galvanized requiring replacement (GRRs) is mandatory within 10 years of the compliance date (tentatively October 2037), regardless of 90th percentile lead levels.
- The service line replacement plan must document control and access issues for private property service line replacement. "Under the control" must be replaced.

- The updated inventory (tentatively due October 2027) must include lead connectors. Lead connectors are defined as not exceeding 2 feet in length.
- Water systems must offer lead sampling for any customer served by a LSL, GRR, or unknown service line, regardless of lead levels from compliance monitoring.
- The action level is lowered from 15 parts per billion (ppb) to 10 ppb; LCRR's trigger level is removed.
- Filters must be provided to all customers within 60 days of being determined to have multiple action level exceedances (three times within 5 years).
- All tap sampling results must be reported to consumers within 3 calendar days after the system learns of the results.

Although the RWS is mainly a water wholesaler operating a complicated network of transmission pipelines and treatment facilities, there are some existing retail customers who are directly connected to the transmission pipelines. An evaluation of the service lines on the customer side is being performed, and, if identified, any lead user service lines on the customer side will have to be replaced according to the LCRR. In the meantime, SWRCB is also working on the revision of its own version of the LCRR to align with requirements of the federal LCRR; this may possibly include additional requirements.

5.1.2 Total Coliform Rule

SFPUC conducts approximately 160 total coliform tests each month in the RWS. The RWS has always complied with the total coliform treatment technique (<5 percent positive tests) and E. coli maximum contaminant level (MCL) in accordance with the California Revised Total Coliform Rule. Total coliform positive tests are typically very low (0 to 1 percent). Over multi-year periods, there can be localized areas with increased coliform positive rates. When this occurs, an investigation is conducted, and any appropriate corrective actions are taken. If wholesale customers are impacted, they are included in the investigation. Corrective actions generally focus on the sample site or a very specific area.

5.1.3 Per- and Polyfluoroalkyl Substances

In September 2019, Governor Newsom signed Assembly Bill 756 into law. This required a public water system under a SWRCB order to report monitoring results for perfluorooctanoic acid (PFOA) and perfluorooctane sulfonate (PFOS), two PFAS compounds, to the state and to provide public notifications, as prescribed in the bill. The previously adopted drinking water notification and response levels for PFOA and PFOS were reduced further by SWRCB in February 2020. In March 2021, SWRCB established drinking water notification and response levels for perfluorobexane sulfonic acid (PFBS). On October 31, 2022, DDW finalized notification and response levels for perfluorobexane sulfonic acid (PFHxS), which is another member of the PFAS group. On April 26, 2024, U.S. EPA finalized the PFAS rule that included MCLs for five PFAS compounds (PFOA, PFOS, PFHxS, perfluorononanoic acid [PFNA], and hexafluoropropylene oxide-dimer acid [HFPO-DA, which is commonly known as GenX]), and for a PFAS mixture of PFNA, PFHxS, PFBS, and GenX in drinking water. The mixture is

Section 5 – Regulatory Compliance 2024 State of the Regional Water System Report

assigned a Hazard Index MCL to account for dose-additive health effects. U.S. EPA's rule requires all community water systems and non-transient, non-community water systems to monitor these six PFAS on a quarterly basis under the recently adopted MCL standards, although Unregulated Contaminant Monitoring Rule Fifth Round (UCMR5) sampling may satisfy some of those monitoring requirements.

In March 2019, SWRCB ordered select airports and landfills to investigate any impacts to nearby groundwater drinking sources and to determine whether PFAS is present. SWRCB had issued similar orders regarding PFAS monitoring at various industrial locations, urban wildfire areas, wastewater treatment facilities, and drinking water wells near these locations. SWRCB had not ordered a PFAS investigation for other community water systems, including the RWS. However, to assess the presence and extent of PFAS in their sources of water supply, SFPUC proactively and voluntarily monitored for PFAS in its RWS sources at several sites—seven surface water reservoirs, AEP, TTF intake, SVWTP effluent, and HTWTP effluent—between August 2019 and February 2020. At each location, 18 different PFAS compounds were analyzed using the available method (Method 537.1) approved by U.S. EPA and SWRCB. The monitored compounds included PFOA and PFOS. Samples were collected by SFPUC's experienced staff, following the very stringent sampling protocols established by SWRCB. These monitoring results confirmed that there were no PFAS detections at all RWS locations.

Upon completion of the first-round, voluntary PFAS monitoring indicated above—and in the absence of mandatory monitoring requirements from SWRCB—SFPUC conducted another round of voluntary PFAS monitoring for the RWS using the newer analytical method (Method 533) approved by U.S. EPA. The new method mainly targeted 25 short-chain PFAS contaminants. SFPUC completed two rounds of voluntary PFAS monitoring for the RWS, including the eight Phase 1 RGSR wells. The second round was completed in 2021, and all results were non-detect.

In December 2021, U.S. EPA published its UCMR5. The RWS was sampled for the required 29 PFAS contaminants on a quarterly schedule in 2023 (except for one location, Sunset Reservoir North, that was out of service and had its sampling extended to March 2024), and all results were non-detect.

5.1.4 Unregulated Contaminant Monitoring Rule

Every 5 years, U.S. EPA issues a list of unregulated contaminants to be monitored by public water systems. In the Fourth Unregulated Contaminant Monitoring Rule four-quarter monitoring completed in January 2019, SFPUC found quinoline, a coal-tar lining derivative, at the point of entry into the SFWS at Baden Valve Lot, at LMPS, and at the outlet at Sunset Reservoir. Although SFPUC has terminated the use of coal-tar in its repair and replacement program, there are still existing pipelines containing this type of lining. Replacing all these linings will require significant effort that can only be done over a longer period. The CSPL No. 2 Reach 5 Rehabilitation project is currently in design phase. Its scope includes removing 3.8 miles of coal tar enamel (CTE) lining and replacing it with CML in the existing 60-inch WSP between Millbrae Yard and Baden Valve Lot. This project is expected to be completed by 2027. The project AAR recommended using the water jetting (WJ) nonabrasive surface cleaning method to remove the existing CTE lining, with performance standard WJ-1 or WJ-2 as a minimum standard requirement before repairs and relining with CML. WJ-1 will remove existing lining to a matte finish without any visible foreign

Section 5 – Regulatory Compliance 2024 State of the Regional Water System Report

matter; WJ-2 will remove existing lining until there are stains/residues on less than 5 percent of the surface area. Given tightening regulatory requirements, and to minimize CTE leaching potential, SFPUC is planning to proceed with the WJ-1 cleaning method. Also, the CSPL No. 2 Reaches 2 and 3 Rehabilitation project is in the design phase; it includes relocating 1.5 miles of pipeline to the decommissioned CSPL No. 1 alignment and relining 2.2 miles of CTE-lined 60-inch WSP, stretching between CSPS and the Bellevue Valve Lot. This is expected to be completed by 2028.

UCMR5 required monitoring of 30 contaminants, (29 PFAS contaminants plus lithium). SFPUC completed the UCMR5 quarterly sampling in 2023 (except for one location, Sunset Reservoir North, that was out of service and had its sampling extended to March 2024) and all results were non-detect.

5.1.5 Other Revisions

In 2014, DDW implemented an MCL of 10 micrograms per liter (μ g/L) for hexavalent chromium. Following a legal challenge, the MCL was repealed in 2017. The MCL process was restarted to address the issues identified in the lawsuit; a draft proposed MCL of 10 μ g/L was issued in 2022, with the final rule adopted by SWRCB in April 2024. Since the implementation of the 10 μ g/L MCL in 2014, SFPUC has maintained a water quality operational goal of 4 μ g/L. There is hexavalent chromium above the current 10 μ g/L MCL and above the water quality goal in San Francisco groundwater wells and the RGSR groundwater. SFPUC implemented a blending strategy for the San Francisco groundwater wells to maintain hexavalent chromium concentrations below 4 μ g/L. This strategy will have to be extended to the RGSR wells when they are put in service.

SWRCB lowered the perchlorate detection limit for purposes of reporting (DLR), with the DLR decreasing from $4 \mu g/L$ to $2 \mu g/L$ as of July 1, 2021; and from $2 \mu g/L$ to $1 \mu g/L$ as of January 1, 2024. Future sampling of the RGSR wells may result in more perchlorate detections (currently detected in three wells) due to the lowered DLR.

On July 27, 2020, SWRCB adopted a definition of "microplastics in drinking water," in accordance with the requirements of Senate Bill No. 1422, which was incorporated as §116376 of California Health and Safety Code. With limited information on the potential health impacts of microplastics, DDW has not set regulatory levels to date and is focusing on monitoring, as described in the "Microplastics in Drinking Water Policy Handbook (August 2022)." DDW is employing a 4-year monitoring campaign to provide a better understanding of the prevalence of microplastics in drinking water systems, pending the adoption of the standard method of analysis and better definition of sampling protocols. SFPUC will closely monitor and track the regulatory development and participate in the monitoring efforts to ascertain the extent, if any, of microplastics in RWS's water sources and treated water. The nature of SFPUC source waters coming from protected watersheds makes it unlikely for microplastics to occur, and concentrations of microplastics in drinking water are likely to be extremely low.

U.S. EPA's M/DBP Stage 3 proposal is due by the end of July 2024. The National Drinking Water Advisory Council submitted recommended M/DBP rule changes to U.S. EPA in December 2023. The key recommendations include:

- **Disinfectant Residual.** Address the potential for no or low disinfectant residual in distribution systems
- **Premise Plumbing.** U.S. EPA should advance a national building water quality improvement initiative, based on an enhanced partnership among federal and state agencies.
- **DBPs of Emerging Concern.** Address data and analysis gaps associated with DBPs of emerging concern.
- **Multi-Benefit Precursor Control.** Establish a source water evaluation screening requirement and provide additional mandatory treatment to reduce DBP formation.
- **Finished Water Storage Tanks.** Address finished water storage tank vulnerabilities by establishing a national inspection and cleaning as needed requirement.
- **Chloramination.** Improve chloramination practices to promote control of microbial contamination and DBP formation potential.
- **Consecutive Systems.** Improve water quality and regulatory compliance rates for consecutive systems.

SFPUC participated in Water Research Foundation (WRF) project 5156 (Occurrence of *Legionella spp.* In Drinking Water Distribution Systems), with monitoring started in August 2022 and completed in 2022-23 (project meant to inform the M/DBP Stage 3 proposal). SFPUC's Millbrae laboratory developed internal *Legionella* testing capability for the WRF project and ongoing monitoring.

5.1.6 Drinking Water Permit Compliance

SWRCB DDW is responsible for implementing and enforcing drinking water regulations in California. SFPUC tracks a variety of regulatory measures associated with O&M activities to ensure compliance, including the drinking water system permit administered by the SWRCB DDW. All federal and state primary drinking water standards were met within the RWS in the reporting period (FY23 and FY24).

5.2 Environmental Compliance

Environmental stewardship is a goal of the 2023 updated Water System LOS. The WE Environmental Stewardship Policy provides direction for the management of the lands and natural resources that affect or are affected by SFPUC WE operations. Implementation of the Environmental Stewardship Policy is the responsibility of all WE employees, and training is a critical aspect of providing staff with the information necessary to meet this goal. The specific Environmental Stewardship Policy strategies are incorporated into the regular tailgate trainings performed for WE staff, based on their work assignments and locations, to ensure that staff

Section 5 – Regulatory Compliance 2024 State of the Regional Water System Report

receive this information as part of their regular responsibilities. WE also submits a report to SFPUC every 2 years, summarizing the implementation of the Environmental Stewardship Policy. The most recent report was submitted at the December 13, 2022, meeting.

In accordance with the WE Environmental Stewardship Policy and Water System LOS Environmental Stewardship Goal, SFPUC's environmental stewardship starts with impact avoidance and environmental regulatory compliance. SFPUC activities and third-party activities on SFPUC lands are evaluated for environmental regulatory compliance and consistency with SFPUC plans and policies through the Maximo work order review and project review processes. Projects are discussed by an interdisciplinary committee of SFPUC staff. Projects are modified to incorporate BMPs and environmental impact avoidance and minimization measures to protect resources whenever feasible. When impacts cannot be avoided, permits may need to be obtained to comply with environmental laws and regulations, such as the California Fish and Game Code, the Clean Water Act, and the California and federal Endangered Species Acts. San Francisco's Planning Department prepares any necessary California Environmental Quality Act documentation, and SFPUC oversees the compliance with the requirements of these documents. If a project requires federal permits or approvals, NRLMD works with the federal lead agency to prepare any required National Environmental Policy Act documents.

SFPUC environmental permitting and compliance efforts include reviewing and preparing documentation pursuant to the California Environmental Quality Act; and obtaining routine maintenance agreements and lake and streambed alteration agreements with the California Department of Fish and Wildlife; permits for compliance with Sections 401, 402, and 404 of the Clean Water Act; California Air Resources Board (CARB) permits; compliance with hazardous materials regulations; and federal special use permits with the NPS, USFS, and the Bureau of Land Management.

SFPUC regularly evaluates environmental compliance procedures and protocols to streamline processes and ensure that they are consistent across the system. Environmental compliance for O&M activities is documented through Maximo, in coordination with HHWP and WSTD maintenance planning teams, and the Project Review process; larger projects maintain separate project-specific records of environmental compliance.

SFPUC's environmental regulatory compliance includes the fulfillment of the mitigation commitments from WSIP. These WSIP commitments include monitoring and maintenance of the Bioregional Habitat Restoration (BHR) projects; permit-required releases and bypass flows to benefit aquatic species below SFPUC dams and diversion structures; and ecological monitoring in Alameda and San Mateo creeks. The BHR includes approximately 2,000 acres of lands set aside in perpetuity on the Alameda and Peninsula watersheds that must be maintained and monitored to meet specific environmental performance measures. Support for the BHR effort was initially funded by WSIP bond funds; in recent years, this has been increasingly supplemented by CIP bond and programmatic funds. WSIP permits require that the BHR sites be protected, monitored, and maintained in perpetuity.

5.2.1 National Pollutant Discharge Elimination System Permit Compliance

In 2016, the NPDES statewide drinking water discharges permit (NPDES permit number CAG140001) went into effect, and SFPUC received coverage on January 20, 2016. This permit replaced the individual permit for the Pulgas Dechloramination Facility, and the General NPDES permit for surface water treatment facilities. Coverage under this statewide permit is comprehensive, because it includes chlorinated drinking water as well as groundwater, and spans the entire RWS from Hetch Hetchy to CCSF's county line. Also in 2016, filter backwash discharges at HTWTP were covered under a new NPDES permit (NPDES permit number CAG382001). In 2021, this NPDES permit was reissued, and it continues to provide coverage for filter backwash discharges at HTWTP. SFPUC continues to receive coverage for discharges of aquatic pesticides (i.e., algaecides) into drinking water reservoirs under the general aquatic pesticide application permit (NPDES permit CA990005). The NPDES statewide drinking water discharge permit that was adopted in 2016 has not been reissued and continues to provide coverage for SFPUC operations. The SFPUC NPDES permit coverage is provided by these three NPDES permits, and SFPUC continues to work with the state and regional boards to meet permit requirements and minimize impacts to receiving waters. The RWS was in compliance with NPDES permits (there were no violations in FY23 and FY24).

5.2.2 California Unified Program Compliance (Hazardous Waste and Materials)

The Unified Hazardous Waste and Hazardous Materials Management Regulatory Program (Unified Program) was established in 1993 to protect public health and safety, and to restore and enhance environmental quality. The Unified Program is overseen by the California Environmental Protection Agency (CalEPA), coordinating with partner state agencies to ensure consistency and to set program standards established by Cal OES, the Department of Toxic Substances Control, the Office of the State Fire Marshal, SWRCB, and CalEPA. The Unified Program organizes the administration and activities of six programs:

- 1. Aboveground Petroleum Storage Act Program
- 2. California Accidental Release Prevention Program
- 3. Hazardous Materials Business Plan Program
- 4. Hazardous Materials Management and Inventory Program (Generator Program)
- 5. Hazardous Waste and Hazardous Waste Treatment Program (Tiered Permitting)
- 6. Underground Storage Tank Program

Water treatment plants are overseen by the following programs: Aboveground Petroleum Storage Act (Table 5-1), California Accidental Release Prevention Program (Table 5-2), and Hazardous Generator or Hazardous Material Business Plan Program (Table 5-3). Most of the pump stations, valve lots, and smaller facilities are overseen by the Hazardous Materials Business Plan Program, Hazardous Waste Generator Program, and Underground Storage Tank Program. Table 5-4 shows the various facilities and the different programs responsible for oversight of the facilities.

Facility Name	Last Revised
Early Intake	2021
Moccasin	2021
Warnerville	2022
Baden Pump Station	2024
Harry Tracy Water Treatment Plant	2023
San Antonio Pump Station/Sunol Valley Chloramination Facility	2023
Santa Clara Valley Intertie Pump Station	2023
Sunol Valley Water Treatment Plant	2022
Tesla Treatment Facility	2023
Millbrae Yard	2022
Sunol Corporation Yard	2023

Table 5-1: Facilities in the Aboveground Storage Tank Program

Table 5-2: Facilities in the California Accidental Release Prevention Program

Facility Name	Last Revised
Harry Tracy Water Treatment Plant	2021
San Antonio Pump Station/Sunol Valley Chloramination Facility	2023
Sunol Valley Water Treatment Plant	2023

Table 5-3: Facilities in the Hazardous Generator and Hazardous Material Business Plan Program

Facility Name	Last Revised
O'Shaughnessy	2021
Cherry Valley Compound	2021
Early Intake	2021
South Fork Maintenance Yard	2022
Moccasin	2021
Rock River Lime Plant	2022
Warnerville	2022
Alameda Creek Diversion Dam Fish Passage Facility	2024
Alameda East Portal	2024
Alameda West Portal	2024
Baden Pump Station	2024
Bear Gulch Crossover Facility	2024
Calaveras Oxygenation Facility	2024
Calaveras Valve Lot	2024
Casey Quarry	2024
Crystal Springs Bypass Tunnel and Shaft	2024
Crystal Springs Pump Station	2024
Crystal Springs Pump Station Substation	2024
F Street Well and Treatment Facility	2024
Guadalupe Crossover	2024
Harry Tracy Water Treatment Plant	2024
Irvington Portal	2024
Millbrae Maintenance Yard	2024
Millbrae Yard Well and Treatment Facility	2024
Mt. Alviso Valve Lot	2024
Newark Control Building	2024
Palo Alto (Barron) Valve Lot	2024
Polhemus Fluoride Station	2024
Pulgas Dechloramination Facility and Pump Station	2024
Pulgas Valve Lot	2024
Ravenswood Control Building	2024
San Antonio Oxygenation Facility	2024
San Pedro Valve Lot	2024
Sawyer Ridge Radio Station	2024
SFPUC-Valley Water Intertie Pump Station	2024
Sunol Corporation Yard	2024
Sunol Fire Pump Station	2024
Sunol Valley Chloramination Facility/San Antonio Pump Station	2024
Sunol Valley Water Treatment Plant	2024
Tesla Treatment Facility	2024
Thomas Shaft Facility	2024

Note:

SFPUC = San Francisco Public Utilities Commission

Type of Program in the Unified Program	Number of Facilities in the Program
Aboveground Petroleum Storage Act Program	11
California Accidental Release Prevention Program	3
Hazardous Materials Business Plan Program	34
Hazardous Materials Management and Inventory Program (Generator Program)	8
Hazardous Waste and Hazardous Waste Treatment Program (Tiered Permitting)	2
Underground Storage Tank Program	1

Table 5-4: Number of SFPUC Division Facilities Enrolled in the Unified Program

Note:

SFPUC = San Francisco Public Utilities Commission

Certified Unified Program Agencies implement the Unified program at the local level by consolidating and coordinating administrative requirements, permits, inspections, and enforcement activities for the six programs. Depending on the location of the facility, the Certified Unified Program Agencies for WSTD include San Joaquin County Department of Environmental Health, Alameda Department of Environmental Health, Santa Clara Department of Environmental Health, City of Sunnyvale, and San Mateo Environmental Health Services.

WSTD facilities either carry hazardous materials over a certain threshold or generate hazardous waste, which puts these facilities under the Unified Program. For example, hazardous materials at some of the WSTD facilities include aqua ammonia, ammonium sulfate, fluoride, sodium bisulfite, sodium hydroxide, petroleum products, and cylinders of gases (i.e., oxygen, argon, carbon dioxide, and nitrogen). Hazardous materials at pump stations and valve lots may include propane or diesel generators. Hazardous waste generated at the pump stations and valve lots include the used oil from the generators. The goal of the Unified Program is to protect lives, property, and the environment by reducing the factors that contribute to emergencies associated with hazardous materials.

WSTD complies with the Unified Program to protect the staff, customers, community, and environment from adverse effects as a result of the storage or possible release of hazardous materials and waste. This is done primarily by documenting significant amounts of hazardous materials so that emergency responders can effectively protect the public. WSTD continuously updates their plans to ensure regulatory compliance with the Unified Program by working with the local Certified Unified Program Agencies.

Similarly, HHWP continuously updates their plans to ensure regulatory compliance with the Unified Program. HHWP must maintain various permits/plans/procedures for their operations, including wastewater permits, discharge permits, Stormwater Pollution Prevention Plans, and Hazardous Materials Business Plans. Permitting is current and up to date. All hazardous material/waste permits are captured in California's Environmental Reporting System. CalEPA oversees California's Unified Program. The Unified Program is a consolidation of multiple environmental and emergency management programs. Under the Clean Water Act, U.S. EPA

authorizes the NPDES permit program to state, tribal, and territorial governments, enabling them to perform many of the permitting, administrative, and enforcement aspects of the NPDES program. California is authorized to implement Clean Water Act programs through SWRCB; CalEPA retains oversight responsibilities over SWRCB, which administers wastewater and stormwater discharge permits. HHWP also maintains small water systems permits and operations plans for facilities at Moccasin, Early Intake, O'Shaughnessy, and Cherry Valley.

A comprehensive list SFPUC program plans for can be found in Appendix B, Table B-2. EAPs maintained by SFPUC can be found in Appendix B, Table B-2.

5.3 State of California Division of Safety on Dams

DSOD has jurisdiction over 12 dams that are operated and maintained by HHWP and WSTD within SFPUC's WE. The dams that are regulated by DSOD include:

O'Shaughnessy Dam	Calaveras Dam
Lake Eleanor Dam	Turner Dam
Cherry Valley Dam	Pilarcitos Dam
Early Intake Dam	Upper and Lower Crystal Springs Dams
Priest Dam	San Andreas Dam
Moccasin Dam	

DSOD categorizes the condition of each of these dams within its jurisdiction as either Satisfactory, Fair, Poor, Unsatisfactory, or Not Rated.

- **Satisfactory.** No existing or potential dam safety deficiencies are recognized. Acceptable performance is expected under all loading conditions (static, hydrologic, and seismic), in accordance with the applicable regulatory criteria or tolerable risk guidelines.
- **Fair.** No existing dam safety deficiencies are recognized for normal loading conditions. Rare or extreme hydrologic and/or seismic events may result in a dam safety deficiency. Risk may be in the range to take further action. Additional DSOD criteria may include:
 - The dam has a long-standing deficiency that is not being addressed in a timely manner.
 - The dam is not certified and its safety is under evaluation.
 - The dam is restricted and operation of the reservoir at the lower level does not mitigate.
- **Poor.** A dam safety deficiency is recognized for loading conditions that may realistically occur. Remedial action is necessary. A poor rating may also be used when uncertainties exist regarding critical analysis parameters that identify a potential dam safety deficiency. Further investigations and studies are necessary. Additional DSOD criteria can include the following:
 - The dam has multiple deficiencies or a significant deficiency that requires extensive remedial work.

- **Unsatisfactory.** A dam safety deficiency is recognized that requires immediate or emergency remedial action for problem resolution.
- Not Rated. The dam has not been inspected, is not under state jurisdiction, or has been inspected but, for whatever reason, has not been rated.

WE has identified the need for capital improvements on its dams and continues to work closely with DSOD on the scope and schedule for these investments. As reported in the previous SRWS Report, SFPUC delivered to DSOD a conceptual plan for implementing known dam safety projects over the next 15 years, the 15-Year Dam Safety Plan. DSOD has reviewed and responded favorably to the conceptual plan. SFPUC continues to make progress on the dam safety projects that are currently authorized under the existing 10-Year CIP.

In addition to the large capital projects that were identified in the 15-year Dam Safety Plan, WE manages a thorough dam safety program that includes inspection, surveillance, and monitoring tasks for each of its facilities. This program is executed by a diverse set of dam safety professionals, including engineers, watershed keepers, hydrologists, and other technical staff.

5.3.1 Dam Safety Program

The Dam Safety Program includes: 1) field inspection and monitoring activities; 2) valve exercising; and 3) vegetation management.

5.3.1.1 Field Inspections and Monitoring

Field inspections consist of routine inspections, formal annual inspections, and episodic inspections, accompanied by engineering surveys following seismic events of specified magnitude.

Routine inspections are conducted by SFPUC staff, including engineering survey crews and watershed keepers. Staff record readings on piezometers and seepage drains, and also perform routine visual inspection of spillways and appurtenances. The survey crew conducts a routine dam displacement survey on monuments for vertical and horizontal movements.

Annual inspections are conducted by the DSOD inspector, together with the SFPUC inspection team. DSOD inspects the upstream and downstream face of the dam, the crest and toe areas of the dam, groins, seepage points, spillways, spillway basins, outlet structures, tunnels, valves, piping, and metalwork. The DSOD inspector typically observes the exercising of outlet valves once every 3 to 5 years. DSOD issues a written report to SFPUC after each annual inspection to summarize their findings and recommendations. As part of their annual report, DSOD reviews monitoring data, such as piezometers, deflection and settlement surveys, and seepage monitoring. Annual inspections were performed by DSOD in FY23 and FY24.

At HHWP, monitoring data are collected manually during the routine monthly inspection and the bi-annual engineering survey. At WSTD, monitoring data are collected through both manual reading on site and through dataloggers with data transmitted to the office. The monitoring data include piezometer readings, seepage flows, survey readings, reservoir levels, and rainfall information. Piezometer readings, reservoir levels, and rainfall data are plotted over a 10-year period to identify trends. Piezometer readings, which represent water pressure, are labeled on

Section 5 – Regulatory Compliance 2024 State of the Regional Water System Report

each dam cross-section to illustrate the internal phreatic surface. Survey readings that show horizontal and vertical movement are summarized in a tabular format with a 10-year history. Monitoring data are a central element in the reports submitted to DSOD each year. Maintenance and repair consist of annual flushing of piezometer piping and DSOD annual inspection recommendation follow-ups. DSOD annual inspection recommendation follow-ups generally consist of vegetation clearing, rodent control, minor spillway repair, and repair of seepage measuring devices. These activities are included in the operating budget. Inspections and engineering surveys are required following an earthquake, depending on the magnitude of the earthquake and its proximity to the dam. For WSTD, the inspection and survey criteria are specified in the EAPs for each dam. These surveys are conducted immediately or during the next available daylight period. The EAPs are required by law to be updated annually or whenever changes are made. For HHWP, criteria are specified in HHWP's Earthquake Notification Procedure. No earthquakes triggering surveying have been experienced on the HHWP project recently.

5.3.1.2 <u>Maintenance – Valve Exercising</u>

WSTD's valve exercising program requires exercising adit and emergency release valves for each dam once per year. Every 3 to 5 years, DSOD inspectors, along with a WSTD engineer and inspector, will need to witness the valve exercising for each dam. A wet test with all the valves fully opened and closed is preferred. When environmental restrictions prevent the full release of water downstream (as was the case for Turner Dam and LCSD), a dry test will be done by opening and closing the emergency release valves with the adit valves and line-valves closed (thus not allowing any water to go downstream). After testing, the emergency release valve is then closed, and the adit valves and line valves are opened and closed.

HHWP's program requires exercising the release valves for each dam once per year. This activity is scheduled in Maximo and performed by the watershed keepers. At least once every 3 years, DSOD inspectors, along with a HHWP engineer and inspector, witness the valve exercising for each dam. Though a wet test with all the valves opened is preferred, a dry test will be done (not allowing any water to go downstream) during dry hydrologic conditions. Valve exercising tasks for each dam are summarized in Section 4.

5.3.1.3 <u>Maintenance – Vegetation Management</u>

SFPUC and DSOD inspections regularly trigger vegetation and rodent clearance work along dams and spillways. Work is transmitted to the maintenance crews for completion either by memorandum from the engineering section (WSTD) or by Maximo work order (HHWP). Vegetation work completed is summarized for each dam in Section 4.

5.3.2 DSOD Inspections

During this reporting cycle, DSOD performed joint inspections with WE staff at multiple dams. This section summarizes the dates of the inspections, the current DSOD condition category, and a brief description of the findings of the inspection for each of the dams.

Section 5 – Regulatory Compliance

2024 State of the Regional Water System Report

5.3.2.1 O'Shaughnessy Dam

DSOD categorizes the condition of O'Shaughnessy Dam as "Satisfactory." HHWP personnel performed joint inspections with DSOD at O'Shaughnessy Dam on June 1, 2023; and June 25, 2024. Inspections confirmed the current condition rating of the dam. Some minor maintenance items were identified and have been addressed. All valves and drum gates were operated in accordance with DSOD's requirements.

5.3.2.2 <u>Cherry Valley Dam</u>

DSOD categorizes the condition of Cherry Valley Dam as "Fair" due to spillway capacity limitations. HHWP personnel performed joint inspections with DSOD on June 1, 2023; and June 24, 2024. Inspections confirmed the current condition rating of the dam. All valves were operated in accordance with DSOD's requirements.

The rating will be increased from "Fair" to "Satisfactory" when the spillway is improved to pass the PMF with the required freeboard. This project was a candidate capital project in 2023 and will be included again as a candidate capital project request in 2025.

5.3.2.3 <u>Eleanor Dam</u>

DSOD categorizes the condition of Eleanor Dam as "Satisfactory." HHWP personnel performed joint inspections with DSOD on June 1, 2023; and June 24, 2024. Inspections confirmed the current condition rating of the dam. DSOD requested repair of the spillway bays, diversion wall, and some minor repairs to the upstream right abutment contact. The spillway bays were repaired in 2023 and 2024, and further work is scheduled for fall 2024. All valves were operated in accordance with DSOD's requirements.

5.3.2.4 Priest Dam

DSOD categorizes the condition of Priest Dam as "Satisfactory." HHWP personnel performed joint inspections with DSOD on June 19, 2023; and June 25, 2024. Inspections confirmed the current condition rating of the dam. DSOD provided positive comments regarding the two new standardized weirs and cutoff walls installed in 2021, which improves the ability to monitor leakage from the dam and low-level outlet tunnel. All valves were operated in accordance with DSOD's requirements.

5.3.2.5 <u>Moccasin Dam</u>

DSOD categorizes the condition rating of Moccasin Dam as "Fair" due to spillway capacity limitations. HHWP personnel performed joint inspections with DSOD on January 19, 2023; and June 25, 2024. Inspections confirmed the current condition rating of the dam. All valves were operated in accordance with DSOD's requirements.

The rating will be increased from "Fair" to "Satisfactory" following completion of the Moccasin Dam and Reservoir Long-Term Improvements project, when the auxiliary is improved to pass the design PMF.

Section 5 – Regulatory Compliance

2024 State of the Regional Water System Report

5.3.2.6 Early Intake Dam

DSOD categorizes the condition of Early Intake Dam as "Fair" due to the condition of the dam's concrete. HHWP personnel performed joint inspections with DSOD at Early Intake Dam on January 19, 2023; and June 24, 2024. Inspections confirmed the current condition rating of the dam. The Early Intake Dam, Long-Term project will address deficiencies of the dam.

5.3.2.7 <u>Calaveras Dam</u>

DSOD categorizes the condition of Calaveras Dam as "Satisfactory." WSTD personnel performed joint inspections with DSOD at Calaveras Dam on October 25, 2022; February 10, 2023; January 26, 2024. This included exercising valves and performing visual inspections of the dam, spillway, and outlet structure. Inspections went well, confirming the satisfactory condition of the dam; however, some maintenance items, such as minor crack repairs, seepage, and erosion caused by the 2022/2023 winter storm were identified. Maintenance items are being addressed in FY23 and FY24.

5.3.2.8 <u>Turner Dam</u>

DSOD categorizes the condition of Turner Dam as "Satisfactory." WSTD personnel performed joint inspections with DSOD at Turner Dam on December 6, 2022, and January 26, 2024. This included exercising valves and performing visual inspections of the dam, spillway, and outlet structure. Inspections went well, confirming the satisfactory condition of the dam. Maintenance items identified in the inspections include removal of minor emergent vegetation and resolving two upstream outlet valves that failed to open. All the maintenance items have been addressed.

5.3.2.9 Lower Crystal Springs Dam

DSOD categorizes the condition of LCSD as "Satisfactory." WSTD personnel performed joint inspections with DSOD at LCSD on November 2, 2022; and January 18, 2024. This included exercising valves and performing visual inspections of the dam, spillway, and outlet structure. Inspections went well, confirming the satisfactory condition of the dam; however, maintenance issues such as removing a fallen tree and realigning a waterstop between metal plates atop the stilling basin wall were identified and are being addressed.

5.3.2.10 San Andreas Dam

DSOD categorizes the condition of San Andreas Dam as "Fair," due to major deficiencies in the spillway. WSTD personnel performed joint inspections with DSOD at San Andreas Dam on November 2, 2022; and January 18, 2024. This included exercising valves and performing visual inspections of the dam, spillway, and outlet towers. The spillway requires major upgrades, and a dedicated outlet structure is required. Both are included in the CIP program. During inspection, rodent holes and emerging vegetation on the upstream slope were observed; these issues are being addressed.

5.3.2.11 Pilarcitos Dam

DSOD categorizes the condition of Pilarcitos Dam as "Satisfactory." WSTD personnel performed joint inspections with DSOD at Pilarcitos Dam on November 2, 2022; and January 18, 2024. This included exercising valves and performing visual inspections of the dam, spillway, and outlet towers. Inspections went well, confirming the satisfactory condition of the dam; however, some

maintenance items such as rodent holes and vegetation were identified. These issues are being addressed.

5.4 America's Water Infrastructure Act

SFPUC will conduct a risk and resilience assessment (RRA), as required by the America's Water Infrastructure Act of 2018 (AWIA). In October 2018, the AWIA was signed into law, requiring water utilities serving more than 3,300 persons to conduct an RRA and update their ERP, based on specific criteria outlined in the Act. The compliance deadline for SFPUC to complete their RRA is March 31, 2025; the ERP is due September 30, 2025. SFPUC will meet target deadlines for the RRA and ERP, as they did in the last cycle.

Pursuant to the AWIA requirements, SFPUC's RRA will evaluate:

- risks to the system from malevolent acts and natural hazards; and
- resilience of system components, in consideration of monitoring practices, financial infrastructure, chemical storage and handling, and O&M.

The RRA will be completed using a methodical process based on the AWWA J100 methodology:

- Asset Characterization. A list will be established of SFPUC's critical assets that, if compromised, could result in service interruption. Assets included the various source water, treatment, distribution, storage, and cyber assets associated with the drinking water system. AWIA applies only to drinking water systems; therefore, the wastewater and stormwater assets will not be included in this effort.
- Threat Characterization. A set of hazard scenarios will be identified, taking an all-hazards approach as required by AWIA, to evaluate credible threats to SFPUC. The threats will include major earthquake, flood, wildfire, power outage, physical assault, water quality contamination, cyber-attack, and resource interruption.
- **Consequence Analysis.** AWIA COF will be identified for identified assets.
- **Vulnerability and Threat Analysis.** The probability of failure will be estimated for threatasset pairs developed from the asset and threat characterizations.
- **Risk and Resilience Analysis.** The results will be combined into an estimated risk analysis for identified and evaluated threat-asset pairs.

SFPUC is required to review, revise, and submit a recertification of the RRA every 5 years.

5.5 Federal and State Power Regulations

5.5.1 North American Electric Reliability Corporation/Western Electricity Coordinating Council

The North American Electric Reliability Corporation (NERC) is the Federal Energy Regulatory Commission-approved authority that develops and enforces reliability standards for the North

Section 5 – Regulatory Compliance 2024 State of the Regional Water System Report

American bulk electric system. SFPUC owns power generation and transmission assets that fall under the jurisdiction of NERC's Compliance Monitoring and Enforcement Program. NERC works hand in glove with regional Compliance Enforcement Authorities (CEA) to ensure bulk electric system reliability. The Western Electricity Coordinating Council (WECC), the Western Interconnection's CEA, has been delegated the authority to enforce NERC's Reliability Standards, accomplishing this via a compliance monitoring process that includes compliance audits, self-certifications, spot checks, compliance investigations, self-reports, self-logging, periodic data submittals, preliminary screening, and investigating complaints that allege violations of the reliability standards. HHWP is the SFPUC division responsible for ensuring compliance with these regulatory activities.

- Enforcement Actions: Two operations and planning (O&P)-related enforcement actions that were self-reported in 2020 and 2021, and two critical infrastructure protection-related enforcement actions that were self-reported in 2023, remain open. WECC Enforcement previously indicated that resolution of one of the self-reports would be handled during the 2023 WECC compliance audit. However, prior to the audit, WECC removed the requirement associated with HHWP's 2020 enforcement action from the audit scope. Accordingly, this enforcement action remains open. On June 28, 2024, WECC granted HHWP a compliance exception for the 2020 FAC-008 facilities ratings violation found during the 2020 WECC audit. With respect to the remaining open enforcement actions, no additional mitigation actions have been required.
- WECC Compliance Audit: HHWP's last WECC compliance audit was conducted in June 2023. The audit scope included 14 requirements from four critical infrastructure protection and five O&P reliability standards. The audit concluded with no findings, one recommendation, and two positive observations. SFPUC has completed the implementation of the recommendation. SFPUC's next WECC audit is anticipated to be during calendar year 2026.
- Self-Certification: SFPUC was not required to self-certify in 2022 for calendar year 2021. In December 2023, SFPUC was notified by WECC that HHWP would not be required to complete the annual WECC self-certification process for the 2023 calendar year. Accordingly, SFPUC did not self-certify to any O&P or critical infrastructure protection reliability requirements related to calendar year 2023. However, WECC could request that SFPUC perform a guided self-certification at some point during calendar year 2024 because each quarter WECC selects entities to complete a self-certification.
- Self-Logging: HHWP applied for WECC's self-logging program and received WECC approval to participate in the program in March 2024. The self-logging program is reserved for registered entities distinguished for their demonstrated ability to identify, assess, and correct minimal-risk issues of noncompliance. The program allows SFPUC to report low-risk noncompliance issues; in turn, SFPUC receives expedited review and resolution of the issue. HHWP made its first self-log for a low-risk PRC-019 violation in May 2024.

2024 State of the Regional Water System Report

5.5.2 Federal Energy Regulatory Commission

5.5.2.1 Scope and Jurisdiction

The Federal Energy Regulatory Commission (FERC) has regulatory jurisdiction over the operation of HHWP's Moccasin Lowhead Powerhouse. This facility does not fall under the NERC/WECC reliability standards. HHWP is required to provide documentation and facilitate inspections to maintain FERC compliance.

5.5.2.2 Status and Updates

During this reporting cycle, Moccasin Lowhead Powerhouse has been out of service. A flood on Moccasin Creek damaged the powerhouse, resulting in ongoing remediation since 2018. The powerhouse is projected to be returned to service sometime during March 2025.

5.5.3 Wildfire Mitigation Plan

California Senate Bill (SB) 901 (2018), amended Public Utilities Code (PUC) § 8387, Chapter 6, Wildfire Mitigation. PUC section 8387 (b)(1) requires that "the local publicly owned electric utility or electrical cooperative shall, before January 1, 2020, prepare a wildfire mitigation plan (WMP). After January 1, 2020, a local publicly owned electric utility or electrical cooperative shall annually prepare a WMP. It shall submit the plan to the California Wildfire Safety Advisory Board (WSAB) on or before July 1 of that calendar year. Each local publicly owned electric utility and electrical cooperative shall update its plan annually and submit the update to the WSAB by July 1 of each year. At least once every 3 years, the submission shall be a comprehensive revision of the plan."

SFPUC's WMP is built on the following primary objectives:

- 1. **Minimizing Sources of Ignition.** SFPUC continues to evaluate prudent and cost-effective improvements to its physical assets, operations, and training to minimize the risk of its facilities being the origin or contributing source of a catastrophic wildfire. These programs include, but are not limited to, implementation of fire risk analysis tools to assess the risk and consequence of a potential ignition; strategic grid hardening, such as replacing high-risk equipment on distribution poles; an increase in situational awareness capabilities, achieved by adding more strategically placed weather stations; and proactive deenergization of lines during critical fire weather conditions. SFPUC will continue to implement additional recommendations over time through WMP evaluation and continuous improvement.
- 2. Grid Reliability and Resiliency. The second objective is to improve the reliability and resiliency of SFPUC-owned and operated electric grid. In addition to reducing wildfire ignition risks, programs such as grid hardening and enhanced vegetation management provide additional benefits, including improved reliability and resiliency. SFPUC will continue to assess industry best practices and new technologies that could help reduce the likelihood of a disruption in service due to planned or unplanned events; and expedite grid recovery efforts following a significant event, such as a fire.

3. **Measurement of Effectiveness and Performance.** The third objective of SFPUC's WMP is to measure the effectiveness and performance of SFPUC's specific wildfire mitigation strategies. SFPUC will monitor the performance – e.g., the increased rate of equipment failures or vegetation contacts. Based on performance, SFPUC will modify their program to continuously improve the safety, reliability, and resiliency of their equipment.

The 2023 and 2024 WMPs were submitted to the WSAB before the regulatory deadline of July 1 of that calendar year. This update includes the following accomplishments made in 2023.

- 1. HHWP began using a drone for additional inspections of distribution line power poles.
- 2. Distribution pole construction standards were updated to replace old cross arms and poles with composite or fiberglass.
- 3. Distribution pole construction standards were updated to add increased avian protection.
- 4. Satellite vegetation monitoring is now being used to supplement annual Light Detection and Ranging (LiDAR) flights.
- 5. NRLM supported the California Department of Forestry and Fire Protection in performing more than 80 acres of controlled burns in the SFPUC watershed.
- 6. A comprehensive audit was completed to ensure that all transmission, distribution, and substations assets are documented in Maximo.

5.5.4 Physical Security Mitigation Plan

On January 10, 2019, the California Public Utilities Commission issued Decision 19-01-018 (Decision), requiring electrical utilities—including publicly owned utilities such as SFPUC—to identify electric distribution infrastructure subject to the Decision (Covered Distribution Facilities or CDFs), assess the potential risks associated with a physical attack on CDFs, and prepare a risk mitigation plan.

The Decision requires evaluation of the following elements of the existing design and operations of a CDF, and identification of the potential risks associated with a physical attack:

- existing power system resiliency and/or redundancy solutions (e.g., identifying other facilities capable of serving the load, temporary circuit ties, mobile generation, and/or storage solutions);
- availability of spare assets to restore a particular load;
- existing physical security protections to reasonably address the risk;
- potential for emergency responders to identify and respond to an attack in a timely manner;
- location and physical surroundings, including proximity to gas pipelines and geographical challenges and impacts of weather;

- history of criminal activity at the facilities in the area;
- availability of other sources of energy to serve the load (e.g., customer-owned backup generation or storage solutions); and
- availability of alternative ways to meet health, safety, or security needs.

SFPUC prepared a Physical Security Mitigation Plan (PSMP) for applicable CDFs. In accordance with the Decision, SFPUC appointed the Executive Director of the San Francisco Department of Emergency Management to act as the *qualified authority* to review the PSMP. The final PSMP incorporates recommendations from the qualified authority. The latest PSMP was submitted to the California Public Utilities Commission on June 14, 2022, and SFPUC will review and update the PSMP every 5 years.

6. Emerging Issues

There are several emerging issues that will impact WE over the next reporting cycle. Some issues are general and are a result of the economy and responding to a change in workforce culture. However, WE must also respond to changes in local, state, and federal laws. This section will discuss emerging issues that will be addressed during the next reporting cycle. The section is organized into two subsections: 6.1, General; and 6.2, Water Quality.

6.1 General

This section will include a discussion of:

- Transitioning to a cleaner utility
- Obsolete equipment/technology
- U.S. EPA Cyber Security

6.1.1 Transitioning to a Cleaner Utility

WE is committed to transitioning to a cleaner utility. Two entities have passed regulations and/or initiatives to ensure that this transition becomes reality. The first is CARB, which is the lead state agency for climate change programs and oversees all air pollution control efforts in California to attain and maintain health-based air quality standards. CARB's regulatory efforts include regulation aimed at cleaning up off-road construction equipment (heavy equipment) and moving toward zero emission small-engine equipment. In addition, the SFBOS has amended existing Administrative and Environmental Codes to require that any new passenger vehicles in the CCSF fleet be zero emission. This section describes status and challenges.

Heavy Equipment. Both HHWP and WSTD operating divisions rely on heavy equipment for their daily operations. Examples of heavy equipment include rollers, tractors, backhoes, dozers, graders, loaders, excavators, forklifts, crane trucks, sewage pumper trucks, and dump trucks. In FY22-23 and FY23-24, both divisions encountered significant increases in equipment cost compared to budgeted amounts. For example, many items cost almost double the projected price. In addition, suppliers were not honoring contract pricing due to supply chain issues and the impacts of high inflation. Due to insufficient funding and availability of equipment, the two divisions fell short of their heavy equipment purchasing goals. WE will continue to coordinate with SFPUC Finance and executive management to overcome current challenges. Temporary solutions include leasing equipment; however, equipment essential for wildfire mitigation work is not available for lease, given that this equipment is in high demand. WE anticipates that the purchase of CARB-compliant equipment will continue to present challenges, both in terms of funding and availability, for the foreseeable future.

Small Engine Equipment. CARB was directed to ban the sales of gas-powered small off-road engines and spark-ignited engines rated at, or below, 25 horsepower. CARB regulations went into effect on January 1, 2024. Examples of equipment used by the WE that falls under this regulation include smaller chainsaws, edgers, lawn mowers, leaf blowers, portable generators, pressure washers, riding mowers, and string trimmers. This transition effort was not funded in our operating budget, and equipment will be replaced as it is retired. WE is still challenged with

Section 6 – Emerging Issues and Concerns 2024 State of the Regional Water System Report

battery life (about 1 hour) and the daily use of about 6 hours a day when staff are working in remote areas. WE also needs to overcome challenges with charging a large number of batteries on a daily basis. WE will continue to address these challenges but anticipates completing the equipment conversion before 2030.

Conversion to Zero Emission Initiatives. As stated in the 2022 SRWS, the SFBOS approved ordinance 115-17, amending the existing Administrative and Environmental Codes to require any new passenger vehicles procured for the CCSF fleet to be zero-emission vehicles. Over the last 2 years, WE expanded their EV passenger fleet and is in the process of improving access to EV charging stations. In the Bay Area, WE added several EV charging stations at Millbrae and is in the process of adding EV charging stations at Rollins Road. The long-term buildout of EV charging infrastructure is being planned under the Millbrae Campus project. EV charging stations are in the planning process at HHWP.

6.1.2 Obsolete Equipment/Technology

The water industry is adapting to technological advances occurring at a fast pace. We are in a transition from the Third Industrial Revolution, defined by the development of digital technology, electronics, automation, and information technology, to the Fourth Industrial Revolution, with integration of cyber-physical systems, the Internet of Things, and artificial intelligence dominating the new phase of the industrial revolutions. Although digital technology and automation have enhanced the detection of problems in the operation of the RWS, there are negative impacts, one of which is impacting WSTD's operations more and more in recent years. In the last 15+ years, WSTD embraced automation and the increased use of electronics in the operation of various water treatment and conveyance facilities. These instruments serve to protect assets and provide instantaneous feedback to the operators who are centrally located at HTWTP and SVWTP but monitor and operate the Bay Area RWS facilities that go from San Joaquin County – through Alameda, Santa Clara, and San Mateo counties – to San Francisco. For example, thermal and current sensors have been installed that will shut down the motors before the pumps and motors are damaged for overheating or overcurrent. Instrumentation is widely used to measure various residuals, tank levels, flow rates, temperature, conductivity, etc., throughout the RWS.

Automation and the use of electronics have reduced the number of staff who have to be located at treatment facilities other than HTWTP and SVWTP. However, with rapid technological advances, instruments and equipment that rely on electronics are far more susceptible to equipment obsolescence. Models that used to be serviceable for 30+ years are now phased out in 10 years or less, with manufacturers notifying customers that parts will no longer be available and that services not supported for the older models. Some of the more costly equipment falling into this category include pump controllers; VFDs; magnetic and ultrasonic flowmeters; automatic transfer switches; UV light treatment units; flywheel UPSs; and building control systems such as the HVAC system at the Sunol Yard.

To mitigate such impacts, WSTD has started to increase R&R and capital budgets. WSTD is only in the beginning stages of doing this and will need to right-size the R&R and capital budgets to account for the replacement of obsolete electrical and electronic equipment. WSTD will also need to increase the number of people who will be responsible for replacing the lower cost assets, while

Section 6 – Emerging Issues and Concerns 2024 State of the Regional Water System Report

working with Infrastructure to replace higher-cost assets and assets that are not simple swapouts. Assets such as the flywheel UPS units at Tesla are not only costly to replace, estimated at \$2.5 to \$3 million for the UPS units alone, but their replacement would involve other equipment that interacts with the flywheel UPS units and the controls. WSTD is also working on using CMMS to track electrical and electronic instruments and equipment that are known to have a short lifespan. The latter will be initiated at WSTD once the asset registry is updated to include all WSIP assets. The update is expected to be completed by the end of 2024 or early 2025. HHWP's and WSTD's electricians and electronic maintenance technicians have also been turning to eBay for parts no longer available through the manufacturers to maintain obsolete equipment.

A related issue that has the same effect as obsolete equipment is that equipment is increasingly not built to last. This is also true of mechanical equipment such as pumps and valves. For this issue, WSTD uses the same mitigation measures used for technology obsolescence: increasing funding and staffing. An additional mitigation measure that will be implemented is to add lead time to procure replacement equipment. Lead times to procure specialized equipment used in water treatment and conveyance increased during the pandemic, and this has persisted even though such issues have been resolved for common goods.

What started as an emerging issue in the 2022 report is confirmed to be an ongoing issue that is here to stay and must be addressed by gearing up funding, projects, and staffing.

6.1.3 U.S. EPA Cyber Security

U.S. EPA is the sector risk management agency charged with ensuring that the water sector is prepared for any hazard, including cyber risks. Drinking water and wastewater systems are an attractive target for cyberattacks because they are a lifeline-critical infrastructure sector but often lack the resources and technical capacity to adopt rigorous cybersecurity practices. Disabling cyberattacks are striking water and wastewater systems throughout the United States.

U.S. EPA is developing cybersecurity standards for the water industry, but because of current risks, they are now reaching out to states with recommended actions for all water and wastewater utilities. U.S. EPA has urged all utilities to implement the recommendations in the Cybersecurity and Infrastructure Security Agency (CISA) fact sheet, "Top Cyber Actions for Securing Water Systems." The fact sheet outlines practical actions that water and wastewater utilities can take to better protect water systems from malicious cyber activity. Additional information regarding the U.S. EPA development of standards is not available at this time.

Conducting a regular cybersecurity assessment is one of the recommendations. According to U.S. EPA, if a water or wastewater utility uses operational technology such as industrial control systems and SCADA systems for the production and distribution of safe water, then the adequacy of the cybersecurity of those systems should be evaluated.

SFPUC is beginning to self-assess the cybersecurity of water systems and related operational technology systems using the U.S. EPA water cybersecurity assessment tool. This tool is based on CISA's cybersecurity performance goals and poses a list of questions to help identify cybersecurity gaps. The goal of this work is to identify cybersecurity gaps and begin to resolve them to mitigate risks and prepare for eventual regulations from U.S. EPA. WE anticipates that

operating our network at a higher level of security will require investments into hardware and software systems as well as additional operational technology personnel.

6.2 Water Quality

SFPUC continues to monitor water quality issues. This section includes a discussion of:

- disinfection byproducts;
- T&O;
- PFAS;
- microplastics; and
- an update on the "Water Quality Strategic Plan"

6.2.1 Disinfection Byproducts

SFPUC notifies wholesale customers when elevated DBPs reach 80 percent of the drinking water standards (i.e., MCLs). This corresponds with wholesale customer notifications when total trihalomethanes (TTHM) reach 64 μ g/L or haloacetic acids (HAA5) reach 48 μ g/L at Irvington Portal or at HTWTP. These levels were exceeded at Irvington Portal on May 22, 2023, for HAA5; and on June 5, 2023, for TTHM, due to elevated precursors during a significant spring runoff period.

U.S. EPA's M/DBP Stage 3 proposal is due in summer of 2025. The National Drinking Water Advisory Council submitted recommended M/DBP rule changes to U.S. EPA in December 2023.

SFPUC participated in Water Research Foundation (WRF) project 5156 (Occurrence of *Legionella spp.* In Drinking Water Distribution Systems), with monitoring started in August 2022 and completed in 2022-23. This project was meant to inform the M/DBP Stage 3 proposal. SFPUC's Millbrae laboratory developed internal *Legionella* testing capability for the WRF project and ongoing monitoring.

6.2.2 Taste and Odor

In early December 2016, SFPUC received an unusually high number of T&O complaints from both retail and wholesale customers. The complaints were linked to an algal bloom in San Antonio Reservoir that was producing geosmin, a very common T&O compound. SFPUC has not experienced a major T&O event since 2016. In response to the 2016 event, SFPUC increased the routine T&O compound monitoring program at the SVWTP and initiated two treatment improvement projects for SVWTP: a PAC system and an ozone system. The PAC system construction was completed in December 2018, and it has been used on an as-needed basis depending on available source waters and algal blooms. The ozone project completed its design documents and a construction contract was awarded on May 14, 2024. Notice to Proceed for the ozone construction contract is projected to be issued on September 30, 2024. Although PAC provides T&O treatment improvements at SVWTP, ozone will provide additional treatment capabilities for removing more T&O compounds and will provide other water-quality benefits, such as DBP reductions. Future ozone treatment will be a valuable tool for optimizing water quality from the SVWTP during long Hetch Hetchy shutdowns.

6.2.3 PFAS

On April 26, 2024, U.S. EPA finalized the PFAS rule that included MCLs for five PFAS compounds (PFOA, PFOS, PFHxS, PFNA, and HFPO-DA, which is commonly known as GenX), and for a PFAS mixture of PFNA, PFHxS, PFBS, and GenX in drinking water. The mixture is assigned a Hazard Index MCL to account for dose-additive health effects. U.S. EPA's rule requires all community water systems and non-transient, non-community water systems to monitor these six PFAS on a quarterly basis under the recently adopted MCL standards, although UCMR5 sampling may satisfy some of those monitoring requirements.

SFPUC proactively and voluntarily monitored for PFAS in its RWS sources at several sites – seven surface water reservoirs, AEP, TTF intake, SVWTP effluent, and HTWTP effluent – between August 2019 and February 2020. At each location, 18 different PFAS compounds were analyzed using the available method (Method 537.1) approved by U.S. EPA and SWRCB. These monitoring results showed no PFAS detections at all RWS locations.

Upon completion of the first-round, voluntary PFAS monitoring indicated above—and in the absence of mandatory monitoring requirements from SWRCB—SFPUC conducted another round of voluntary PFAS monitoring for the RWS using the newer analytical method (Method 533) approved by U.S. EPA. The new method mainly targeted 25 short-chain PFAS contaminants. SFPUC completed two rounds of voluntary PFAS monitoring for the RWS, including the eight Phase 1 RGSR wells. This work was completed in 2021, and all results were non-detect.

In December 2021, U.S. EPA published its UCMR5. The RWS was sampled for the required 29 PFAS contaminants on a quarterly schedule in 2023 (except for one location, Sunset Reservoir North, that was out of service and had its sampling extended to March 2024), and all results were non-detect.

6.2.4 Microplastics

In July 2020, SWRCB adopted a definition of microplastics as solid polymeric materials to which chemical additives or other substances may have been added, which are particles that have at least three dimensions that are greater than 1 nanometer and less than 5,000 micrometers (μ m). Polymers that are derived in nature and have not been chemically modified (other than by hydrolysis) are excluded. With limited information on the potential health impacts of microplastics, DDW has not set regulatory levels to date and is focusing on monitoring, as described in the "Microplastics in Drinking Water Policy Handbook (August 2022)." DDW is employing a 4-year monitoring campaign to provide a better understanding of the prevalence of microplastics in drinking water systems, pending the adoption of the standard method of analysis and better definition of sampling protocols.

This is an original program globally. SFPUC expects its results to be better than most utilities, given its protected watersheds, but cannot be certain until data are available. The SWRCB resolution adopting the definition of microplastics noted that evidence concerning the toxicity and exposure of humans to microplastics is nascent and rapidly evolving, and that the proposed definition of "microplastics in drinking water" is subject to change in response to new information. The definition may also change in response to advances in analytical techniques and/or the standardization of analytical methods.

2024 State of the Regional Water System Report

6.2.5 Other Contaminants of Emerging Concern

SFPUC has completed its "Water Quality Strategic Plan" update. The goals of the plan update are to address upcoming issues related to drinking water quality to meet regulations, proactively protect public health, respond to future drinking water quality challenges, and maintain/ improve customer satisfaction in drinking water quality delivered to wholesale and retail customers. Developmental material was reviewed with wholesale customers and other interested parties during focus area workshops. The draft final report was shared with wholesale customers for comment on July 9, 2024, and comments were received on July 31, 2024. The final report update was completed on September 25, 2024.

		Tuble A-	L. Dums		
Asset	Dam Type	Dam Height (feet)	County	Completion Date	DSOD Jurisdictional?
			ountry		
O'Shaughnessy Dam	Concrete Gravity Arch	430	Tuolumne	1923/1938	Yes
Cherry Valley Dam	Earth and Rock	330	Tuolumne	1955	Yes
Early Intake Diversion Dam	Concrete Arch	81	Tuolumne	1924	Yes
Eleanor Dam	Concrete Buttressed Arch	70	Tuolumne	1918	Yes
Moccasin Dam	Earth and Rock	70	Tuolumne	1929	Yes
Priest Dam	Earth and Rock	160	Tuolumne	1923	Yes
Moccasin Upper Dam	Concrete- Gravity	30	Tuolumne County	1936	Yes, appurtenance to Moccasin Dam
		Вау	Area		
Calaveras Dam	Earth and Rock Filled	220	Alameda	1925/2019	Yes
Turner Dam	Earth	195	Alameda	1965	Yes
Upper Alameda Diversion Dam	Concrete Slab and Buttress	31	Alameda	1931	No
Lower Crystal Springs Dam	Concrete Gravity	163	San Mateo	1888/1890/ 1911	Yes
Upper Crystal Springs Dam	Earth	92.5	San Mateo	1877/1891	No
Pilarcitos Dam	Earth	95	San Mateo	1866/1867/ 1874	Yes
San Andreas Dam	Earth	105	San Mateo	1870/1875	Yes
San Mateo Creek Dam No. 1	Earth	20	San Mateo	1898	No
San Mateo Creek Dam No. 2	Concrete Arch	40	San Mateo	1898	No
Stone Dam	Masonry Arch	31	San Mateo	1871	No
		San Fi	rancisco		
Sunset North Dam	Earth	74	San Francisco	1938	Yes
Sunset South Dam	Earth	34	San Francisco	1960	Yes
University Mound North Basin	Earth	17	San Francisco	1885	Yes
University Mound South Basin	Earth	61	San Francisco	1937	Yes
Merced Manor Dam	Earth	23	San Francisco	1936	No

Table A-1: Dams

Note:

DSOD = Division of Safety of Dams

2024 State of the Regional Water System Report

Asset	Number of Wellheads	Location	Capacity				
	Bay Area						
Pleasanton Well Field	2	Pleasanton	< 1 mgd				
Peninsula Conjunctive Use Wells (2019)	13	Various	~6.2 mgd				
Sunol Filter Gallery	_	Sunol	7.4 mgd				
	Upcountry						
Cherry Valley Compound Well	1	Cherry Valley	3 to 7 gpm				
O'Shaughnessy Backpacker Campground Well	1	O'Shaughnessy	6.8 gpm				
O'Shaughnessy Dam Campground Well	1	O'Shaughnessy	30 gpm				

Table A-2: Groundwater Wells/Filter Galleries

Notes:

gpm = gallons per minute mgd = million gallons per day

2024 State of the Regional Water System Report

	1 uote 11 0. Suppry		
	Capacity of Reservoir	Reservoir Surface Area	
Asset	(AF)	(sq. mi)	Location
	Bay A	rea	
Calaveras Reservoir	96,800	2.2	Alameda County
San Antonio Reservoir	50,500	1.3	Alameda County
Crystal Springs Reservoir	69,300 ¹	2.3	San Mateo County
(Upper and Lower)			-
Pilarcitos Reservoir	3,100	0.2	San Mateo County
San Andreas Reservoir	19,000	0.9	San Mateo County
	Upcour	ıtry	
Early Intake Reservoir	115		Tuolumne County
Hetch Hetchy Reservoir	360,360 ²	3.1	Tuolumne County
Lake Eleanor	27,113 ³	1.5	Tuolumne County
Lake Lloyd	273,500	2.8	Tuolumne County
(Cherry Valley Reservoir)			2
Moccasin Reservoir	552	0.05	Tuolumne County
Priest Regulating Reservoir	1,706	0.07	Tuolumne County

Table A-3: Supply Reservoirs

Notes:

¹ 57,704 AF maximum permissible level due to Fountain Thistle.

² Capacity with drum gates activated.

³ Capacity with flashboards.

AF = acre-feet

sq. mi = square miles

Table A-4: Treated Water Storage

Asset	Capacity (MG)	Location			
Bay Area					
Town of Sunol (two tanks)	0.097 and 0.097	Sunol			
Niles Reservoir	Decommissioned	Niles			
Castlewood Reservoir	0.4	Pleasanton			
Pulgas Balancing Reservoir	60	San Mateo			
Merced Manor Reservoir	9.5	San Francisco			
Sunset Reservoir – North Basin	89.4	San Francisco			
Sunset Reservoir – South Basin	87.3	San Francisco			
University Mound Reservoir – North Basin	59.4	San Francisco			
University Mound Reservoir – South Basin	81.5	San Francisco			
Ирсон	intry				
Moccasin Domestic	0.088	Moccasin			
Early Intake Domestic	0.044	Early Intake			
Cherry Compound	0.066	Cherry			
O'Shaughnessy Domestic	0.041	O'Shaughnessy			

Note:

MG = million gallons

2024 State of the Regional Water System Report

Asset	Capacity (mgd)	Location			
B	ay Area				
TTF	315	Tracy/San Joaquin County			
Thomas Shaft Facility	315	San Joaquin County			
SVWTP	160	Alameda County			
Sunol Chloramination Facility	_	Alameda County			
HTWTP	1401	San Mateo County			
Pulgas Dechloramination Facility	200	San Mateo County			
Uţ	ocountry				
Rock River Lime Treatment Plant	400	Tuolumne County			
Moccasin Camp UV Facility	0.47 per reactor (2)	Tuolumne County			
Early Intake Camp UV Facility	0.47 per reactor (2)	Tuolumne County			
O'Shaughnessy Compound UV Facility	0.17 per reactor (2)	Tuolumne County			

Table A-5: Water Treatment Facilities

Notes:

¹ Peak hydraulic capacity is 180 mgd for a few hours.

HTWTP = Harry Tracy Water Treatment Plant

mgd = million gallons per day SVWTP = Sunol Valley Water Treatment Plant

TTF = Tesla Treatment Facility

UV = ultraviolet

2024 State of the Regional Water System Report

Tuble A-0: water Ir	1				
			Flow Rate		
		T 11	(Design or	T . 11 .1	
Arrel	C!		Operating)	Installation	
Asset	Size	(miles)	(mgd)	Date	
	Bay Area		100	1024	
CRT	10.5′	25	400	1934	
Alameda No. 1	69″	0.6	67	1934	
Alameda No. 2	91″	0.6	134	1953	
Alameda No. 3	96″	0.6	152	1967	
Alameda No. 4	66″	0.6	160	2011	
San Antonio Pipeline	60″	2.1	230	1967	
SABPL	66″	1.3	230	2014	
Calaveras Pipeline	44 to 72"	6	80	1965/1992	
Irvington Tunnel No. 1	10.7′	3.5	400	1934	
Irvington Tunnel No. 2	102″	3.5	400	2014	
BDPL No. 1	60″	21.2	46	1925/1933	
BDPL No. 2	66″	21.2	59	1935/1936	
BDPL No. 3	72″	34	80	1952	
BDPL No. 4	90″	34	80	1965/1967	
DDFL NO. 4	90	54	80	1973	
	East Bay: 72"	7	80	0011 (0010	
BDPL No. 5	Peninsula: 60"	9	55	2011/2012	
Bay Tunnel	9′	5	120	2014	
	10.3-foot	1.0		1004	
Pulgas Tunnel	horseshoe	1.9		1924	
Stanford Tunnel	90″	0.2	80	1949	
Palo Alto Pipeline	12 to 36"	4.4		1938	
Crystal Springs Bypass Tunnel	9.5′	3.4	215	1969	
Crystal Springs Bypass Pipeline	96″	0.9	215	1970	
New Crystal Springs Bypass Tunnel	96″	0.8	215	2011	
SSPL	60″	13.4	111	1948-1958	
CSPL No. 1	44"	17.1	10	1885/1956	
CSPL No. 2	60″	19.3	52	1937/1956	
CSPL No. 3	60″	3.6	60	1971/1987	
SAPL No. 1	44"	12.5	22	1870-1939	
				1927-1928	
SAPL No. 2	54″	12.3	37	2020	
SAPL No. 3	60 to 66"	6.6	65	1992/2014	
SSBPL	60"	1.1	65	1947	
Crystal Springs-San Andreas Force				1898-1932	
main	61″	4.7	90	1968	
Stone Dam Tunnel No. 1	4'-6" by 4'-9"	0.1	45	1872-1948	
Stone Dam Tunnel No. 2	3'-6" by 4'-4"	0.61	45	1872-1948	
San Mateo Tunnel No. 1	3'-6" by 5'-1"	0.65	40	1868	
San Mateo Tunnel No. 2	4'-4" by 4'-6"	0.67	45	1898	
Sun mateo i uniter i vo. 2	y	0.07	10	1070	

Table A-6: Water Transmission – Pipelines and Tunnels

2024 State of the Regional Water System Report

Asset	Size	Length (miles)	Flow Rate (Design or Operating) (mgd)	Installation Date
	Upcountry			
Canyon Power Tunnel	14' by 14'-6" horseshoe	10.8	Design: 471	1965
Cherry Power Tunnel	12' by 12' horseshoe	5.5	Design: 523	1959
Early Intake Bypass	14' by 14'-6" horseshoe	0.38	NA	1967
Eleanor-Cherry Tunnel	10'-10" by 10'-10" horseshoe	1.1	Operating: 646	1960
Foothill Division Tunnel	13'-4" by 14'- 3" horseshoe	16.4	400	1929
LCA		3.78	Operating: 107	1917
Moccasin Power Tunnel	13' by 13' horseshoe	1	Design: 801	1925
Moccasin Reservoir Bypass Pipeline	108″	0.39	Operating: 320	1972/1988
Mountain Division Tunnel	varies	19.2	Design: 400 at grade of 1.55:1000	1925
Red Mountain Bar Siphon	9.5′	0.48	400	1970
SJPL No. 1	56 to 72"	47.4	Operating: 75	1932
SJPL No. 2	61″	47.4	Operating: 80	1952
SJPL No. 3	78″	47.4	Operating: 150	1968
SJPL No. 4	78″	17.2	Operating: 150	2011-2013

Notes:

BDPL = Bay Division Pipeline CRT = Coast Range Tunnel CSPL = Crystal Springs Pipeline LCA = Lower Cherry Aqueduct mgd = million gallons per day SABPL = San Antonio Backup Pipeline SAPL = San Andreas Pipeline SJPL = San Joaquin Pipeline SSBPL = Sunset Branch Pipeline SSPL = Sunset Supply Pipeline

2024 State of the Regional Water System Report

		,			
	Number of	Total Capacity			
Asset	Pumps	(mgd)	Location		
	Bay Area				
LMPS	5	65	San Francisco		
Baden Pump Station	3	45	San Bruno		
CSPS	4	120	San Mateo		
Town of Sunol (potable)	2	0.72	Sunol		
Sunol Pump Station	3	7.4	Sunol		
Pulgas Pump Station	5	185	San Mateo		
SAPS	8 (electric) 2 (diesel)	160	Sunol		
Upcountry					
Cherry-Eleanor Pump Station	10	300	Tuolumne County		

Table A-7: Water Transmission – Pump Stations

Notes:

CSPS = Crystal Springs Pump Station

mgd = million gallons per day LMPS = Lake Merced Pump Station

SAPS = San Antonio Pump Station

2024 State of the Regional Water System Report

		Valve		
		Size		
Asset	Valves	(inches)	Pipeline	Location
			ı Area	
	V8	36 by 60	ACDD	
	V10	60 by 84	ACDD	
	V11	60 by 84	ACDD	
	V12	36 by 60	ACDD	
Alameda Creek	V13	36 by 60	ACDD	Sunol
	V18	60 by 72	ACDD	
	V20	60 by 72	ACDD	
	V220	60 by 72	ACDD	
	V240	60 by 72	ACDD	
	X10	72	AS-2	
	X20	72	AS-3	
AEP	X30	60	AS-1	Sunol
AEF	X32	60	AS-1	Sunoi
	X50	54	AS-4	
	X55	54	AS-4	
	W35	60	SAPL	
	W41	60	SABPL	
	W42Y	60	SABPL	
	X15	90	AS-2	
	X23	66	SABPL	
	X24Y	66	SABPL	
	X25	72	SABPL	
	X35	66	AS-1	
	X64	12	SUNOL PL	
	X71	96	AS-4	
	X72	96	AS-1	
	X73	84	AS-2	
	X74	84	AS-1	
.1 1	X75	96	AS-3	
Alameda	X76	96	AS-1	0 1
+SAPL +	Y20	54	SAPL	Sunol
SABPL	Y21	54	SAPL	
	Y22	48	SAPL	
	Y23	60 (0	SAPL	
	Y24 Y25	60	SABPL	
	Y27	66 66	SABPL	
	Y28	66 54	SABPL SABPL	
	Y30	34 30	SAPL	
	Y31	24	SAPL	
	Y32	36	SAPL	
	Y35	36	SAPL	
	Y41	20	SAPL	
	Y42	20	SAPL	
	Y43	20	SAPL	
	Y44	36	SAPL	

Table A-8: Water Transmission – Valve Lots

		Valve		
		Size		
Asset	Valves	(inches)	Pipeline	Location
113500	X61	12	TOSPL	Location
	X62	12	TOSPL	
AWP	X63	12	TOSPL	Sunol
11001	X85	72	AS-2	Suitor
	X95	96	AS-4	
	K50	42	CSPL No. 2	
	K51M	36	CSPL No. 2	
	K54P	42	CSPL No. 2/SSPL	
	K54R	30	CSPL No. 2	
	M50	60	SSPL	
	M53R	30	SSPL/SAPL No. 2	
	M54P	42	SAPL No. 1	
	M55P	42	SAPL No. 1/CSPL No. 2	
	P57M	30	SAPL No. 1	
	P57R	42	CSPL No. 2	
	P59R	42	CSPL No. 2	
Baden Valve Lot	R50	42	SAPL No. 2	South San Francisco
Duden varve Lot	R55	54	SAPL No. 2	South Sur Francisco
	R55K	36	SAPL No. 2/SAPL No. 3	
	R58P	42	SAPL No. 2/CSPL No. 2	
	T50	42	SAPL No. 3	
	T52R	42	SAPL No. 2/SAPL No. 3	
	T54M	42	SAPL No. 2/SAPL No. 3	
	T55	54	SAPL No. 3	
	T55P	16	CSPL No. 2/SAPL No. 3	
	T56R	42	SAPL No. 2/SAPL No. 3	
	T57P	42	CSPL No. 2	
	T58K	24	CSPL No. 2/SAPL No. 3	
	C34	72	BDPL No. 3	
	C36	72	BDPL No. 3	
Barron Creek	C35D	42	BDPL No. 3/BDPL No. 4	Palo Alto
Durron Crook	D34	90	BDPL No. 4	1 410 1 110
	D36	90	BDPL No. 4	
	C58	72	BDPL No. 3	
	C60	72	BDPL No. 3	
Bear Gulch Valve	D58	84	BDPL No. 4	Atherton
Lot	D60	84	BDPL No. 4	
	C59D	42	BDPL No. 3/BDPL No. 4	
	M30	42	SSPL	
D 11 1 D	M31	36	SSPL	
Bellevue and Pepper	M32K	36	CSPL No. 2/SSPL	Hillsborough
Valve Lot	M33L	36	CSPL No. 3/SSPL	
	L30	42	CSPL No. 3	
	C20	66	BDPL No. 3	
	C22D	48	BDPL No. 3/BDPL No. 4	
Calaveras Valve Lot	C23D	48	BDPL No. 3/BDPL No. 4	Milpitas
	D20	72	BDPL No. 4	

		Valve		
		Size		
Asset	Valves	(inches)	Pipeline	Location
	V21	30	Calaveras Dam	
	V22	48	Calaveras Dam	
	V23	48	Calaveras Dam	
	V24	60	Calaveras Dam	
	V25	30	Calaveras Dam	
	V26	48	Calaveras Dam	
	V27	48	Calaveras Dam	
	V31	72	Calaveras Dam	
	V33	72	Calaveras Dam	
	V34	48	Calaveras Dam	
	V36	30	Calaveras Dam	
	V37	30 by 16	Calaveras Dam	
Calaveras Reservoir	V38	30 by 16	Calaveras Dam	Sunol
	V330	42	CALPL	
	V397	66	CALPL	
	V40	66	CALPL	
	V41	16	CALPL	
	V41A	16	CALPL	
	V41B	16	CALPL	
	V42	66	CALPL	
	V43	36	CALPL	
	V43A	36	CALPL	
	V43B	36	CALPL	
	V44	66	CALPL	
	V442	66	CALPL	
Crystal Springs/San Andreas	S49	36 by 48	CSPL/SAPL	San Bruno
	M41	24	SSBPL	
	M41A	24	SSBPL	
Capuchino Valve	M41C	24	SSBPL	Com David
Lot	M43	14	SSBPL	San Bruno
	M43A	14	SSBPL	
	M43C	14	SSBPL	
Casey Quarry	M20	42	SSPL	Hillsborough
	C17	78	BDPL No. 3	
	C18D	42	BDPL No. 3/BDPL No. 4	
Crawford Valve Lot	C19	78	BDPL No. 3	Fremont
	D17	78	BDPL No. 4	
	D19	78	BDPL No. 4	

		Valve		
		Size		
Asset	Valves	(inches)	Pipeline	Location
	H10	42	LCS Outlet PL	
	H11	42	LCS Outlet PL	
	H12	42	LCS Outlet PL	
	H20	42	LCS Outlet PL	
	H21	42	LCS Outlet PL	
	H22	42	LCS Outlet PL	
	H88	16	LCS Outlet PL	
	H88A	16	LCS Outlet PL	
	H89	60	CSPL/SAPL	
	H90	16	LCS Outlet PL	
	H91	66 by 60	DSOD Emerg.	
Crystal Springs	H92	66 by 60	DSOD Emerg.	Crystal Spring
Reservoir	H93	24	LCS Outlet PL	jen r o
	H96	24	LCS Outlet PL	
	J61K	24	CSPL No. 1/CSPL No. 2	
	J62K	24	CSPL No. 1/CSPL No. 2	
	K60	48	CSPL No. 2	
	K70	48	CSPL No. 2	
	L40P	30	CSPL No. 3/Millbrae Yard	
	L41K	42	CSPL No. 3/Millbrae Yard	
	L59K	44	CSPL No. 2/CSPL No. 3	
	L60	44	CSPL No. 1	
	L70	44	CSPL No. 1	
Crystal Springs and El Cerrito Valve Lot	K20	48	CSPL No. 2	Hillsborough
Davis Tunnel Diversion	S20	56 by 52	Davis Tunnel	
	A64D	24	BDPL No. 1/BDPL No. 4	
Edgewood Road	B65D	24	BDPL No. 2/BDPL No. 4	San Mateo
Valve Lot	B66C	20	BDPL No. 2/BDPL No. 3	Cultification
Burlingame Valve Lot	K30	36	CSPL No. 2	Burlingame
	K38P	16	CSPL No. 2	
	K39P	16	SAPL No. 1	
El Camino Real/	K40	30	CSPL No. 2	
Millbrae Yard Valve	K40P	12	CSPL No. 2	Millbrae
Lot	K41P	12	CSPL No. 2	
	M40	42	SSPL	
	M42K	36	SSPL/CSPL No. 2	
	A17	66	BDPL No. 2	
	A18	66	BDPL No. 2	
	A19	66	BDPL No. 2	
	A191	36	BDPL No. 2	
Grimmer Shutoff	A19B	36	BDPL No. 1/BDPL No. 2	Hayward
Station	A19E	24	BDPL No. 2/BDPL No. 5	J
	A23B	24	BDPL No. 1/BDPL No. 2	
	B17	60	BDPL No. 1	
	B18	60	BDPL No. 1	
	E15A	42	BDPL No. 2/BDPL No. 5	

		Valve			
		Size			
Asset	Valves	(inches)	Pipeline	Location	
	C24	72	BDPL No. 3		
	C26	72	BDPL No. 3		
Guadalupe Valve	C25D	42	BDPL No. 3/BDPL No. 4	Santa Clara	
Lot	D24	90	BDPL No. 4		
	D26	90	BDPL No. 4		
	T10R	54	SAPL No. 3		
	T11	66	SAPL No. 3	C D	
HTWTP	T12	20	SAPL No. 3	San Bruno	
	T20	42	SAPL No. 3		
TT:11-111	M15	78	SSPL		
Hillsborough Valve	M21K	36	CSPL No. 2/SSPL	Hillsborough	
Lot	M22J	36	CSPL No. 2/SSPL	0	
	A09	16	Hayward Serv.		
	A10	66	BDPL No. 2		
Irvington Portal	B10	60	BDPL No. 1	Hayward	
Ũ	C10	60	BDPL No. 3	2	
	D10	72	BDPL No. 4		
	A21	42	Hayward Intertie		
Hayward/EBMUD	A22	36	Hayward Intertie	TToomaad	
Intertie	A23	36	Hayward Intertie	Hayward	
	A24	36	Hayward Intertie		
	A11	60	BDPL No. 2		
	A11.1	16	Hayward Pipeline		
	A11.1 A13E	24	BDPL No. 2/BDPL No. 5		
	B11	60	BDPL No. 1		
	C11	78	BDPL No. 3		
New Irvington	D11	96	BDPL No. 4	Fremont	
Portal	E10	90 72	BDPL No. 2	(NIT)	
Tortai	E10 E11	72	BDPL No. 5	(1111)	
	H1	24	Hayward Pipeline		
	H2	24	NIT No. 1 Manifold		
	H3	24	NIT No. 1 to Hayward		
	IT2-1	96	Pipeline		
			IT2		
	C30	42	BDPL No. 3		
Mountain View/	C31D	48	BDPL No. 3/BDPL No. 4	Mountain View	
Alviso Valve Lot	C32D	48	BDPL No. 3/BDPL No. 4		
	D30	72	BDPL No. 4		
	A20U	66	BDPL No. 2/BDPL No. 5		
Newark Tunnel	B20U	60	BDPL No. 1/BDPL No. 5	Fremont	
Shaft	E15	72	BDPL No. 5		
	E20U	72	BDPL No. 5		
	F40	36	PAPL		
Palo Alto Pipeline	F45	36	PAPL	Palo Alto	
	F50	24	PAPL		

		Valve		
	X7 1	Size	TD1 11	T (*
Asset	Valves	(inches)	Pipeline	Location
	A14	66	BDPL No. 2	
	A15	66	BDPL No. 2	
	A161	36	BDPL No. 2	
Paseo Padre Shutoff	A16B	36	BDPL No. 1/BDPL No. 2	Hayward
Station	B14	60	BDPL No. 1	
	B15	60	BDPL No. 1	
	E14	72	BDPL No. 5	
	E14A	42	BDPL No. 2/BDPL No. 5	
	S10	22	PIL	
Pilarcitos Reservoir	S11	26 by 36	PIL	Pilarcitos
	S12	26 by 36	PIL	
Ravenswood Tunnel	B50U	66	BDPL No. 5	
Shaft	E50U	60	BDPL No. 5	Fremont
	E52B	24	BDPL No. 2/BDPL No. 5	
	A50U	60	BDPL No. 5	
	A60	42	BDPL No. 1	
	A61B	30	BDPL No. 1/BDPL No. 2	
	A62B	30	BDPL No. 1/BDPL No. 2	
	B60	66	BDPL No. 2	
	B62	48	BDPL No. 2	
	E10F	24	PAPL	East Palo Alto
Redwood City Valve	E60	60	BDPL No. 5	Redwood City
Lot	E61B	42	BDPL No. 2/BDPL No. 5	Reawood eny
	E61	60	BDPL No. 5	
	F05	24	BDPL No. 1/BDPL No. 2	
	F06	24	PAPL	
	F10	20	PAPL	
	F20	20	PAPL	
	F26	24	PAPL	
	F30	30	PAPL	
	G10	120 by 96	Pulgas Tunnel	
	G11	120 by 120	Pulgas Tunnel	
	G12	42	Pulgas PS	
	G13	42	Pulgas PS	
	G14	42	Pulgas PS	
	G15	42	Pulgas PS	
	G16	48 by 48	Pulgas PS	
Crustal Springs	G17	48 by 48	Pulgas PS	
Crystal Springs	G18	84	Pulgas Balancing Res.	Can Mataa
Bypass Tunnel/ Bypass Pipeline	G18A	18	Pulgas Balancing Res.	San Mateo
	G20	120 by 120	CSBT	
	G32	96	NCSBT	
	G34	96	CSBPL	
	G36	78	NCSBT/SSPL	
	G38	60	NCSBPL/CSPL No. 2	
	G40	72	CSBPL/SSPL and CSPL No. 2	
	G41	54	CSBPL/SSPL	
	G42	42	CSBPL/CSPL No. 2	

		Valve		
		Size		
Asset	Valves		Directine	Location
Asset		(inches)	Pipeline	Location
	H81	72 72	CSOS No. 1	
	H82		CSOS No. 1	
	H83	60 (0	CSPS- CSPL/SAPL	
	H84	60 60	Reservoir – Potable Pipeline CSPS Suction	
	H85	80 36	CSPS Disc. to	
	H86	56 72		
CSPS	H87	42	Potable Pipeline	San Mateo
	H97		SSPL	
	H98	42	SSPL	
	H99	42 12	SSPL	
	J10		CSPL No. 2	
	J11 K10	12	CSPL No. 2	
	K10	60 60	CSPL No. 2	
	M10	60	SSPL	
	N20	54	SAPL No. 2RW	
	N21	54	SAPL No. 2RW	
	N30	48	SAPL No. 3RW	
	N31	48	SAPL No. 3RW	
	N32	48	SAPL No. 3RW	
	N33	48	SAPL No. 3RW	
	N40	54	SAPL No. 2	
	N41	60	SAPL No. 3RW	
	N50	54	SAPL No. 3RW	
	N51	60 06	SAPL No. 3RW	
San Andreas	N69	96	HTWTP Treated Water	
Reservoir	N72	96 70	HTWTP Treated Water	San Bruno
	N74	78	SSBPL	
	P10	24	SAPL No. 1	
	P48	44	SAPL No. 1	
	R11 R12	54 54	SAPL No. 2	
			SAPL No. 2	
	R20	42	SAPL No. 2	
	R70	54 54	SAPL No. 2	
	R71	54 26	SAPL No. 2	
	T64R	36	SAPL No. 2/No. 3	
	T65R	36	SAPL No. 2/No. 3	
	T70	36	SAPL No. 3	
	A68	42	BDPL No. 1	
	A70	42	BDPL No. 1	
	B68 B70	42	BDPL No. 2 BDPL No. 2	
	B70	42	BDPL No. 2 BDPL No. 2	
Pulgas Valve Lot	C68	48	BDPL No. 3 BDPL No. 3	San Mateo
-	C70	48 72	BDPL No. 3 BDPL No. 4	
	D68	72 72	BDPL No. 4	
	D70	72	BDPL No. 4	
	E68	60 (0	BDPL No. 5	
	E70	60	BDPL No. 5	

		Valve		
		Size		
Asset	Valves	(inches)	Pipeline	Location
	X11	20	SVWTP Eff.	
	X111	20	SVWTP Eff.	
	X112	20	SVWTP Eff.	
	X12	60	SVWTP Eff.	
	X14	66	AS-2	
	X22	60	SVWTP Eff.	
	W11	54	CALPL	
CADC Value Lat	W12	66	CALPL	Cruzal
SAPS Valve Lot	W15	36	San Antonio Pipeline	Sunol
	W20	60	SVWTP Eff.	
	W21	54	SVWTP Eff.	
	W22	54	SVWTP Eff.	
	W30	60	San Antonio Pipeline	
	W31	42	San Antonio Pipeline	
	W32	60	San Antonio Pipeline	
	W33	60	San Antonio Pipeline	
	Y01	36	San Antonio Pipeline	
	Y02	36	San Antonio Pipeline	
San Antonio	Y03	36	San Antonio Pipeline	Sunol
Reservoir	Y04	36	San Antonio Pipeline	
	Y05	36	San Antonio Pipeline	
	S13	36 by 36	San Mateo Tunnel No. 1	
	S30	36 by 36	San Mateo Tunnel No. 2	
San Mateo Creek	S31	39 by 18	San Mateo Tunnel No. 2	
Dam	S32	39 by 18	San Mateo Tunnel No. 2	
	S33	39 by 18	San Mateo Tunnel No. 2	
	S40	30	San Mateo Tunnel No. 2	
	M60	42	SSPL	
	T60	48	SAPL No. 3	
	T61M	36	SAPL No. 3/SSPL	
	T62R	30	SAPL No. 3/SAPL No. 2	<u>c</u> 1
San Pedro Valve Lot	T63R	30	SAPL No. 3/SAPL No. 2	Colma
	T64M	36	SAPL No. 3/SSPL	
	R59	42	SAPL No. 2	
	R60	42	SAPL No. 2	
Charlen J. Frank Daniel	C40	48	BDPL No. 3	D-1- A1-
Stanford East Portal	D40	72	BDPL No. 4	Palo Alto
	C23.1	42	BDPL No. 3	
	C23.2	42	BDPL No. 3	
SFWD/Valley Water	C23.3	42	BDPL No. 3/BDPL No. 4	Santa Clara
	D23.1	42	BDPL No. 4	
	D23.2	42	BDPL No. 4	
	C50	48	BDPL No. 3	D 1 A1/
Stanford West Portal	D50	72	BDPL No. 4	Palo Alto
	S60	22	Stone Dam	
Stone Dam	S61	48 by 48	Stone Dam	Stone Dam
CODDI	N44	78	SSBPL	C D
SSBPL	N75	78	SSBPL	San Bruno

		Valve			
		Size			
Asset	Valves	(inches)	Pipeline	Location	
	W10	42	CALPL		
SVWTP	W40	60	San Antonio PL	Sunol	
	C14	78	BDPL No. 3		
	D14	78	BDPL No. 4		
Tissiack Valve Lot	C15D	42	BDPL No. 3/BDPL No. 4	Fremont	
	C16	78	BDPL No. 3		
	D16	78	BDPL No. 4		
		Upc	ountry		
Canyon Portal Valve House	CPVH BFV	96	Kirkwood Powerhouse Penstock	Early Intake	
	SG 1	24			
Eleanor Release	SG 2	24	Eleanor Creek	Eleanor	
Valves	G 3	24	Licuitor Creek	Licuitor	
	G 4	24			
Early Intake Dam	SG 1	36	Tuolumne River	Early Intake	
	SG 2	36		,	
Cherry-Eleanor	SG A	72 by 96	Cherry-Eleanor Tunnel	Cherry Pump Station	
Tunnel	SG B	72 by 96		, I	
Mountain Tunnel	HG 2	48 by 60	Manualain Turanal	To state to to to	
Headgates	HG 3 HG 4	48 by 60 48 by 60	Mountain Tunnel	Early Intake	
	FCV 1	40 Dy 60 66			
	FCV 1 FCV 2	66			
	JFV 1	18		Cherry Valve House	
	JFV 2	18	Cherry Creek		
Cherry Valley Dam	12-inch Needle	12	cherry creek		
	BFV 1	84			
	BFV 2	84			
	BFV 3	84	Cherry Power Tunnel		
	EC-EXO101	60	SJPL No. 1		
	EC-EXO201	60	SJPL No. 2		
	EC-EXO301	72	SJPL No. 3		
	EC-EXO102	60	SJPL No. 1		
Emery Crossover	EC-EXO202	60	SJPL No. 2	Stanislaus County	
Valves	EC-EXO302	72	SJPL No. 3	Stariisiaus County	
	EC-EXOUX12	36	SJPL Nos. 1 and 2		
	EC-EXOUX23	42	SJPL Nos. 2 and 3		
	EC-EXODX12	30	SJPL Nos. 1 and 2		
$C_{\rm max} = 1.1 T_{\rm m}^{-1}$	EC-EXODX23	36	SJPL Nos. 2 and 3		
Granite Portal Valve House	BFV	94	Holm Powerhouse Penstock	Tuolumne County	
	ODP101	60	SJPL No. 1		
Oakdale Portal	ODP201	60	SJPL No. 2	Tuolumne County	
Valve House	ODP301	78	SJPL No. 3	- actualitie County	
	ODP401	78	SJPL No. 4		

		Valve			
		Size			
Asset	Valves	(inches)	Pipeline	Location	
110000	V1	72	Tuolumne River	Location	
	V2	75	ruolumite ruver		
O'Shaughnessy Dam		60		O'Shaughnessy Dam	
e onauginessy Duni	V12 and V13	36	Canyon Power Tunnel	e shaughnessy built	
	V12 and V15 V15 and V16	60			
West Portal Valve	BFV 1 and				
House	BFV 2	104	Moccasin Penstock	West Portal	
110400	PC-PXO101	60	SJPL No. 1		
	PC-PXO201	60	SJPL No. 2		
	PC-PXO301	72	SJPL No. 3		
	PC-PXO102	60	SJPL No. 1		
	PC-PXO202	60	SJPL No. 2		
Pelican Crossover	PC-PXO302	72	SJPL No. 3		
Valves	PC-PXO402	72	SJPL No. 4	Vernalis	
Varves	PC-PXOUX12	36	SJPL Nos. 1 and 2		
	PC-PXOUX23	42	SJPL Nos. 2 and 3		
	PC-PXODX12	42 30	SJPL Nos. 1 and 2		
	PC-PXODX12	36	SJPL Nos. 2 and 3		
	PC-PXODX34	36	SJPL Nos. 3 and 4		
	RC-RXO101	60	SJPL No. 1		
	RC-RXO201	60 60	-		
	RC-RXO301	80 72	SJPL No. 2		
			SJPL No. 3		
Roselle Crossover	RC-RXO102	60 (0	SJPL No. 1	Riverbank	
	RC-RXO202	60 72	SJPL No. 2		
Valves	RC-RXO302	72	SJPL No. 3		
	RC-RXOUX12	36	SJPL Nos. 1 and 2		
	RC-RXOUX23	42	SJPL Nos. 2 and 3		
	RC-RXODX12	30	SJPL Nos. 1 and 2		
	RC-RXODX23	36	SJPL Nos. 2 and 3		
SJPL No. 4 Tie-In	P4J301	60	SJPL No. 3	Stanislaus County	
Vault	P4J401	60	SJPL No. 4	5	
	T3E331	36	SJPL No. 3		
SJPL Nos. 3 and 4	T3E301	72	SJPL No. 3	Stanislaus County	
Throttling Station	T4E431	36	SJPL No. 4	5	
	T4E401	72	SJPL No. 4		
SJPL No. 2	T2E201	48	SJPL No. 2		
Throttling Station	T2E231	30	SJPL No. 2	Stanislaus County	
T2E					
SJPL No. 2	T2W201	48	SJPL No. 2		
Throttling Station	T2W231	30	SJPL No. 2	Stanislaus County	
T2W					
	SJV331	42	SJPL No. 3		
	SJV311	42	SJPL No. 3		
	SJV212	20	SJPL No. 2		
San Joaquin River	SJV231	30	SJPL No. 2	Stanislaus County	
Valve House	SJV211	30	SJPL No. 2	Standiau County	
	SJV131	30	SJPL No. 1		
	SJV112	18	SJPL No. 1		
	SJV113	24	SJPL No. 1		

2024 State of the Regional Water System Report

Asset	Valves	Valve Size (inches)	Pipeline	Location
	TUV101	60	SJPL No. 1	
Tesla UV Valve	TUV201	60	SJPL No. 2	San Joaquin County
House	TUV301	78	SJPL No. 3	San jouquin County
	TUV401	78	SJPL No. 4	
Tesla Portal Valve	TPV101	60	SJPL No. 1	
House	TPV201	60	SJPL No. 2	San Joaquin County
Tiouse	TPV301	78	SJPL No. 3	

Notes:

ACDD = Alameda Creek Diversion Dam AEP = Alameda East Portal AS = Alameda Siphon AWP = Alameda West Portal BDPL = Bay Division Pipeline BFV = butterfly valve CALPL = Calaveras Pipeline CSBPL = Crystal Springs Bypass Pipeline CSBT = Crystal Springs Bypass Tunnel CSOS = Crystal Springs Outlet Structure CSPL = Crystal Springs Pipeline CSPS = Crystal Springs Pump Station DSOD = Division of Safety of Dams EBMUD = East Bay Municipal Utility District HTWTP = Harry Tracy Water Treatment Plant LCS = Lower Crystal Springs NCSBPL = New Crystal Springs Bypass Pipeline NCSBT = New Crystal Springs Bypass Tunnel NIT = New Irvington Tunnel PAPL = Palo Alto Pipeline PIL = Pilarcitos Dam Pipeline Pulgas PS = Pulgas Pump Station SABPL = San Antonio Backup Pipeline SAPL = San Andreas Pipeline SAPS = San Antonio Pump Station SFWD = San Francisco Water Department SJPL = San Joaquin Pipeline SSBPL = Sunset Branch Pipeline SSPL = Sunset Supply Pipeline TOSPL = Town of Sunol Pipeline SVWTP = Sunol Valley Water Treatment Plant UV = ultraviolet Valley Water = Santa Clara Valley Water District

2024 State of the Regional Water System Report

Asset	Capacity (mgd)	Location
	Bay Area	
DWR	50	Sunol
	30 mgd to/from EBMUD	
EBMUD	15 mgd to/from SFPUC	Hayward
	15 mgd to City of Hayward	
Valley Water	40	Milpitas

Table A-9: Water Transmission - Interties

Notes:

DWR = California Department of Water Resources EBMUD = East Bay Municipal Utility District mgd = million gallons per day Valley Water = Santa Clara Valley Water District SFPUC = San Francisco Public Utilities Commission

Table A-10: Water Transmission - Town of Sunol Distribution System

Asset	Size (inches)	Total Length (miles)	Capacity (mgd)
	Bay Are	ea	
	4″	0.75	
Town of Sunol Distribution	6″	0.66	0.15
System	8″	0.2	0.15
	2″	0.7	
	Upcount	try	
Moccasin Camp	N/A	N/A	N/A
Early Intake Camp	N/A	N/A	N/A
O'Shaughnessy Compound	N/A	N/A	N/A
Cherry Valley Compound	N/A	N/A	N/A

Notes:

mgd = million gallons per day N/A = not applicable

2024 State of the Regional Water System Report

Tuble 11 11, Watershea and Lanas Manazement Watersheas					
Asset	Size of Hydrologic Watershed (sq. mi)	Area Owned by SFPUC (sq. mi)	Location		
Asset	Bay Area	511 OC (sq. m)	Location		
Calaveras Watershed	135	26	Alameda and Santa Clara Counties		
Crystal Springs Watershed	24.8	24.8	San Mateo County		
Pilarcitos Watershed	6.2	6.1	San Mateo County		
San Andreas Watershed	4.1	4.0	San Mateo County		
San Antonio Watershed	40	13	Alameda County		
	Upcountry				
Early Intake Watershed	29	0	Tuolumne County		
Hetch Hetchy Watershed	459	0	Tuolumne County		
Moccasin Watershed	0	0	Tuolumne County		
Lake Eleanor Watershed	79	0	Tuolumne County		
Lake Lloyd Watershed	114	0	Tuolumne County		
Lower Cherry Diversion Dam Watershed	32	0	Tuolumne County		
Priest Watershed	2.8	0	Tuolumne County		

Table A-11: Watershed and Lands Management - Watersheds

Notes:

SFPUC = San Francisco Public Utilities Commission

sq. mi = square miles

Table A-12: Powerhouses

Asset	Power Output at Full Reservoir (MW)	Draft (mgd)	Location	Completion Date	
	Upcountry				
Kirkwood Powerhouse	125	820	Tuolumne County	1964	
Moccasin Powerhouse	110	860	Tuolumne County	1925/1969	
Moccasin Low Head Powerhouse	2.9	265	Tuolumne County	1986	

Notes:

mgd = million gallons per day MW = megawatt

NW = megawatt

Table A-13: Penstocks

Asset	Total Length (miles)	Location	Completion Date	
Upcountry				
Kirkwood Penstock	0.37	Tuolumne County	1964	
Moccasin Penstock	1.1	Tuolumne County	1925/portions in 1969	
Moccasin Low Head Penstock	0.5	Tuolumne County	1986	

2024 State of the Regional Water System Report

Asset	Status	Туре	Location
	l	Bay Area	
Cypress Work Center	Active	Former Cottage – now Natural Resources offices,	San Mateo County
		work and meeting center	
Crystal Springs Cottage	Active	Watershed Keeper Residence	San Mateo County
Davis Tunnel Cottage	Active	Watershed Keeper Residence	San Mateo County
North San Andreas	Active	Watershed Resources	San Mateo County
Cottage		Manager Residence	
Pilarcitos Cottage	Active	Watershed Keeper Residence	San Mateo County
Sawyer Camp Cottage	Active	Watershed Keeper Residence	San Mateo County
Upper Crystal Springs Cottage	Active	Watershed Keeper Residence	San Mateo County
Lower Crystal Springs Cottage	Active	Watershed Keeper Residence	San Mateo County
San Andreas Cottage	Active	Watershed Keeper Residence	San Mateo County
Alameda East Cottage	Active	Watershed Keeper Residence	Alameda County
Andrade Road Cottage	Active	Watershed Keeper Residence	Alameda County
Irvington Cottage	Active	Watershed Keeper Residence	Alameda County
Ohlone Cottage	Active	Watershed Keeper Residence	Alameda County
San Antonio Cottage	Active	Watershed Keeper Residence	Alameda County
Calaveras No. 2 Cottage	Decommissioned	Watershed Keeper Residence	Alameda County
Niles Cottage	Decommissioned	Watershed Keeper Residence	Alameda County
Calaveras No. 1 Cottage	Active	Watershed Keeper Residence	Alameda County
Sunol Yard Cottage	Removed	Watershed Keeper Residence	Alameda County
Tesla Cottage	Active	Operator Residence	San Joaquin County
Polhemus Fluoride Building	Active	Emergency Supply Stockpile and Staging Site	San Mateo County
Mt. Allison	Active	Radio Repeater Site	San Mateo County
Sawyer Ridge	Active	Radio Repeater Site	Alameda County
Pulgas Water Temple	Active	Public Grounds	San Mateo County
Sunol Water Temple	Active	Public Grounds	Alameda County
	u	pcountry	
O'Shaughnessy Office and cottages	Active	Office, other, residence for HHWP essential personnel and NPS	Tuolumne County
Cherry Cottages and Bunkhouse	Active	Office, residence for HHWP essential personnel, USFS, NPS	Tuolumne County
Early Intake Cottages and Bunkhouse	Active	Office, other, residence for HHWP essential personnel and NPS	Tuolumne County
Lake Eleanor Cottage and Bunkhouse	Active	Office and residence for NPS	Tuolumne County
Mather Cabins	Active	Other and residence for NPS	Tuolumne County

 Table A-14: Watershed and Lands Management – Structures (Non-Operations)

Asset	Status	Туре	Location
Moccasin Camp Offices	Active	Office, other, residence for	Tuolumne County
and Cottages		HHWP essential personnel	
Priest Cottage	Active	Residence for HHWP	Tuolumne County
		essential personnel	
Rock River Cottage	Active	Residence for HHWP	Tuolumne County
		essential personnel	
Warnerville Cottages	Active	Residence for HHWP	Stanislaus County
		essential personnel	
West Portal Cottage	Active	Residence for HHWP	Tuolumne County
		essential personnel	
Oakdale Office	Active	Office	Stanislaus County
South Fork Yard Office	Active	Office and shop	Tuolumne County
and Building		-	
Warnerville Shops	Active	Office and shop	Stanislaus County
Cherry Creek Diversion	Active	Gatehouse	Tuolumne County
Dam Structures			
Intake Switchyard	Active	Power transmission control	Tuolumne County
Control Building			
Warnerville Switchyard	Active	Power transmission control	Stanislaus County
Control Building			5
Holm Powerhouse	Active	Powerhouse	Tuolumne County
Kirkwood Powerhouse	Active	Powerhouse	Tuolumne County
Moccasin Powerhouse	Active	Powerhouse	Tuolumne County
Burnout Ridge Radio	Active	Radio Site	Tuolumne County
Site			5
Duckwall Radio Site	Active	Radio Site	Tuolumne County
Intake Ridge Radio Site	Active	Radio Site	Tuolumne County
Moccasin Peak Radio	Active	Radio Site	Tuolumne County
Site			
Poopenaut Pass Radio	Active	Radio Site	Tuolumne County
Site			
Old Moccasin	Not Active	vacant	Tuolumne County
Powerhouse			
Alameda Valve House	Active	Valve House	Alameda County
Albers Road Valve House	Active	Valve House	Stanislaus County
Canyon Portal Valve	Active	Valve House	Tuolumne County
House			
Cashman Creek Valve	Active	Valve House	Stanislaus County
House			
Cherry Valve House	Active	Valve House	Tuolumne County
Emery Road Crossover	Active	Valve House	Stanislaus County
Auxiliary Control			
Building			
Emery Road Crossover	Active	Valve House	Stanislaus County
Valve House			

	04.4	The second se	T 41
Asset	Status	Туре	Location
Granite Portal Valve	Active	Valve House	Tuolumne County
House			
Oakdale Portal Valve	Active	Valve House	Stanislaus County
Houses			
Pelican Crossover Valve	Active	Valve House	Stanislaus County
House			
Roselle Crossover Valve	Active	Valve House	Stanislaus County
House			
San Joaquin Valve	Active	Valve House	Stanislaus County
House			
Tesla Portal Valve	Active	Valve House	San Joaquin County
Houses			
West Portal Valve House	Active	Valve House	Tuolumne County
Cherry Compound	Active	Water treatment	Tuolumne County
Memcor			
Early Intake UV	Active	Water treatment	Tuolumne County
Treatment Plant			
Moccasin UV Treatment	Active	Water treatment	Tuolumne County
Plant			
O'Shaughnessy UV	Active	Water treatment	Tuolumne County
Treatment Plant			
Rock River Lime Plant	Active	Water treatment	Tuolumne County
Tesla Chlorination	Inactive	Water treatment	San Joaquin County
Building			

Notes:

HHWP = Hetch Hetchy Water and Power NPS = National Park Service USFS = United States Forest Service UV = ultraviolet

2024 State of the Regional Water System Report

Asset	Size (acres)	Location Bay Area	Purpose
Casey Quarry	1	San Mateo County	
Skyline Quarry	16	San Mateo County	Emergency Supply Stockpile and Staging
Donovan Quarry	66	Redwood City	Emergency Supply Stockpile

Table A-15: Buildings and Watersheds – Quarries

Table A-16: Buildings and Grounds - Corporation Yards

Asset	Size (acres)	Location
	Bay Area	
Millbrae Corporation Yard	10	Millbrae
Sunol Corporation Yard	25	Sunol
Rollins Facility	3	Burlingame
	Upcountry	
Moccasin	6	Moccasin
South Fork Maintenance Yard	1.5	Tuolumne County
Warnerville Yard	2	Oakdale
Oakdale Yard	NA	Oakdale

Table A-17: Rolling Stock

	Qua	antity
Asset	Bay Area	Upcountry
Passenger Cars	20	0
Light Duty Trucks, SUVs, Vans	217	118
Heavy Equipment	31	27
Trailer Equipment, Equipment on Trailers	60	63
Other Equipment – Boats	109	25
Medium and Heavy Duty Trucks	26	20

Appendix B: Emergency Response and Preparedness Plans

Listed below are the relevant ERPs that directly relate to RWS. Plans <u>not</u> listed below include state-level plans, county-level plans, and some division- or bureau-specific contingency plans.

	Draft/Revision	Last Exercised
Plan	Date	Last LACICISCA
Regional Water System Emergency Pipeline Repair Recovery and Readiness Program	2004	2015
City and County of San Francisco Emergency Response Plan	2017	2017
Risk Management Plan – California Accident Release Prevention Program for HTWTP	2017	Reviewed July 2018
Risk Management Plan – California Accident Release Prevention Program for Sunol Valley Water Treatment Plant	2021	2021
Risk Management Plan – California Accident Release Prevention Program for Sunol Valley Chloramination Facility	2023	2023
Spill Prevention, Control, and Countermeasure Plan – San Antonio Pump Station	2023	2023
Sunol Valley Chloramination Facility and Water Treatment Plant Hazardous Materials Business Plans	2024	2024
Water Quality Notifications and Communications Plan (Rev. 7)	2022	November 2021
Water Contamination and Response and Consequence Management Plan	2016	2012
Regional Water System Emergency Disinfection and Recovery Plan	2024	2016
SFPUC EOPs	Overall EOP - 2012 WSTD DEOP - 2013 WQD DEOP - 2016 NRLMD DEOP and FOG - 2014 HHWP DEOP - 2013 CDD DEOP - 2013	WE portion (all divisions) – June 2017 HHWP portion – August 2018 CDD portion – February 2017 WSTD portion – October 2019 WQD portion – April 2016 NRLMD portion – June 2019

 Table B-1: Relevant Emergency Response Plans for the Regional Water System

Appendix B - Emergency Response and Preparedness Plans

2024 State of the Regional Water System Report

Plan	Draft/Revision Date	Last Exercised
SFPUC Continuity of Operations Plan	June 2019	March 2020
Mountain Tunnel Emergency Restoration Plan	2014	March 2017
Emergency Action Plans - DSOD Jurisdictional Bay Area Dams	2017	Turner Dam: May 3, 2017 Calaveras Dam – September 20, 2018
Emergency Action Plans – DSOD Jurisdictional Upcountry Dams	2022	O'Shaughnessy Dam – August 26, 2022 Cherry Valley Dam – August 26, 2022 Lake Eleanor – May 15, 2022 Priest Dam – March 11, 2022 Moccasin Dam – January 12, 2022
Water Quality Division EOP and supplemental Field Operations Guide	2016	2016
Moccasin Overflow Emergency Response Plan – Moccasin Wastewater Treatment Plant	2016 Reviewed March 2018	2018
America's Water Infrastructure Act Drinking Water Utility Risk and Resilience Assessment	2020	N/A
America's Water Infrastructure Act Drinking Water Utility Emergency Response Plan	2020	N/A

Notes:

CDD = City Distribution Division DEOP = Division Emergency Operations Plan DSOD = Division of Safety of Dams EOP = Emergency Operations Plan HHWP = Hetch Hetchy Water and Power HTWTP = Harry Tracy Water Treatment Plant NRLMD = Natural Resources and Lands Management Division SFPUC = San Francisco Public Utilities Commission WE = Water Enterprise WQD = Water Quality Division WSTD = Water Supply and Treatment Division

Draft/Revision Last Plan Date Exercised Risk Management Plan - California Accident Release 2021 2021 Prevention Program for Harry Tracy Water Treatment Plant Risk Management Plan - California Accident Release 2023 2023 Prevention Program for Sunol Valley Water Treatment Plant Risk Management Plan - California Accident Release 2023 2023 Prevention Program for Sunol Valley Chloramination Facility/San Antonio Pump Station Emergency Response Plan - Moccasin Powerhouse and 2023 2023 Switchyard Emergency Response Plan - Moccasin Wastewater Treatment 2024 updates in 2004 Plant and Water Tanks progress Emergency Response Plan - Early Intake 2023 In progress Emergency Response Plan - Rock River Lime Treatment Plant 2023 In progress Emergency Response Plan - Holm Powerhouse, Kirkwood 2023 In progress Powerhouse, Early Intake Switchyard, and Fuel Area Emergency Response Plan - Warnerville Maintenance Yard 2023 In progress Emergency Response Plan - Moccasin Maintenance Yard 2023 2023 Hazardous Communication Program for Hazardous 2024 2023 Substances and Pesticides Fire Prevention Plan - Holm Powerhouse 2023 In progress Fire Prevention Plan - Moccasin and Early Intake 2023 Moccasin (2023) Early Intake (In progress) Fire Prevention Plan - Kirkwood Powerhouse, Early Intake 2023 In progress Switchyard, and Fuel Area Sewer System Management Plan - Moccasin 2024 in progress 2024 Spill Prevention, Control, and Countermeasure Plan -2024 2024 Moccasin Spill Prevention, Control, and Countermeasure Plan – South 2024 2024 Fork Maintenance Yard Spill Prevention, Control, and Countermeasure Plan -2024 2024 O'Shaughnessy Dam Maintenance Yard

Table B-2: Relevant Plans for the Unified Program

Appendix B – Emergency Response and Preparedness Plans

2024 State of the Regional Water System Report

	Draft/Revision	Last
Plan	Date	Exercised
Spill Prevention, Control, and Countermeasure Plan – Cherry Maintenance Yard	2024	2024
Spill Prevention, Control, and Countermeasure Plan – Warnerville Maintenance Yard and Switchyard	2024	2024
Spill Prevention, Control, and Countermeasure Plan – Baden Pump Station	2024	2024
Spill Prevention, Control, and Countermeasure Plan – Harry Tracy Water Treatment Plant	2023	2023
Spill Prevention, Control, and Countermeasure Plan – San Antonio Pump Station/Sunol Valley Chloramination Facility	2023	2023
Spill Prevention, Control, and Countermeasure Plan – Santa Clara Valley Intertie Pump Station	2023	2023
Spill Prevention, Control, and Countermeasure Plan – Sunol Valley Water Treatment Plant	2022	2022
Spill Prevention, Control, and Countermeasure Plan – Tesla Treatment Facility	2023	2023
Spill Prevention, Control, and Countermeasure Plan – Millbrae Yard	2022	2022
Spill Prevention, Control, and Countermeasure Plan – Sunol Corp Yard	2023	2023
Spill Prevention, Control, and Countermeasure Plan – Crystal Springs Substation Pump Station	2023	2023
Hazardous Material Business Plan – Rock River Lime Plant	2024	2024
Hazardous Material Business Plan – South Fork Maintenance Yard	2024	2024
Hazardous Material Business Plan – Cherry Valley Compound	2024	2024
Hazardous Material Business Plan - O'Shaughnessy	2024	2024
Hazardous Material Business Plan – Early Intake	2024	2024
Hazardous Material Business Plan - Moccasin	2024	2024
Hazardous Material Business Plan -Warnerville	2024	2024
Hazardous Material Business Plan – Harry Tracy Water Treatment Plant	2024	2024
Hazardous Material Business Plan – Millbrae Maintenance Yard	2024	2024

Appendix B – Emergency Response and Preparedness Plans

2024 State of the Regional Water System Report

Disc	Draft/Revision	Last
Plan	Date	Exercised
Hazardous Material Business Plan – Baden Pump Station	2024	2024
Hazardous Material Business Plan - Crystal Springs Pump Station	2024	2024
Hazardous Material Business Plan – Pulgas Dechloramination Facility and Pump Station	2024	2024
Hazardous Material Business Plan – Polhemus Fluoride Station	2024	2024
Hazardous Material Business Plan – Tesla Treatment Facility	2024	2024
Hazardous Material Business Plan – San Antonio Oxygenation Facility	2024	2024
Hazardous Material Business Plan – Sunol Valley Chloramination Facility/San Antonio Pump Station	2024	2024
Hazardous Material Business Plan – Sunol Valley Water Treatment Plant	2024	2024
Hazardous Material Business Plan - Casey Quarry	2024	2024
Hazardous Material Business Plan – Crystal Springs Bypass Tunnel and Shaft	2024	2024
Hazardous Material Business Plan – SFPUC-Valley Water Intertie Pump Station	2024	2024
Hazardous Material Business Plan – Thomas Shaft Facility	2024	2024
Hazardous Material Business Plan - Sunol Corporation Yard	2024	2024
Hazardous Material Business Plan – Calaveras Oxygenation Facility	2024	2024
Hazardous Material Business Plan – Bear Gulch Crossover Facility	2024	2024
Hazardous Material Business Plan – Mt. Alviso Valve Lot	2024	2024
Hazardous Material Business Plan - Calaveras Valve Lot	2024	2024
Hazardous Material Business Plan – Guadalupe Crossover	2024	2024
Hazardous Material Business Plan – Palo Alto (Barron) Valve Lot	2024	2024
Hazardous Material Business Plan - Newark Control Building	2024	2024
Hazardous Material Business Plan – Irvington Portal	2024	2024
Hazardous Material Business Plan – San Pedro Valve Lot	2024	2024

Appendix B – Emergency Response and Preparedness Plans

2024 State of the Regional Water System Report

Plan	Draft/Revision Date	Last Exercised
Hazardous Material Business Plan – Ravenswood Control Building	2024	2024
Hazardous Material Business Plan - Alameda East Portal	2024	2024
Hazardous Material Business Plan – Alameda West Portal	2024	2024
Hazardous Material Business Plan – F Street Well and Treatment Facility	2024	2024
Hazardous Material Business Plan - Millbrae Yard Well and Treatment Facility	2024	2024
Hazardous Material Business Plan - Sunol Fire Pump Station	2024	2024
Hazardous Material Business Plan – Alameda Creek Diversion Dam Fish Passage Facility	2024	2024
Hazardous Material Business Plan – Pulgas Valve Lot	2024	2024
Hazardous Material Business Plan – Sawyer Ridge Radio Station	2024	2024
Hazardous Material Business Plan – Crystal Springs Pump Station Substation	2024	2024

Notes:

SFPUC = San Francisco Public Utilities Commission

Appendix C: Pipeline Inspection Schedule

									INSPECTION PRIORITY SCORE							
		_					_		0.375 0.15 0.15 0.15 0.05 0.05 0.075				1.00			
Piveline	Section		Date Next	3.411	T	Matl.	Year Built	D '.	3.6.1	Pop. Dens		Dia.	Pipeline PSI	Pipeline=5 Adit=4 Tunnel=1	Redun- dancv	SCORE TOTAL
San Antonio Reservoir	Intake Structure	Inspection	Inspection	Miles	Туре	Iviati.	Built	Dia.	Matl.	ity	Age	D1a.	P51	Tunnel=1	dancy	SCORE IOTAL
	Control House to Y20		7/1/2024	0.27	Adit	Steel	1967	42	1	1	2.7	0.6		4	1	12.95
Hillsborough Tunnel and	Control House to 120		7/1/2024	0.27	Tunnel/	Steel	1955-	42	1	1	2.7	0.0		4	1	12.95
Sunset Supply Pipeline	M20 to M30		10/1/2024	2.35	Pipeline	Steel	1958	78-90	1	5	3.1	3.5	2.5	5	1	25.65
	11120 10 11100		10/1/2021	2.00	Tipellite	oteer	1954-		-	-	0.1	0.0	2.0		-	20100
Sunset Supply Pipeline	M30 to M50		10/1/2024	7.28	Pipeline	Steel	1958	60	1	5	3.1	2	2.9	5	1	23.60
					1		1954-									
Sunset Supply Pipeline	M10 to M20		10/1/2024	1.35	Pipeline	Steel	1958	78-90	1	2	3.1	4.5	1.5	5	1	22.15
	84-inch-UVE-001 and															
(Annual Trash Screen	144-inch-UVE-001 to															
Inspection)	003		1/1/2025	0.13	Pipeline	Steel	2011	84-144								
		11/1/1999														
		and	1 (1 (2025	0.11	D: 1:	C , 1	1954-	60		_	0.1		A (_	-	
Sunset Supply Pipeline	M50 to M60	2/1/2024	1/1/2025	3.41	Pipeline	Steel	1958 1954-	60	1	5	3.1	2	2.6	5	1	
Sunset Supply Pipeline	M60 to CDD	2/1/2024	1/1/2025	1.95	Pipeline	Steel	1954- 1958	60	1	5	3.1	2	2.7	5	1	23.50
Crystal Springs Pipeline																
No. 1	L60 to CDD		4/1/2025	3.86	Pipeline	Steel	1956	44	1	4	3	0.7	3	5	1	20.05
Crystal Springs Pipeline		10/12/201								_				_		
No. 2 (CIP)	K40 to K50	6	9/1/2025	3.86	Pipeline	Steel	1937	54-60	1	5	3.7	2	2.9	5	1	
		5/16/2019 and														
Bay Division Pipeline No. 3 (Railroad Sliplining) –		and $10/16/202$														
Warranty Inspection	C26 to C30	10/10/202	10/1/2025		Pipeline	Steel	1952	72-78	1	5	3.2	3.5	3.6	5	1	
	C40 and D40 to C50	5	10/1/2025		1 ipenite	Siter	1752	72-70	1	5	5.2	5.5	5.0	5	1	
Stanford Tunnel	and D50		1/1/2026	0.33	Tunnel	Steel	1952	90	1	3	3.2	4.6		1	5	24.20
Bay Division Pipeline No. 1			, ,						1	-					-	
(CIP)	A60 to A70	10/1/2001	4/1/2026	3.97	Pipeline	Steel	1933	60	2	5	3.8	2	3.9	5	1	
Bay Division Pipeline No. 4		6/1/1996													1	
(Railroad Sliplining) -		and					1965-									
Warranty Inspection	D26 to D30	1/1/2024			Pipeline	Steel	1973	84-96	1	5	2.7	5	3.7	5	1	
Balancing Reservoir Pipeline	All	10/1/2005	4/1/2026	0.21	Pipeline	РССР	1975	96	5	1	2.4	5	0.1	5	1	
							1927-									
San Andreas Pipeline No. 2	R20 to R50		7/1/2026	1.15	Pipeline	Lock-bar/Steel	1928	54	2	5	4	1.6	5	5	1	29.15
San Andreas Pipeline No. 2	R60 to CDD		7/1/2026	1.70	Pipeline	Lock-bar/Steel	1927- 1928	54	2	5	4	1.6	3.7	5	1	28.50

Appendix C – 20-Year Pipeline Inspection Schedule 2024 State of the Regional Water System Report

									INSPECTION PRIORITY SCORE											
									0.375	0.15	0.15	0.075	1.00							
										Pop.				Pipeline=5						
		Date Last	Date Next				Year			Dens			Pipeline	Adit=4	Redun-					
Pipeline	Section	Inspection	Inspection	Miles	Type	Matl.	Built	Dia.	Matl.	ity	Age	Dia.	PSI	Tunnel=1	dancy	SCORE TOTAL				
Bay Division Pipeline No. 2																				
(CIP)	B50U to B60	7/1/2015	7/1/2026	4.92	Pipeline	Steel	1935	66	1	5	3.8	2.5	4.1	5	1					
Bay Division Pipeline No. 2																				
(CIP)	B60 to B70	1/29/2020		3.97	Pipeline	Steel	1935	66	1	5	3.8	2.5	3.9	5	1					
San Antonio Pipeline	W20 to Y20	8/4/2016	9/1/2026	2.07	Pipeline	PCCP	1967	60	5	1	2.7	2	0.9	5	1					
		10/13/201																		
Alameda Siphon 3	X20 to X22 and X25	6	10/1/2026	0.55	Siphon	PCCP	1967	96	5	1	2.7	5	0.5	5	1					
San Andreas Pipeline No. 3	T50 to T60	3/1/1997	4/1/2027	3.38	Pipeline	Steel	1997	54-60	1	5	2.2	2	4.9	5	1					
San Andreas Raw Water																				
Pipeline No. 2	N25 to R12	5/1/1994	4/1/2027	0.16	Adit	Steel	2010	72	1	5	1.2	3		4	1					
San Andreas Raw Water																				
Pipeline No. 3	N35 to N51	5/1/1994	4/1/2027	0.58	Adit	Steel	2010	72	1	5	1.2	3		4	1					
Bay Division Pipeline No. 4							1965-													
(CIP)	D26 to D40	6/1/1996	8/1/2027	12.00	Pipeline	Steel	1973	84-96	1	5	2.7	5	3.7	5	1					
Bay Division Pipeline No. 4																				
(CIP)	D50 to D68	5/19/2017	10/1/2027	7.86	Pipeline	PCCP	1967	84-96	5	5	2.7	5	3	5	1					
Calaveras Pipeline	V34 to SVWTP		10/1/2027	3.96	Pipeline	Steel	1992	44	1	1	1.8	0.7	4.3	5	1	14.40				
Crystal Springs Pipeline		11/16/201																		
No. 3	L30 to L41K	7	1/1/2028	3.61	Pipeline	PCCP	1971	60	5	5	2.5	2	2.9	5	1					
Crystal Springs Pipeline		11/16/201																		
No. 3	P48 to L59K	7	1/1/2028	2.54	Pipeline	PCCP	1987	60	5	5	2	2	2.9	5	1					
San Mateo Creek Dam					Tunnel/															
Pipeline and Tunnel 2	All	9/1/2009	1/1/2028	1.61	Pipeline	Steel	1937	48	1	1	3.7	1.1		1	1					
Crystal Springs Bypass																				
Tunnel (Inspect Every																				
10 Years)	G20 to G32 and G34	1/1/2011	4/1/2028	3.12	Tunnel	Steel	1970	114	1	4	2.6	5		1	5					
	Water Temple to A70, B70, C70, D68 and																			
Pulgas Tunnel	E70		4/1/2028	2.24	Tunnel	Steel	1967	123	1	2	2.7	5		1	5	22.55				
Bay Division Pipeline No. 3												1								
(CIP)	C20 to C26	3/1/2010	6/1/2028	8.96	Pipeline	Steel	1952	72-78	1	5	3.2	3.5	4.1	5	1					
Bay Division Pipeline No. 3												1								
(CIP)	C26 to C40	5/16/2019	6/1/2028	8.19	Pipeline	Steel	1952	72-78	1	5	3.2	3.5	3.6	5	1					
Crystal Springs Bypass																				
Pipeline	G34 to G41	6/28/2018	7/1/2028	0.81	Pipeline	PCCP	1970	96	5	2	2.6	5	1.5	5	1					
Crystal Springs Pipeline																				
No. 2	K50 to K70		10/1/2028	6.22	Pipeline	Steel	1937	60	1	5	3.7	2	3	5	1	24.55				
Crystal Springs Pipeline							1937/195					1								
No. 2	K60 to CDD	8/1/2002	10/1/2028	3.68	Pipeline	Steel	6	60	1	5	3.7	2	3	5	1					
Bay Division Pipeline No. 3	C50 to C70		1/1/2029	7.84	Pipeline	RCP	1952	72-78	1	5	3.2	3.5	3	5	1	26.05				

Appendix C – 20-Year Pipeline Inspection Schedule 2024 State of the Regional Water System Report

	INSPECTION PRIORITY SCORE														CORE	
									0.375	0.15	0.15	0.15	0.05	0.05	0.075	1.00
										Pop.				Pipeline=5		
		Date Last	Date Next				Year			Dens			Pipeline	Adit=4	Redun-	
Pipeline	Section	Inspection	Inspection	Miles	Type	Matl.	Built	Dia.	Matl.	ity	Age	Dia.	PSI	Tunnel=1	dancy	SCORE TOTAL
Crystal Springs Outlet					Outlet											
Tunnel 1	H12 to H87	7/1/2005	7/1/2029	0.10	Tunnel	Steel	1891	44	1	1	5	0.7		4	1	
Crystal Springs Outlet					Outlet											
Tunnel 2	H23 to H82	7/1/2005	7/1/2029	0.13	Tunnel	Steel	1931	54	1	1	3.9	1.6		4	1	
Crystal Springs Pipeline																
No. 2	K20 to K40	12/1/2006		5.30	Pipeline	Steel	1937	54-60	1	5	3.7	2	2.9	5	1	
Bay Division Pipeline No. 3	C10 to C20	3/1/2007	10/1/2030	8.55	Pipeline	RCP	1952	72-78	1	5	3.2	3.5	4	5	1	
							1954-			_		_		_		
Sunset Supply Pipeline	M40 to M50	11/1/2007		3.66	Pipeline	Steel	1958	60	1	5	3.1	2	2.8	5	1	
Bay Division Pipeline No. 1	A50U to A60	3/1/2009	7/1/2031	4.92	Pipeline	Steel	1933	60	1	5	3.8	2	4.1	5	1	
		10/1/0000	E /1 /0000	0.04	D: 1	C , 1	1965-	01.01		_		_		_		
Bay Division Pipeline No. 4	D20 to D30	12/1/2009		8.96	Pipeline	Steel	1973	84-96	1	5	2.7	5	4.1	5	1	
Bay Division Pipeline No. 3	C20 to C30	3/1/2010	4/1/2033	8.96	Pipeline	Steel	1952	72-78	1	5	3.2	3.5	4.1	5	1	
	D50 / D/0	(11 12010	= (1 (2000		D: 1	T 1 1 (0, 1	1927-	- 1	-	_			4.0	_		
San Andreas Pipeline No. 2	R50 to R60	6/1/2010	7/1/2033	3.38	Pipeline	Lock-bar/Steel	1928	54	2	5	4	1.6	4.9	5	1	
Alameda Siphon 1	X30 to X35	10/1/2010		0.56	Siphon	RCP	1933	69	1	1	3.8	2.8	0.5	5	1	
Bay Division Pipeline No. 2	A10 to A20	10/1/2010	10/1/2033	7.12	Pipeline	RCP and Steel	1935	66	1	5	3.8	2.5	4.1	5	1	
		3/1/2011														
		and 8/1/2015														
		8/1/2015 and														
Bay Division Pipeline No. 1	B10 to B20		10/1/2033	7.11	Pipeline	RCP and Steel	1933	60	2	5	3.8	2	4.1	5	1	
Bay Division Pipeline No. 4	D10 t0 D20	1/1/2013	10/1/2033	7.11	Tipenne	KCI allu Steel	1933	00	2	5	3.8	2	4.1	5	1	
(PCCP 10-Year Recurring		and														
Inspection)	D10 to D20	3/6/2023	1/1/2034	8.52	Pipeline	PCCP	1967	96	5	5	2.7	5	4	5	1	
New Crystal Springs Bypass	D10 t0 D20	5/ 6/ 2025	1/1/2004	0.52	ripenne	reer	1707	70	5	5	2.7	5	Ŧ	5	1	
Tunnel	G32 to G36		4/1/2034	0.80	Tunnel	Steel	2012	96	1	2	1.1	5	1.5	1	1	
Alameda Siphon 4	All		1/1/2035	0.54	Siphon	Steel	2013	66	1	1	1.1	2.5	0.5	5	1	
San Andreas Pipeline No. 3	T60 to CDD		1/1/2035	1.94	Pipeline	Steel	2012	36	1	5	1.1	0.1	3.7	5	1	
Bay Division Pipeline No. 5	E60 to E70		4/1/2035	4.00	Pipeline	Steel	2012	60	1	5	1.1	2	3.9	5	1	
	E50U to Redwood		-, -, -, -000	1.00	- 17 01110	01001	-010		-			-	0.5	, , , , , , , , , , , , , , , , , , ,	-	
Bay Division Pipeline No. 5	City Valve Lot		7/1/2035	4.93	Pipeline	Steel	2013	60	1	5	1.1	2	4.1	5	1	
,	New Irvington		, , =====						-			-		-	-	
	Tunnel to Newark															
Bay Division Pipeline No. 5	Valve Lot		10/1/2035	7.01	Pipeline	Steel	2013	72	1	5	1.1	3	4.1	5	1	
San Antonio Backup Pipeline	All		1/1/2036	1.32	Pipeline	Steel	2013	66	1	1	1	2.5	0.4	5	1	
Balancing Reservoir Pipeline	All		4/1/2036	0.21	Pipeline	PCCP	1975	96	5	1	2.4	5	0.1	5	1	
Sunset Branch	N42 to M41	10/1/2013		1.11	Pipeline	Steel	1954	61	1	5	3.1	2.1	2.7	5	1	
Crystal Springs Pipeline		. ,										İ				
No. 2	K10 to K20	5/21/2014	1/1/2037	2.36	Pipeline	Steel	1937	54-60	1	3	3.7	2	2.3	5	1	

Appendix C – 20-Year Pipeline Inspection Schedule 2024 State of the Regional Water System Report

								INSPECTION PRIORITY SCORE												
									0.375 0.15 0.15 0.15 0.05 0.05 0.075 1.											
										Pop.				Pipeline=5						
		Date Last	Date Next				Year			Dens			Pipeline	Âdit=4	Redun-					
Pipeline	Section	Inspection	Inspection	Miles	Type	Matl.	Built	Dia.	Matl.	ity	Age	Dia.	PSI	Tunnel=1	dancy	SCORE TOTAL				
Crystal Springs San Andreas					Force															
Force Main	H83 to San Andreas		4/1/2037	4.50	Main	Steel	2015	60	1	2	1	2		5	1					
Bay Division Pipeline No. 4	D50 to D68		10/1/2037	7.86	Pipeline	PCCP	1967	84-96	5	5	2.7	5	3	5	1					
Irvington Tunnel 1	All	4/4/2015	10/1/2037	3.48	Tunnel	Steel	1933	126	1	2	3.8	5		1	1					
Crystal Springs Bypass																				
Tunnel (Inspect Every																				
10 Years)	G20 to G32 and G34	1/1/2011	4/1/2038	3.12	Tunnel	Steel	1970	114	1	4	2.6	5		1	5					
Sunol Valley Water																				
Treatment Plant 78-Inch											_		_							
Effluent Pipeline	All	9/1/2015	/ /	1.59	Pipeline	Steel	1966	78	1	1	2.7	3.5	0.7	5	1					
Calaveras Pipeline	SVWTP to W10	9/1/2015	4/1/2038	1.63	Pipeline	Steel	1966	66	2	1	2.7	2.5		5	1					
San Antonio Pipeline	W20 to Y20		7/1/2038	2.07	Pipeline	PCCP	1967	60	5	1	2.7	2	0.9	5	1					
Alameda Siphon 3	X20 to X22 and X25		7/1/2038	0.55	Siphon	PCCP	1967	96	5	1	2.7	5	0.5	5	1					
Pilarcitos Tunnel 1 and																				
200 Feet of 33-Inch Concrete		- (- (10/0	3'6" by	-		_	_								
Pipeline	S10 to S13		10/1/2039	0.29	Tunnel	Brick	1868	5'1"	2	1	5	5		1	1					
	E20U to E50U, B50U					.		100	_		_	_			_					
Bay Tunnel	and A50U	6	4/1/2040	5.14	Tunnel	Steel	2015	108	1	1	1	5		1	5					
Calaveras Outlet Pipe	Outlet Tower to V34	5/9/2017	7/1/2040	0.28	Adit	Steel	2016	72-78	1	1	1	3		4	1					
	Upper Alameda							=/ / 1</td <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>												
Upper Alameda Creek	Creek to Calaveras	1/1/ /0010	7/1/2040	1.05	т 1		1931	5'6" by 6'6'"	1	1	2.0	-		1	1					
Tunnel	Reservoir	1/16/2018	7/1/2040	1.85	Tunnel	Concrete	1931	66	1	1	3.9	5		1	1					
Crystal Springs Pipeline	1 20 to 1 41V	11/16/201	10/1/2040	2 (1	D:1:	PCCP	1071	(0	5	5	2.5	2	2.9	5	1					
No. 3	L30 to L41K	7 11/16/201	10/1/2040	3.61	Pipeline	FCCF	1971	60	5	5	2.5	2	2.9	5	1					
Crystal Springs Pipeline No. 3	P48 to L59K	11/16/201	10/1/2040	2.54	Pipeline	PCCP	1987	60	5	5	2	2	2.9	5	1					
Crystal Springs Bypass	F40 10 L39K	/	10/1/2040	2.34	ripeine	rttr	1967	60	5	5	2	2	2.9	5	1					
Pipeline	G34 to G41		1/1/2041	0.81	Pipeline	PCCP	1970	96	5	2	2.6	5	1.5	5	1					
Bay Division Pipeline Nos. 3	0.10041		1/1/2041	0.01	ripenne	i CCi	1770	,0	5	~	∠.0	5	1.5	5	1					
and 4 Crossover Pipelines	I-680	5/30/2018	1/1/2041	0.41	Pipeline	Steel	2014	78	1	5	1.1	3.5	2.5	5	1					
	1-000	12/14/201	1/1/2041	0.11	ripemie	Jitti	2014	70	1	5	1.1	5.5	2.5	5	1					
San Andreas Pipeline No. 1	P10 to Baden	12/14/201	4/1/2041	4.41	Pipeline	Steel	1898	44	2	5	5	0.7	2.9	5	1					
	1 to to butch	Ŭ	1/1/2011	1,11	1 ipenite	51001	1927-		-	<u> </u>	5	0.7	2.7	Ŭ	-					
San Andreas Pipeline No. 2	R12 to R20	3/27/2019	10/1/2041	2.17	Pipeline	Lock-bar/Steel	1928	54	2	5	4	1.6	5	5	1					
Bay Division Pipeline No. 3	C30 to C40	5/16/2019		8.19	Pipeline	Steel	1920	72-78	1	5	3.2	3.5	3.6	5	1					
Irvington Tunnel 2	All	2/13/2020		3.59	Tunnel	Steel	2015	102	1	2	1	5		1	1					
San Andreas Pipeline No. 2		,,	, _, _,						-	_	-	-		-	-					
(Warranty Inspection)	R12 to R20	10/1/2022	10/1/2042	2.17	Pipeline	Lock-bar/Steel	2020	54	2	5	0	1.6	5	5	1					
Alameda Siphon 2	X10 to X15	5/25/2023		0.55	Siphon	Steel	1953	90	1	1	3.1	4.5	0.5	5	1					
Palo Alto Pipeline	F6 to F60		5/1/2044	5.36	Pipeline	Steel	1938	36	1	5	3.7	0.1	3.6	5	5	25.00				

Appendix C - 20-Year Pipeline Inspection Schedule

2024 State of the Regional Water System Report

	INSPECTION PRIORITY SCORE														
	0.375	0.15	0.15	0.15	0.05	0.05	0.075	1.00							
Pipeline	Section	Date Next Inspection		Type	Matl.	Year Built	Dia.	Matl.	Pop. Dens itv	Age	Dia.	Pipeline PSI		Redun-	SCORE TOTAL
Bay Division Pipeline No. 4 (Railroad Sliplining) – Milpitas	D20 to D24	5/1/2044	3.87	Pipeline	Steel	1965- 1973	90								

Notes:

CDD = City Distribution Division

CIP = Capital Improvement Program

PCCP = prestressed concrete cylinder pipe

PSI = pounds per square inch

RCP = reinforced concrete cylinder pipe SVWTP = Sunol Valley Water Treatment Plant

Appendix D: Watershed Map

